




**JANUARY 1949**

Drilling bench faces in power tunnel at Safety Mountain Dam, Ouachita River, Arkansas—page 12.

25 Cents a Copy

\$2.00 per year

# OHIO GRAVEL CO. likes TELSMITH *Complete plant service*



Walter J. Flach, Vice Pres.  
Ohio Gravel Co.

● One of the largest and most successful operators in the United States, the Ohio Gravel Co., Cincinnati, Ohio, has six large plants serving southern Ohio, Indiana and Kentucky. All are in the Cincinnati area—at Clevel-

Miami, Miamiville, Newtown, Red Bank... and the latest all-Telsmith plant at Camp Dennison. The latter is designed for a large output of 100% crushed chips.


Company management is in the capable hands of Fred W. Cornuelle, President; and Walter J. Flach, Vice-President, who is in charge of plant operations and new plant construction.

Heretofore Mr. Flach has designed the plants himself, personally selected all equipment, and purchased it from several leading machinery makers. This new plant is an exception. Mr. Flach decided to try a complete gravel plant service... and chose Telsmith. He is very pleased with results.

Mr. Flach gave his ideas and his preliminary layouts to Telsmith engineers. After analyzing his requirements, Telsmith submitted preliminary drawings with equipment recommendations, secured Mr. Flach's approval, then made detailed drawings for the complete plant. Telsmith equipment units were matched and balanced to assure a smooth-running plant.



Mr. Flach found that Telsmith Service relieved him of a great deal of technical detail. Installation was simpler, easier and faster. Telsmith Complete Plant Service means larger capacity, with a better product, at lower cost.

Telsmith's more than 40 years of engineering know-how are at your disposal. Consultation without cost. Send for Bulletin G-50.



Telsmith 13-B  
Gyratory  
Crusher

Telsmith 48"  
Fine Crushing  
Gyrasphere



One of the two  
Telsmith 4' x 12'  
Double Deck  
Vibro-King 2-  
Bearing Finishing  
Screens

G-15R

## TELSMITH Equipment in this plant

- 30" x 5'-6" Special Plate Feeder • 25" x 36" Roller Bearing Jaw Breaker • 30" x 179' Plant Belt Conveyor • 5' x 12' 2-Deck Pulsator 4-Bearing Scalping Screen • 13-B Gyratory Crusher • 48" Fine Crushing Gyrasphere • No. 8 Belt Elevator 76' cts. • Two 4' x 12' 2-Deck Vibro-King 2-Bearing Finishing Screens • Four 16" x 18" Squad Bin Gates • 24" x 279' Stockpiling Belt Conveyor with Tripper

## SMITH ENGINEERING WORKS, 4030 N. HOLTON STREET, MILWAUKEE 12, WISCONSIN

713 Commercial Trust Bldg. Philadelphia 2, Pa. Rish Equipment Co. Roanoke 7 & Richmond 10, Va. Charleston 22 & Clarksburg, W. Va. Brandeis M. & S. Co. Louisville 8, Ky. L. V. Fraley & Son St. Louis 12, Mo. W.C. Caye & Co. Atlanta 7, Ga.  
Interstate Equip. Co. Knoxville 8 and Nashville 6, Tenn. Priestner Machinery Co., Inc. Memphis 3, Tenn. Tractor & Eqt. Co., Inc. Birmingham 1, Ala. Southern Eqt. & Tractor Co. Monroeville, Pa.  
Alamo Iron Works, San Antonio 6, Texas Martin-Lumby Co., 1845 Plantation Road, Dallas 9, Texas Don Graze, Jacksonville 2, Fla.

# On jobs like this...

## NORTHWEST ADVANTAGES MEAN MONEY!

Here's rock—the kind of rock that really tests a shovel day in and day out. This is another *Key Machine* spot that calls for the best in equipment.

Your Northwest is built for the *Key Machine* spots. It's built to make money. Northwest brings you a combination of advantages found in no other Shovel, Crane, Dragline or Pullshovel... advantages that make it a real Rock Shovel—and when you have a real Rock Shovel you never have to worry about output in easy digging.

Profits begin in the *Key Machine* spots. You can't afford anything but the best at the heart of the job. Plan ahead now to have a Northwest Rock Shovel.

NORTHWEST ENGINEERING COMPANY  
135 South LaSalle Street, Chicago 3, Illinois

- Simplicity of design for easy maintenance.
  - Northwest Dual Independent Crowd utilizes force of other shovels waste.
  - "Feather-Touch" Clutch Control for easy operation.
  - Uniform Pressure Swing Clutches for cooler, smoother running.
  - Cushion Clutch reduces shock overloads on parts under power.
  - Cast Steel Machinery Side Frames assure alignment and reduce wear.
  - Alloy Cast Steel Bases for greater strength and rigidity.
  - All High-Speed Shafts on Ball or Roller Bearings assure minimum loss to friction.
- These and other Northwest advantages assure higher output and greater dependability in the Key Spots.*



## cal NORTHWEST sales agents

ALA. —BIRMINGHAM  
Tractor & Equip. Co.  
MONTGOMERY  
Ray-Brooks Machy. Co., Inc.  
FLA. —JACKSONVILLE  
Fla.-Ga. Tractor Co.  
TAMPA  
Fla.-Ga. Tractor Co.  
ORLANDO  
Fla.-Ga. Tractor Co.  
LAKE LAND  
Fla.-Ga. Tractor Co.  
MIAMI  
Fla.-Ga. Tractor Co.  
PENSACOLA  
Ray-Brooks Truck & Tractor Co.


TALLAHASSEE  
Fla.-Ga. Tractor Co.  
GA. —ATLANTA  
Tractor & Machy. Co., Inc.  
SAVANNAH  
Fla.-Ga. Tractor Co.  
LA. —MONROE  
Southern Equip. & Tractor Co.  
NEW ORLEANS  
Woodward Wright & Co.  
SHREVEPORT  
Construction Machy. Corp.  
MD. —BALTIMORE  
McClung-Lagan Equip. Co.  
MISS. —W. JACKSON  
Watkins-Aldridge Equip. Co.

N. C. —CHARLOTTE  
No. Car. Equip. Co.  
DULFORD  
No. Car. Equip. Co.  
RALEIGH  
No. Car. Equip. Co.  
ASHEVILLE  
No. Car. Equip. Co.  
WILMINGTON  
No. Car. Equip. Co.  
S. C. —COLUMBIA  
Brill-Lott Road Machy. Co.  
TENN. —CHATTANOOGA  
Nixon Machy. & Supply Co.  
NASHVILLE  
Nixon Machy. & Sup. Co., Inc.  
MEMPHIS  
Chertaw, Inc.  
VA. —RICHMOND  
Highway Machy. & Supply Co.  
HURFOLK  
Hampton Roads Tractor & Equipment Co.  
W. VA. —CHARLESTON  
W. Va. Tractor & Equip. Co.



# "QUICK-WAY" TRUCK SHOVELS

REG. U. S. PAT. OFF.



**Always  
DEPENDABLE**

Yes, "QUICK-WAYS" are dependable—and economical, quick and profitable to you. "QUICK-WAYS" accurate balance and strength with light weight permit higher travelling and working speeds, more yardage per day. Simplicity of design and quality steel construction give longer working life, lower operating and maintenance costs, lower initial cost and easier servicing. There's a "QUICK-WAY" owner near you, ask HIM.

**1** Wherever a truck can go, and at truck speed, that's where you can take a "QUICK-WAY." Low center of gravity and proper balance does it.

**2** Speed on the job moves more material per day at less cost—a "QUICK-WAY" gets around fast.

**3** First in the field and still the leader, "QUICK-WAYS" have gotten around more and longer than any other truck mounted power shovel.

**"QUICK-WAY" TRUCK SHOVEL CO., DENVER, COLO.**

Service available from our distributors strategically located throughout the United States and worldwide



Model E: 4/10 cu. yd. cap., for mounting on any standard 5-ton truck.

Model J: 1/4 cu. yd. cap., for mounting on any standard 1 1/2-ton truck.

**"QUICK-WAY"**

## "QUICK-WAY" TRUCK SHOVEL DISTRIBUTORS:

- BRANDEIS MACH. & SUPPLY CO.  
Louisville, Evansville
- FLORIDA-GEORGIA TRACTOR CO. OF  
WAYCROSS  
Savannah, Waycross
- FLORIDA-GEORGIA TRACTOR CO. OF  
JACKSONVILLE  
Jacksonville
- FLORIDA-GEORGIA TRACTOR CO. OF  
TAMPA  
Tampa, Lakeland, Orlando
- FLORIDA-GEORGIA TRACTOR CO. OF  
MIAMI  
Miami
- FLORIDA-GEORGIA TRACTOR CO. OF  
TALLAHASSEE  
Tallahassee, Florida
- HAMPTON RDS. TRACTOR & EQUIP. CO.  
Norfolk
- INDUSTRIAL TRACTOR & EQUIP. CO.  
Nashville
- NORTH CAROLINA EQUIPMENT CO.  
Raleigh, Charlotte, Asheville, Wilming-  
ton, Raleigh, Guilford
- FREE STATE EQUIPMENT CO.  
Baltimore, Md.
- POWER EQUIPMENT COMPANY  
Knoxville, Chattanooga
- RAY BROOKS MACHINERY CO.  
Montgomery
- RISH EQUIPMENT CO.  
Charleston, Cincinnati, Clarksburg, Rich-  
mond, Roanoke
- SOUTHERN EQUIPMENT SALES CO.  
Columbia
- TRI-STATE, INC.  
Atlanta, Macon
- TRI-STATE TRACTOR CO.  
Albany, Ga.



# Contents

**\$2,830,000,000 for Southern Contracts Last Year is All-Time Record in Peacetime—by Samuel A. Lauver** 10

## Southern Construction Projects

Industrial, Proposed Stage	13
Industrial, Contract Stage	42
Engineering, Proposed Stage	42
Engineering, Contract Stage	44
Highways and Bridges	44
Private Building, Proposed Stage	48
Private Building, Contract Stage	48
Public Building, Proposed Stage	49
Public Building, Contract Stage	50

**Breaking the Camel's Back** 19

**Construction Plant at Fort Gibson Dam** 25

**Carolinas A. G. C. Branch Holds Most Successful Convention** 28

**Galveston Engineer District Lets \$4,300,000 Contract for Benbrook Dam Job** 30

**Contractors Overtime Pay Problem Discussed** 31

**Two Tunnels Being Bored at Blakely Mountain Dam** 32

**Baytown Tunnel Is Part of \$9,000,000 Gulf Road Change** 34

**\$18,250,000,000 Construction Value Seen for 1949**  
—by J. W. Follin 35

**Little Rock Flood Control Project Protects Large Industrial Area and City Airport** 38

**Equipment at Work—by L. H. Houck** 40

**Equipment and Material Makers' News** 51, 52, 54

**American Road Builders to Meet Next Month at Washington** 55

**Letters—On Construction Costs** 56

**Advertisers' Index** 70

## LITTLEFORD

### PRESSURE DISTRIBUTOR



**cuts operating costs—heats faster—applies material more accurately**



**FULL CIRCULATING SPRAY BAR**—Littleford "Spray Master" Distributors have the Full Circulating Vacuum Flow Spray Bar up to 24 feet in width. This Spray Bar circulates by vacuum not pressure, therefore, insures full circulation through the bar without pressure on the nozzles. Spraying is done by pressure.

**ONE VALVE CONTROL**—one single valve controls all the operations of the "Spray Master." The valve turned to "Spray," the spraying is instant, the valve turned to "Circulate" and the spray stops with vapor like accuracy. Then too, the "Spray Master" single valve can be turned to "Fill" to fill its own tank or "Transfer" to transfer materials from one tank to another.

**FOR EFFICIENT SPRAYING**—for building or repairing highways, the "Spray Master" is a low cost, labor saving unit that will handle all bituminous materials. There's no lost motion, it heats faster, sprays accurately and efficiently. See your nearest . . .

#### DISTRIBUTOR

Banks-Miller Supply Co.,  
Huntington, W. Va.  
Bell-Lott Road Machinery Co.,  
West Columbia, S. C.  
Browning-Ferris Machinery Co.,  
Dallas and Houston, Tex.  
Chortlaw, Inc., Memphis, Tenn.  
J. D. Coggins Co., Albuquerque, N. M.  
Construction Machinery Co., Shreveport, La.  
E. F. Craven Co., Greenville, S. C.  
Fletcher Eqt. & Supply, New Orleans, La.  
J. W. Grass, Russell, Ga.  
Lowell Machinery Corp., Miami, Fla.  
John C. Louis Co., Inc., Baltimore, Md.  
H. D. Moody & Sons, Inc., Jacksonville, Fla.  
Plains Machinery Co.,  
Amarillo & Abilene, Tex.  
O. S. Stapley Co., Phoenix, Arizona  
Miller G. Williams Mch. Co.,  
Montgomery, Ala.  
Wilson Machinery & Supply,  
Lexington, Kentucky  
Wilson-Weesner-Wilkinson Co.,  
Nashville, Tenn.



405 E. Pearl St., Cincinnati 2, Ohio



VOL. 16 NO. 1

**JANUARY 1949**

**SAMUEL A. LAUVER**  
Managing Editor

**WM. E. McCORD**  
Advertising Manager

**L. H. HOUCK**, Correspondent  
12 Linden Drive,  
Jefferson City, Mo.

**PRICE — \$2.00 A YEAR**  
**25 CENTS PER COPY**

**PUBLISHED MONTHLY BY**  
**MANUFACTURERS RECORD PUBLISHING CO.**

109 Market Place  
BALTIMORE 3, MARYLAND

**PUBLISHERS OF**  
**MANUFACTURERS RECORD**  
**DAILY CONSTRUCTION BULLETIN**  
**BLUE BOOK OF SOUTHERN PROGRESS**

#### ADVERTISING OFFICES

**Norman J. Lett**  
20 E. Jackson Blvd.  
Chicago 4, Ill.  
Phone Harrison 7-5867  
**Orville Wright**  
109 Market Place,  
Baltimore 3, Md.  
Phone Lexington 7865

**F. O. Schroeder**  
301 Finance Bldg.,  
State Capitol,  
Richmond 19, Va.  
**Willie S. Drake**  
278 Sleepy Hollow Road  
Pittsburgh 16, Pa.  
Phone Lehigh 7867

**C. A. Zimmerman**  
227 Spenser Street,  
Glendale 2, Calif.  
**Warren T. Mayers**  
130 E. 61st Street,  
New York 21, N. Y.  
Phone Tompkins 6-6200

# These money-making

## ORLANDO, FLORIDA

Cutting this ditch for a curb line takes power and capacity. The sturdy No. 12 has both to spare.



## SANTA FE DAM, CALIF.

Grading a haul road for heavy trucks on top of the dam, the No. 12 leaves a smooth surface in rocky material.



## BALTIMORE, MARYLAND

Setting the pace for the paver, the No. 12 moves right along finishing final grade on the Philadelphia road.



## RAMSEY COUNTY, MINN.

Keeping good roads good — another chore for the No. 12, windrowing on oil mix for stabilizer base.



## BERTHOUD PASS, COLO.

8000 feet up! This new road requires fine, accurate finishing. The No. 12 "can do" within  $\frac{1}{4}$  inch.



# motor graders

ALL YEAR AROUND, on hundreds of construction and highway jobs, you'll see these husky one-man "Caterpillar" Diesel Motor Graders tackling a wide range of tasks. In scorching heat and bitter cold, they have the rugged stamina for heavy grading, as well as the accuracy for fine finishing. Designed and built entirely by one manufacturer, they're all "Caterpillar"—front axle to radiator cap. And they're sold and serviced by one reliable, well-equipped dealer. The advantage is all yours with these hard-working money makers in your line-up.

CATERPILLAR TRACTOR CO. • PEORIA, ILLINOIS

*sure get around!*



#### GRAND COULEE DAM, WASHINGTON

Relocating a highway calls for banksloping, ditching, grading. That's duck soup for the No. 12.



#### IDAHO FALLS, IDAHO

150 miles of Bonneville County road to keep clear. Equipped with V-type snow plow and wing, the No. 12 does the job.



#### CENTRAL VALLEY, TRACY, CALIF.

The versatile No. 12, besides maintaining haul roads, is also used for smoothing canal bed ahead of a Monaghan.



#### WASHINGTON COUNTY, COLORADO

A No. 12 widens and rebuilds as much as one mile of road a day.

# CATERPILLAR

REG. U. S. PAT. OFF.

# DIESEL

ENGINES • TRACTORS • MOTOR GRADERS  
EARTHMOVING EQUIPMENT

# Now! IT'S THE

# BD-3

A 4th DIESEL  
MOTOR GRADER JOINS  
THE ALLIS-CHALMERS LINE\*



**MOST POWERFUL MOTOR GRADER  
IN ITS CLASS**

**78 BRAKE HP. — 19,042 LBS.**

**2-Cycle GM Diesel Engine**

#### **A CONSTRUCTION MACHINE THROUGH AND THROUGH**

Handles every type of grading on road or street construction—builds ditches, cuts back-slopes, removes sod, shapes up and finishes surface . . . scarifies, mixes blacktop, plows snow.

#### **FAST, HIGHLY MANEUVERABLE**

- Six Forward Speeds — 2.21 to 15.58 m.p.h.  
... Three Reverse — 2.64 to 5.74 m.p.h.
- Travel speeds smoothly synchronized with operator controls . . . all the needed power applied as required.
- Easier to steer and maneuver on every type of job — shorter turning radius makes it ideal for narrow roads and streets.

#### **\*OTHER ALLIS-CHALMERS DIESEL-POWERED MOTOR GRADERS**

AD-4, 104 Brake hp. . . . 22,140 lbs.    AD-3, 78 Brake hp. . . . 21,835 lbs.  
BD-2, 50.5 Brake hp. . . . 17,772 lbs.





**COMPLETELY EQUIPPED** including electric starter and lights. Available with scarifier, cab and snowplow. Choice of 7:50, 9:00 or 13:00 front tires.

## **PATTERNED AFTER THE POPULAR MODEL AD MOTOR GRADER**

**STRONG** — exclusive tubular frame . . . absorbs shocks, protects control rods inside frame.

**ACCURATE** — cuts smoothly, blade held firmly on road through direct down pressure.

**HIGH CLEARANCE** — 28" throat clearance for handling bigger windrows without interference.

**"ROLL-AWAY" MOLDBOARD** — less power required to handle bigger windrows at faster speeds. Material is rolled, not pushed.

**FULL CIRCLE REVOLVING BLADE** — swings 360° . . . enables operator to grade either forward or reverse.

**FULL RANGE OF BLADE POSITIONS** . . . plus leaning front wheels, for handling all types of grading with ease.

# **ALLIS-CHALMERS**

TRACTOR DIVISION — MILWAUKEE 1, U. S. A.



\$124,407,000 total were up one hundred eighty-eight per cent; commercial building, total \$104,310,000, up sixty-three per cent, and office building, total \$44,170,000, up eleven per cent.

Public building has increased eighty per cent when compared with such work placed under contract last year. The \$629,349,000 included \$274,850,000 for buildings and hospitals and \$354,499,000 for schools. Industrial construction valued at \$587,971,000 last year showed a thirty-three per cent rise.

Engineering construction has risen over thirty per cent. The total for 1948 was \$410,325,000; for 1947, \$313,942,000. Most of the increase occurred in the fields of government electric projects and sewer and water work. Sewer and water work with its \$142,257,000 total was fifty-nine per cent ahead. Government electric work is now three times last year's volume.

Dams, drainage, and earthwork and airport work remained at practically the same level. The increase shown by the \$203,449,000 total of 1948 for such work was about two per cent higher than in the preceding year. The gain in highway construction value last year, when the total for the South was \$469,193,000, was eight per cent over the \$432,784,000 of 1947.

#### December Total \$325,736,000


December's \$325,736,000 embraced \$134,985,000 for industrial construction, \$64,724,000 for public building, \$62,000,000 for private building, \$35,834,000 for highway and bridge work and \$28,094,000 for heavy engineering and government electric projects. Industrial contract value was up due to the big pipeline work, while the rest of the construction picture showed losses.

The 1949 construction outlook for the country, in which the South participates proportionately, was forecast by Dwight W. Winkelman, president of the Associated General Contractors, at about the same level as that prevailing last year. There may be some drop in the high rate of industrial and public utility construction, he said, but this will probably be offset by an increase in public construction.


#### \$18,000,000,000 Next Year

The A. G. C. head estimated the country's new construction last year at \$18,000,000,000 to which he added \$6,000,000,000 for maintenance and repair operations. Unless there are serious upsets to our economy, he observed, there should be a large volume of construction

(Continued on page 68)



Above—Soybean oil extraction plant erected at Tiptonville, Tenn., by the West Tennessee Soya Mill, Earnest Rice, president. Process engineering was handled by Allis-Chalmers Manufacturing Co., Milwaukee, Wisc., which also supplied the equipment including machinery for bean preparation, oil extraction, solvent recovery and meal conditioning.



Above—The industrial building cost at the end of the year stood at 174, unchanged since the third quarter of 1948 and less than five and one-half per cent above the level of a year ago, it was announced by Austin President, George A. Bryant.

### SOUTH'S CONSTRUCTION BY STATES

	December, 1948	December, 1948	December, 1948	December, 1948
	Contracts Awarded	Contracts to be Awarded	Contracts Awarded Twelve Months 1948	Contracts Awarded Twelve Months 1947
Alabama .....	\$4,582,000	\$76,157,000	\$129,906,000	\$54,608,000
Arkansas .....	2,535,000	9,205,000	78,781,000	33,306,000
District of Columbia .....	7,944,000	6,605,000	46,530,000	42,367,000
Florida .....	19,472,000	18,175,000	271,387,000	227,468,000
Georgia .....	9,151,000	81,029,000	123,294,000	176,611,000
Kentucky .....	5,929,000	8,278,000	64,566,000	34,723,000
Louisiana .....	26,085,000	15,535,000	254,391,000	179,482,000
Maryland .....	12,114,000	68,575,000	203,656,000	169,043,000
Mississippi .....	10,984,000	27,821,000	80,974,000	66,451,000
Missouri .....	21,743,000	14,370,000	134,896,000	82,684,000
North Carolina .....	7,106,000	126,832,000	146,903,000	85,541,000
Oklahoma .....	27,430,000	17,693,000	122,420,000	43,654,000
South Carolina .....	26,237,000	5,817,000	106,724,000	61,736,000
Tennessee .....	21,820,000	66,090,000	150,343,000	54,235,000
Texas .....	162,946,000	261,706,000	730,656,000	551,637,000
Virginia .....	11,136,000	16,491,000	112,467,000	63,285,000
West Virginia .....	8,346,000	22,444,000	72,144,000	34,353,000
<b>TOTAL .....</b>	<b>\$325,637,000</b>	<b>\$840,825,000</b>	<b>\$2,830,038,000</b>	<b>\$1,984,184,000</b>

Below—Wise Contracting Co., Richmond, is proceeding on this \$425,000 addition to the First Baptist Church in the Virginia Capital. J. Binford Walford and O. Pendleton Wright, also of Richmond, are the architects.



# New UNIT 1520

## Self-Propelled RUBBER-TIRED CRANE



## 15 TON CAPACITY

This 50,000 pound Mobile Crane is a completely new member of the UNIT Crane and Shovel line. Designed for both "on and off" highway operation. So compact, it works efficiently even in small, cramped quarters, "in or out" of the yard.

- Rugged . . . Perfectly Balanced
- Hook Roller Construction
- Controlled and Operated by ONE Man
- Powered by ONE Engine
- Hydraulic Steering . . . Air Brakes and 4 Speed Air-Actuated Transmission
- Heavy Duty, yet operated with remarkable SPEED . . . SAFETY . . . ACCURACY . . . ECONOMY!

**UNIT CRANE & SHOVEL CORP.**

6303 W. BURNHAM STREET  
MILWAUKEE 14, WISCONSIN, U. S. A.


**COMPLETELY CONVERTIBLE . . .**




SHOVEL



DRAG



CLAM



HOE



CRANE



MAGNET

**. . . TO ALL ATTACHMENTS**

**REMOVABLE BUMPERS**



Both the UNIT 1520 and 357 Mobile Crane are equipped with removable bumpers.



**UNIT 357  
MOBILE CRANE**

WITH SHOVEL ATTACHMENT

• Self-Propelled • Rides on Rubber • Has 1001 Uses

Greater digging efficiency is attained in excavating by removal of one bumper. Permits additional space to lower boom, thus increasing digging depth in trenching or other excavating jobs. Provides close-range operation on shovel work. Bumper is bolted to undercarriage frame and its removal is a simple operation.

You can tell it's a UNIT by the FULL VISION CAB. There's no other cab like it.



SHOVELS • DRAGLINES • CLAMSHELLS • CRANES • TRENCHERS • MAGNETS





Above—Robert E. McKee, of Dallas, submitted the \$18,317,000 low bid for the Houston, Texas veterans' hospital pictured above, with Westinghouse Electric Corp., elevator division, the low bidder at \$470,380 for elevators and dumbwaiters and Chicago Bridge & Iron Co., low at \$95,100 for the elevated water storage tank. The project is to be carried out on a 200-acre site near the naval hospital and southeast of the \$100,000,000 Texas Medical Center. It involves 23 buildings and will provide 1,089 beds for general hospitalization and rehabilitation of war veterans.

# Southern Construction Projects

## INDUSTRIAL Proposed Stage

**ALABAMA** — Southern Natural Gas Co., Birmingham, has Federal Power Commission authority to construct and operate additional main and branch loop lines in Alabama, for transportation of natural gas; \$865,160.

**ALABAMA** — Alabama Power Co., 640 N. 18th St., Birmingham, Ala., adding new capacity totaling 145,000 kilowatts to its system next year, as part of the \$57,000,000 construction program for the three-year period ending in 1950.

**GREENVILLE** — Pioneer Electric Cooperative has REA loan, \$675,000 for 208 miles line system improvements, and two-way radio communication system; Ala. 22P Butler.

**HARTSELLE** — Joe Wheeler Electric Membership Corp. has REA loan, \$1,985,000 for 740 miles line system improvements.

**LISTERHILL** — Reynolds Metal Co., plans expansion of its aluminum sheet rolling plant; will expend \$5,000,000 for expansion of facilities at the Alabama plant and also in Chicago.

## ARKANSAS

**FAVETTEVILLE** — Ozarks Rural Electric Cooperative Corp. has REA loan, \$665,000 for 199 miles line, headquarters facilities, etc.

**PINE BLUFF** — Paul Finkbeiner, owner and operator of Finkbeiner Packing Co., plans for \$24,000 meat plant.

**SALEM** — North Arkansas Electric Cooperative, Inc. has REA loan, \$1,300,000 for improving present lines.

**SALEM** — North Arkansas Electric Cooperative has REA loan, \$1,390,000 for 572 miles of line system improvements.

## KENTUCKY

**HENDERSON** — City approved \$3,000,000 bond issue for electric power plant.

**OWENSBORO** — Southern Bell Telephone & Telegraph Co. plans new telephone exchange and modernize system, \$1,390,000.

## MARYLAND

**DENTON** — Choptank Electric Cooperative has REA loan, \$1,215,000, for 155 miles line system improvements.

**FREDERICK** — Securities and Exchange Commission approved financing plans of Potomac Edison Co., involving sale of \$5,500,000 in first mortgage bonds, 30,000 shares of cumulative preferred stock and 75,000 shares of common stock.

**HUGHESVILLE** — Southern Maryland Electric Cooperative has REA loan, \$621,000

for 2½ miles transmission line, two switching structures, etc.

**OCEAN CITY** — Ocean Downs Racing Association, Inc., plans trotting track near Ocean City, \$590,900.

## MISSISSIPPI

**JACKSON** — Mississippi Power and Light Co. has registered with Securities & Exchange Commission, Washington, D. C., public offering of \$7,500,000 in first mortgage bonds, to finance part of \$27,000,000 expansion and construction program.

**MERIDIAN** — East Mississippi Rural Electrification Association plans new lines and installations; \$2,500,000.

**MEMPHIS** — Southern Bell Telephone & Telegraph Co., plans new building and dial phone installations, \$1,640,000.

**NATCHEZ** — Adams County and City of Natchez have been authorized by the State Agricultural and Industrial Board to hold an election on a proposed \$300,000 bond issue; if issue is approved, it will be used to purchase a 1,000-acre site for a proposed \$20,000,000 ultra-modern, rayon-pulp plant to be constructed by International Paper Co.

## MISSOURI

**KANSAS CITY** — Panhandle Eastern Pipeline Co. has Missouri Public Service Commission authority to issue \$30,000,000 in sinking fund debentures.

**MARYVILLE** — Nodaway Worth Electric Cooperative has REA loan, \$850,000, for 458 miles line and system improvements.

## NORTH CAROLINA

**HIGH POINT** — Carolina Container Co., C. T. Ingram, vice-pres., has \$500,000 expansion program underway; location on Prospect Road.

**SHELBY** — Southern Bell Telephone and Telegraph Co. plans expansion program costing \$732,000.

## OKLAHOMA

**WALTERS** — Cotton Electric Cooperative has REA loan, \$1,250,000, for 244 miles line system improvements.

## SOUTH CAROLINA

**ABBEVILLE** — Deering, Milliken & Co., Inc., plans addition to Abbeville Mills Co.; \$1,000,000.

**DARLINGTON** — Pee Dee Electric Cooperative has REA loan, \$510,000 for 261 miles line system improvements.

## TENNESSEE

**JEFFERSON CITY** — Appalachian Electric Cooperative has REA loan, \$675,000 for 253 miles line and for system improvement.

**KNOXVILLE** — Knoxville Utilities Board plans \$10,226,000 electric system expansion program.

**KNOXVILLE** — Knoxville Utilities Board seeks approval for \$11,726,000 expansion program.

## TEXAS

**ALVIN** — Phillips Petroleum Co. has preliminary work underway on \$4,000,000 Chocolate Bayou natural gasoline plant.

**AMARILLO** — Producers Grain Corp. plans 2,000,000-bushel grain elevator addition, \$1,000,000.

**COMANCHE** — Comanche County Electric Cooperative Association has REA loan, \$830,000, for 521 miles line system improvements.

**DALLAS** — Dallas Power & Light Co., Dallas Power & Light Bldg. plans 60,000 KW electric generating plant; \$8,270,000.

**DALLAS** — Procter & Gamble Co., Ivorydale, Cincinnati, Ohio, plans out-door plant additions alterations; \$250,000.

**DALLAS** — International Harvester Co., plans wholesale parts depot in Trinity Industrial District; \$1,000,000.

**DALLAS** — Eastman Kodak Co., Rochester, N. Y., plans plant, \$1,000,000.

**DECATUR** — Wise Electric Cooperative, has REA loan, \$550,000 for 301 miles line system improvements.

**HOUSTON** — HomCo., 300 S. Wayside Drive, plans one- and two-story office building with basement, \$1,000,000.

**HOUSTON** — Reichhold Chemicals, Inc., Henry H. Reichhold, Chmn., Board of Directors, Detroit, Mich., plans plant for manufacture of synthetic resins, \$500,000 for initial unit.

**HOUSTON** — Produce Terminal, Inc., plans produce terminal, 3000 Block Washington Ave., at SP tracks, \$2,000,000.

**HOUSTON** — Tennessee Gas Transmission Co. has Federal Power Commission authority to spend \$24,000,000 to expand pipe-line system, consisting of 516 miles new main line loops.


**LUBBOCK** — Producers Grain Corp., Amarillo, plans for bids for 2,000,000-bushel grain elevator, \$1,000,000.

**PORT ARTHUR** — Gulf Oil Corp. plans \$19,000,000 expansion.

**SAN ANTONIO** — United Gas Corp. plans 19-mile gas pipeline; \$2,000,000.

**SAN ANTONIO** — City Public Service

(Continued on page 42)



*Puzzles are his business\**

\* You can count on the Hermitage Service Engineer to come up with the right answer to any perplexing problem relating to the use of cement. Call him in.

**Hermitage Portland Cement Company**

AMERICAN TRUST BUILDING • NASHVILLE 3, TENNESSEE



PORTLAND—HIGH EARLY STRENGTH—AIR ENTRAINING—MASONRY

# SLASH CONSTRUCTION COSTS with MARIONS

**THE MARION LINE**  
Shovels • Draglines • Clamshells • Cranes • Walking Draglines • Pull Shovels

TYPE	CAPACITY	TYPE	CAPACITY
33-M	1/4 cu. yd.	4161	5 cu. yds.
362	1 1/4 cu. yds.	151-M	6 cu. yds.
372	1 1/4 cu. yds.	5323	18 cu. yds.
*93-M	2 1/2-3 cu. yds.	5561	40 cu. yds.
492	3 cu. yds.	**7200 Walker	5-7 cu. yds.
*111-M	3 1/2-4 cu. yds.	**7400 Walker	8-12 cu. yds.
		**7800 Walker	30 cu. yds.

\*Diesel Clutch type and Ward-Leonard electric. \*\*Size of bucket depends on length of boom.

## MARION POWER SHOVEL COMPANY

SEE YOUR MARION DISTRIBUTOR:—

MARION POWER SHOVEL CO.  
6 Glen Iris Park, Birmingham 5, Ala.

OGDEN EQUIPMENT CO.  
2342 Edwards Ave., Jacksonville 4, Fla.

## MARION, OHIO, U.S.A.

Offices and Warehouses in all Principal Cities

HAWKINS EQUIPMENT CO.  
1475 Thomas St., Memphis, Tenn.

RICHMOND MACHINERY & EQUIPMENT CO.  
12 North 15th St., Richmond, Va.

## Three More VIRGINIA BRIDGE Steel Links For Route No. 11



Deck truss bridge over N&W Rwy tracks and New River, Radford, Va.

Continuous Girder and Beam Approach spans over Virginian Rwy and Roanoke River, at Kumas, Virginia.



Beam span overpass crossing Virginian Railway at Salem, Va.

Throughout its long reach from New Orleans northeastward across Louisiana, Mississippi, Alabama, Tennessee and Virginia, to where it leaves the Old Dominion after passing through the famous Shenandoah Valley, Route Eleven is linked again and again by steel structures fabricated and erected by Virginia Bridge. The three new steel bridges illustrated are nearing completion on a 40-mile section of this historic highway in Virginia.

But Route Eleven is no exception—even as these structures are being completed many other bridges, both highway and railroad, are in process of fabrication at our Roanoke, Birmingham and Memphis plants to serve important traffic arteries in eighteen states throughout the South, Southwest and Far West.

More than 50-Years of bridge-building experience is at your service, and regardless of size or design we welcome your inquiry.

# Virginia Bridge Company



ROANOKE

BIRMINGHAM

MEMPHIS

NEW YORK

ATLANTA

DALLAS

UNITED STATES STEEL



**LINK-BELT  
SPEEDER**

# SERVICE

## PROTECTS YOUR INVESTMENT



Zack Laws, who has had 25 years' experience as an operator, recently made this brief, to-the-point comment on the K-370: "It's easy to handle. It's dependable. It gives greater quantity output because it's stronger on the crowd and faster on the swing compared with other machines."

The Link-Belt Speeder line includes twenty-five models, ranging up to 3 yard in capacity, some wheel-mounted, some on crawlers. In every size and type, Link-Belt Speeder advanced engineering is clearly seen in every detail, making for freer action, lower upkeep, long-life and profitable operation.

See our distributor today. Let him show you a size and type to meet your exact needs. Or write for latest catalog.

Link-Belt Speeder advanced engineering, honest construction and quickly available service add up to more profitable machine hours and greater returns on your investment. Your distributor will gladly show you the Link-Belt Speeder line of shovels, cranes and draglines, up to 3 yard capacity and explain the features which contribute to their outstanding performance. For instance—



### SPEED-O-MATIC CONTROL

"Speed-O-Matic" hydraulic control permanently eliminates all "lost motion"—actuates clutches faster and more smoothly. Operators will tell you the "Speed-O-Matic" control relieves manual effort and there is little or no fatigue after a good day's work. Get the facts today—find out how you, too, can greatly increase your output.

## LINK-BELT SPEEDER



**This picture shows  
two important things...**



This picture shows two things that, in six months, caused architects to specify *millions* of square feet of the new Celotex Preseal Roof Insulation on major jobs throughout the country—

**1. "PRESEAL" REDUCES DANGER OF MOISTURE**

A factory-coating of special asphalt on both surfaces and all edges protects Celotex Preseal against moisture... *before, during and after installation.*

**2. "PRESEAL" INSURES A STRONGER BOND**

The coating insures a thorough bond to roof deck and to roofing felts of either the asphalt or coal tar pitch type. Application is easier and faster.

These qualities *plus* uniform, high thermal insulation, make Celotex Preseal a roof insulation you can apply without a worry. Its firmness resists fracturing of the roofing felts under traffic during and after application.

All Celotex products are protected against dry rot and termites by the exclusive (patented) Ferox Process.

For complete information regarding Preseal Roof Insulation, see your Celotex salesman...or write the nearest Celotex office—

**THE CELOTEX CORPORATION, CHICAGO 3, ILLINOIS**

BRANCH SALES OFFICES: Atlanta 3, Ga. • Boston 16, Mass. • Cleveland 14, Ohio • Dallas 1, Texas • Denver 2, Colo. • Detroit 26, Mich. • Los Angeles 13, Calif. • Minneapolis 2, Minn. • New Orleans 12, La. • New York 17, N. Y. • Philadelphia 2, Pa. • Pittsburgh 22, Pa. • St. Louis 3, Mo.

**CELOTEX** *Preseal* **ROOF INSULATION**



## Breaking the Camel's Back

The possible effect of the President's income tax proposals on the construction industry should not be underestimated.

As pointed out last month, our industry is just recovering from the many adversities which beset it throughout the war and the period immediately following. If left alone by government, which is an impractical dream, or if not hamstrung by those to whom the immediate political future is more important than the nation's long range welfare, construction can do its proper job.


There is, however, the little matter of the four billion which the President insists is needed. This is supposed to come from increased corporation and middle and upper bracket personal income taxes. If this recommendation becomes law, it will do no industry any good, but it will smack construction right between the eyes.

The arguments against higher corporate taxes apply to all business. They may be passed over with brief reference to the fact that such taxes are very likely to take the dynamite out of what the President referred to as our dynamic economy.

The higher personal taxes may well be the last straw. Few people stop to think of it, but many construction workers are far above the lower income tax classifications. Much of the potential incentive on the part of these men has already been destroyed by featherbedding and other anti-productive practices on the part of organized labor. If this incentive is further whittled down by requiring machine operators and mechanics, and skilled workers in the building trades to pay larger portions of their earnings into the Federal treasury, we'll soon have a hard time getting anything built.

Revenue raising taxes for justifiable government expenses is a necessary evil, but when they threaten the welfare of any industry so fundamentally essential to the nation's economy as is ours, they become downright dangerous. If we must have the extra four billion, a highly debatable point, let's get it without drying up the sources which produce it.

# POWER!



**PRODUCING  
AGGREGATE**

CRAWLER TRACTORS  
POWER UNITS  
DIESEL ENGINES  
WHEEL TRACTORS

# INTERNATIONAL







## MOVING EARTH

**INTERNATIONAL ENGINES — powering tractors or power units—deliver rugged, low-cost power that cuts operating costs to rock bottom.**

**Producing aggregate** the International UD-18A is one of three International Power Units driving a rock crusher. The low operating cost of these power units is an important factor in profitably meeting the competitive price of crushed stone.

**Moving earth** to clear the way for a hospital

addition is the task of the International TD-18 Diesel Crawler and matched scraper. Averaging 120 yards per hour, the TD-18 did a fast, profitable job of moving a total of 10,000 yards.

You just can't beat International Power for peak production and low operating and maintenance costs. Visit your International Industrial Power Distributor and let him show you how International Tractors and Power Units will produce more profits on your projects.

**INTERNATIONAL HARVESTER COMPANY • CHICAGO**

Listen to James Melton on "Harvest of Stars" every Wednesday evening—CBS



# Industrial Power




# SHUTDOWN INSURANCE...

*Your most  
important  
policy...*




The BUTLER AUTO-BATCH TWINBIN,—an efficient answer to costly shutdowns due to tardy cement deliveries. Utilizes the space for emergency cement reserve which conventional design wastes for batcher and truck access. The principle: A two chamber bin. The upper chamber feeds to dual batcher on a platform pinned to the side. Reserve cement held in lower chamber is brought "upstairs" by elevator when needed. Capacity: 520 barrels. Production: 2 batches every 65 seconds. Result: Continuous operation even when there are delays in spotting that hopper-bottom car.



There's more to the story of the TWINBIN, — much more, — its unusual portability for example. Complete details are yours for the asking. Just write today for the BUTLER TWINBIN Bulletin.

**BUTLER BIN Co.**

WAUKESHA, WISCONSIN



## *Your Profit is in your* **BUCKET**

**3 TYPES  
FOR  
EVERY DIGGING PURPOSE**  
 **$\frac{3}{8}$  to 40 Cu. Yds.**

A full bucket every time . . . and the minimum of maintenance cost, both in dollars spent and in time consumed, will result in more profitable payloads for you. Dragline operators are becoming more and more enthusiastic over the rugged construction, full payloads, and low upkeep of Hendrix Dragline Buckets.

Hendrix Dragline Buckets are engineered by men with "know how" to give you bigger payloads at lower cost. Ask the man who uses one . . . he knows!

**HENDRIX**  
*Lightweight*  
**DRAGLINE  
BUCKETS**

*For descriptive literature ask your dealer  
or write to*

**HENDRIX MANUFACTURING CO., INC.**

**MANSFIELD - LOUISIANA**

# *You Can Handle More Jobs*

with  
**BUCYRUS-ERIE  
2-WHEEL SCRAPERS**



## **G-38**

3½ cu. yd. (struck)  
4¾ cu. yd. (heaped)  
Requires 35 to 55 hp. tractor

## **G-58**

5 cu. yd. (struck)  
6¾ cu. yd. (heaped)  
Requires 50 to 80 hp. tractor

- ★ Loads at front, dumps in rear.
- ★ Simple hydraulic control — positive down pressure on the blade.
- ★ Double curve cutting edge for fast uniform loading.
- ★ Balanced design, non-slap hitch for fast hauling
- ★ Ample flotation — low rolling resistance, exceptional stability.
- ★ Steep dumping angle for fast clean dump.

**H**ERE is equipment that you can count on to keep busy earning profits! Bucyrus-Erie 2-wheel scrapers needn't ever be idle, because they're versatile — capable of handling a host of jobs. Fast and flexible, they can be used with any make of tractor, crawler or rubber tired. They can keep dirt moving on irrigation and drainage projects . . . can give railroads, highway departments, farms a hand: They can handle overburden stripping for mines, reroute streams and channels, build artificial lakes. In construction work they can handle small fill jobs, releasing larger equipment for other tasks. They can build fills over the edges of banks, backfill culvert wing walls, repair washouts, dig and carry loam, handle grading and finishing.

See your International Industrial Tractor Distributor about the profit-earning possibilities of Bucyrus-Erie 2-wheel scrapers on your jobs.

**BUCYRUS-ERIE CO., SOUTH MILWAUKEE, WIS.**

For **BUCYRUS-ERIE** TRACTOR EQUIPMENT See Your  
**INTERNATIONAL INDUSTRIAL  
TRACTOR DISTRIBUTOR**

104T48





Above—\$46,000,000 Fort Gibson dam from the right bank, showing excavation for the right abutment at the lower left, the nearly finished left abutment at upper right center. The two boilers set in a ditch in the upstream dike will furnish steam for concrete curing.

## Construction Plant at Fort Gibson Dam

**F**ORT Gibson Dam, \$46,000,000 project on the Grand River about five miles north of Fort Gibson, Okla., and 12 miles northeast of Muskogee, is now 64 per cent completed. More than 300,000 of the scheduled 465,000 cubic yards of concrete have been placed in the structure, which will be of the gravity type, 2,870 feet long with a maximum height of 110 feet. Its features and methods of construction, as well as the plant being used, are described in the paragraphs that follow:

### Cofferdams

Circular cell type cofferdams were constructed to facilitate foundation excavation. The cells were composed of inter-

locking steel sheet piling driven around a pre-fabricated template approximately 44 feet in diameter. Piling length was 50 feet in the upstream cofferdam. Downstream lengths of 40 feet were driven. The cells were filled with earth and gravel; the earth being dumped from trucks and placed by clamshell and the gravel being pumped into the cells by a dredge mounted on a steel barge. The cells are located on 48-foot centers with circular arc sheet pile sections connecting adjacent cells. These connectors were also filled with earth and gravel in the same manner as were the cells.

The over-all cofferdam operation was planned to be constructed in three stages. Stage One cofferdam projected into the river channel from the left bank and enclosed a work area approximately 400 feet wide and 1,100 feet long. Within this area, the entire left abutment, six power intake monoliths, six spillway monolith foundation lifts and two complete spillway monoliths were constructed. Only foundation lifts were poured for the six spillway monoliths, to provide a channel for second stage diversion. Upon completion of work in Stage One, the cells were removed and the steel piling cleaned and straightened for use in Stage Two construction.

Stage Two cofferdam extends into the river channel from the river's right bank and is attached to one completed spillway


monolith constructed in Stage One.

The right flood plain is rather broad and rises gradually to intersect the sheer limestone bluff into which the right abutment of the dam structure will be tied. Therefore, a different type of cofferdam was constructed through the flood plain area. A vertical "cut-off" wall of interlocking sheet piling was driven through the flood plain overlaid to the limestone. An impervious dike was raised over the cut-off wall to the top elevation of the cells forming the remainder of the cofferdam.

Stage Two cofferdam encloses an area approximately 2,000 feet in length and varies in width from 250 to 500 feet. At present, attention is centered on the construction of the seven right abutment and twenty-three spillway monoliths within the Stage Two area.


Construction of the Second Stage cofferdam diverted the river channel through the opening which was provided during Stage One operations. The diversion channel is approximately 300 feet wide and has a maximum discharge of approximately 149,000 C.F.S. at a water elevation just short of cofferdam over topping. In order to afford access from the operational area into the Second Stage area, a steel trestle bridge was placed across the river diversion with the roadway extending from the left river bank across the bridge, along the top of the Second Stage downstream cofferdam and down a dirt ramp into the Second Stage construction area.

The tentative plan for Third Stage con-



Left—The concrete batching plant at Fort Gibson is about 80 feet high with the aggregate storage bin at the top of the tower.

## Fort Gibson Dam—Continued



*Above—Left—Concrete buckets are hoisted from trucks to forms by two steam gantry cranes mounted on rails, supplemented by crawler type cranes. The placement crew uses two-man vibrators to consolidate the concrete as it is dumped. A standard five-foot lift is used except on the first four pours. At the right is a close-up of the concrete forms, which are of the cantilever type in various lengths with a height of 11 feet 1 1/2 inches. Absorbent lining is used on forms where the concrete surface will be exposed.*

struction is to place a cell type cofferdam upstream and downstream from the foundations of the six spillway monoliths now being used as the river diversion. Upon completion of the cofferdam, the river channel will be completely blocked and the impounded water will begin to form the lake. However, a minimum water level will be maintained by discharging the normal flow of the river through eight 5-foot-8-inch by 7-foot sluice ways located in the spillway monoliths. Third Stage construction will connect the portions of

the dam structure previously constructed in the other two stages of work.


In general, dewatering of the cofferdams is done by three eight-inch, 1,800 gal./min. diesel powered pumps. Supplemental pumping, when required, is done by using 2-inch and 4-inch pneumatic pumps. In order to control water seepage within the working area, a small, low concrete retaining wall was constructed adjacent to the cells to divert all seepage into two centralized sump pits from which water is pumped intermittently.

### Excavation and Foundation Preparation

Excavation, for the most part, consists of removing overburden from the limestone foundation. Two cubic yard shovels, clamshells, end dump Euclid trucks and bulldozers are the principal pieces of excavation equipment in use. Under the present contract, there are approximately 620,000 cubic yards of excavation to be done.

When a dip in the limestone foundation

*Below—Aggregate plant flow chart. A list of the equipment appears on the opposite page.*





Above—Circular cell type cofferdams were constructed. These were composed of interlocking steel sheet piling driven around a prefabricated template about 44 feet in diameter.

occurs in excess of 3 per cent, sloping from upstream to downstream, a keyway is blasted and jackhammered into the upstream one-third to one-half of the foundation. The foundation limestone is generally overlaid by a layer of shale varying from 0 to 5 feet in depth at the axis. The shale increases in thickness as the limestone dips downstream. The faces of the keyways and the structure limits are line-drilled prior to blasting in order to obtain a regular face.

The dip along the limestone strata prevails throughout the limits of the structure. A greater portion of the gravity type monoliths rest on limestone foundation. The stilling basin slab, which lies immediately downstream from either limestone or shale. This slab, which has a minimum thickness of 5 feet, is keyed into the limestone for a minimum of 2 feet in depth along the downstream toe. The training walls and stilling basin walls are placed on limestone, thereby confining the shale that is used for foundation.

It is necessary to treat the surface of all shale areas opened and subject to weathering to prevent rapid deterioration. The treatment consists of spraying the dry, clean, shale surface with an asphalt sealing compound. The seal is sprayed on shale areas to be covered with

concrete within two hours after final excavation has taken place.

Grout pipes to be used in foundation grouting are placed on ten-foot centers along the axis of the dam. The pipe extends from an inspection gallery down to the rock foundation. At a later date, a foundation grouting crew drills into the foundation through these grout pipes and supplies grout at various depths and under varying pressures which are determined by the character of the foundation and existing local conditions. In this manner, a grout curtain is placed under the structure to seal all fractures, cavities or otherwise porous material underlying the rock foundation.

#### Concrete Forms

The basic exterior concrete forms are cantilever type constructed in panels of various lengths and having a height of 11 feet 1 1/4 inches. Using combinations of various length panels, any practical exterior form can be assembled with very little delay. The panels form lifts of concrete approximately five feet in height. The vertical studs and horizontal walers are 7-inch channels, 9.8 pounds per foot and are faced with 2-inch tongue and groove material nailed to 3-inch by 6-inch nailing strips that are bolted to the backs of the channel studs. The forms are held

in place with 3/4-inch rods and "ty-screws."

All forms are fabricated in the contractor's carpenter shop, located at the job site, well in advance of the time scheduled for their use. The shop is equipped

(Continued on page 58)

#### Fort Gibson Aggregate Plant

(Chart on page 26)

1. 36" Apron Feeder
2. 25" x 40" Primary Jaw Crusher Diesel Powered
3. 42" x 60" 4" - 1 1/2" Double Deck Screen Unit
4. 10" x 36" Secondary Jaw Crusher Diesel Powered
5. 6" - 1 1/2" Double Deck Screen Unit 4' x 10'
6. 1 1/2" - 1" Double Deck Screen Unit 4' x 10'
7. 60 Ton Bin Under
8. 40" x 24" Roll Crusher Diesel Powered
9. 1" - 3/4" Double Deck Screen Unit Scalping 1" or 3/4" 60 Ton Bin Under 4' x 12'
9. 24" Apron Feeder 3 H.P. Unit
10. 24" Oscillating Feeder 5 H.P. Unit
11. 1 1/2" x 3 1/2" Double Deck Screen Unit 42 x 12 60 Ton Bin Under
12. Minus 1 1/2" Flow
13. Adjustment for 3" x 6" Reduction to 1 1/2" Minus
14. 12" x 36" Twin Jaw Crusher
15. 7" x 12" Rotary Scrubber (Telsmith)
16. 3 1/2" x 1 1/2" Double Deck Screen Unit 4' x 12' With Spray Bars
17. 150 Ton Storage Bin (Pittsburgh-Des Moines Steel)
18. 50 Ton Surge Bin
19. 1 1/2" Screen Unit Scalping 1 1/2" Minus 1' x 12' 16" x 18" Bin Under
20. 5" x 24" Rotary Scrubber
21. 3" - No. 4 Double Deck Screen 4' x 12' With Spray Bars
22. 12" Bucket Conveyor 1 1/2" Minus to 21
23. 3" Shorthead Symonds Cone Crusher
24. 300 Ton Storage Bin (Bulter Bin)
25. No. 4 No. 8 Double Deck Screen Unit 4' x 12' 150 Ton Bin Under
26. 3" - No. 8 Double Deck Screen Unit 4' x 12' 150 Ton Bin Under
27. 30" Hammermill Crusher 150 H.P. SR
28. Motor Reduction Of No. 4 - 3/4" to No. 8
29. 150 Ton Storage Bin (Pittsburgh-Des Moines Steel)
29. 16" Diameter Sturtevant Sand Air Separator 75 H.P. Motor
30. Adjustment To By-Pass Air Separator Swing Gate
31. 30 Ton Storage Bin 100 Minus To Waste
32. 150 Ton Storage Bin, Sand (Pittsburgh-Des Moines Steel)
33. Adjustment Of Flow Between No. 4 to 1 1/2" Rock And Sand Swing Gate
34. Adjustment Of Flow To Either Mill Swing Gate
35. 0 To 1" Scalping To Waste As Required
36. Scalping Screen 0 to 1/4" Waste
37. 10" Sturtevant Air Separator
38. 1000 KVA Transformer
39. 5 H.P. Motor
40. 7.5 H.P. Motor
41. 15 H.P. Motor
42. 25 H.P. Motor
43. 50 H.P. Motor
44. 75 H.P. Motor
45. 200 H.P. Motor
46. Diesel Motor
47. 10 H.P. Motor
48. 2 10" x 10" Storage Bins
49. 24" Apron Feeder
50. 30 H.P. Motor
51. 1 1/2" Screen Unit Scalping 3/8" Minus

(Equipment is "Cedarapids," except units 15, 17, 23, 34, 38, 39, 32 and 37)

#### Fort Gibson Dam

##### MIX-TABLES ONE CUBIC YARD

	Class B		Class A		Class C, Ext.				Class C Int.		
Mix No.	B27.5W-1 B Spec.-1	B27.5W2	A34.5W	3/4 A 46.W	CE27W-1	CE27W-2	CE Spec. 1	CE Spec. 2	CE Spec. 3	CE25W-1	CE25W2
W/C	.59	.59	.59	.53	.59	.59	.59	.72	.59	.68	.68
Bags Yd.	4.5	4.5	4.5	5.5	6.9	4.5	4.5	4.5	4.5	3.5	3.5
Gal bag	6.68	6.68	6.68	6.0	5.83	6.67	6.67	8.90	6.67	7.68	7.68
Cement	423	423	423	517	564	423	423	423	423	329	329
Water	250	250	250	275	292	250	250	300	250	224	224
sand	958	1100	958	1151	1189	941	940	961	1290	958	933
3/4 Agg.	625	905	550	765	2089	500	450	624	2195	500	450
1 1/2 Agg.	802	1480	877	1421	....	542	592	800	1526	650	675
3" Agg.	1100	....	1100	....	....	699	699	1098	....	725	775
6" Agg.	....	....	....	....	....	801	801	....	....	850	800
Admix.	450cc	450cc	....	550	690	450	450	450	450	350	350
Total Wt.	4158	4158	4158	4129	4114	4157	4157	4308	4157	4186	4186
Item	29	29	29	28	28	31	31	31	31	30	30
CA Factor	.91	.91	.91	.78	.74	.92	.92	.92	.92	.97	.97
Total Gal.	30	30	30	33	35	30	30	40	30	27	27
C Sand	27.5	31.6	27.5	34.5	46	27	27	27	27	25	25.7



*Above—Newly elected officers of the Carolinas Branch after the election. Top row, left to right are R. H. Pinnix, the retiring president, William F. Bowe, C. P. Street, H. S. Crain, directors. Bottom, left to right: E. D. Sloan, director; W. K. Dickerson, Jr., vice president, and Robert Patton, executive secretary.*

## Carolinas A. G. C. Branch Holds Most Successful Convention

### Greenbrier Assembly Attended by Many Members and Ladies—Hear National and State Leaders Talk on Construction Industry Problems

**G**ATHERED at White Sulphur Springs, W. Va., for their twenty-eighth and most successful convention, members of the Carolinas Branch of the Associated General Contractors of America last month elected new officers, discussed their problems, listened to addresses by both local and national leaders on the current outlook and what to expect if present unsettled international conditions should result in war.

W. T. Potter, president of the Greenville, S. C. firm of Potter & Shackelford,

Inc., was elevated to the Carolinas Branch presidency, with W. K. Dickerson, Jr., head of Dickerson, Inc., of Monroe, N. C., elected vice president. C. P. Street, secretary and general manager of McDevitt & Street Co., Charlotte, N. C. retained the office of treasurer of the Carolinas group and Robert Patton, the organization's executive secretary, was re-appointed.

Six new directors were selected. They were: E. D. Sloan, president of Sloan Construction Co., of Greenville, S. C.; Lawrence

C. Merchant, vice president of Merchant Construction Co., of Asheville, N. C.; C. N. Whilden, vice president of Blythe Brothers Co., of Charlotte, N. C.; H. S. Crain, president and treasurer of Crain & Denbo, Inc., of Durham, N. C.; William F. Bowe, of William F. Bowe & Co., Augusta, Ga., and E. G. Skinner, president of Skinner & Rudbeck, Inc., of Charleston, S. C.

#### Pinnix Makes Report

The report on 1948 activities of the Carolinas Branch was delivered by R. H. Pinnix, of Gastonia, N. C., the retiring president, who stated he felt "our accomplishments have been exceedingly worthwhile" and that a valuable service has been rendered the construction-buying and using public in continuing to uphold the standards of the construction industry at the same time praising the cooperation received from architects, engineers and highway departments.

Mr. Pinnix emphasized the importance of apprentice training and the campaign to train personnel for key construction industry positions, expressed gratification at the progress made under the Army affiliation program and pointed to the large increase in membership as an indication of the increasing prestige of the Carolinas Branch. He urged closer cooperation among the members and said full advantage of 1949 opportunities can be taken only by closely watching trends and developments in business and government.

Officials of the country-wide Associated General Contractors organization delivered the keynote addresses at the opening session. Dwight W. Winkelman, president, of Syracuse, N. Y., revealed recently devised plans for mobilizing the construction industry in event of war and H. E. Foreman, managing director, reported generally on national conditions and at the same time urged his audience to give thoughtful attention to world and domestic political and economic affairs.

#### War Role Discussed

Prefacing his address with the prediction that the value of 1949 construction will equal or pass the 1948 level, Mr. Winkelman described proposals recommended to the National Security Resources Board for using the experience and knowledge of the construction industry if war should come. The theme of his talk was that the construction industry in the conflict of the future must act more speedily and more efficiently by previously made plans unhampered by inappropriate regulation.

The three prime functions of the construction industry in wartime, as outlined by Mr. Winkelman, should be to form a nuclei for military construction forces, to repair the damage made by enemy attack on manufacturing, transportation and utility facilities and to do the construction necessary for military and industrial operations and essential civilian requirements. New construction in a future war is expected to top the \$49,000,000,000 worth of work done in World War II, with the additional demand that it

*Below—The Greenbrier, at White Sulphur Springs, W. Va., where the Carolinas Branch of the Associated General Contractors gathered last month.*







*Left—W. T. Potter, the new president. Right—(Top to bottom)—Dwight W. Winkelman, national A. G. C. president; H. S. Foreman, national managing director; R. H. Pinnix, retiring president, and William Muirhead, past president of both the national organization and the Carolinas branch.*

was in obtaining materials, as construction was not considered an end product.

He accented the war-time need for continuing production of essential construction equipment and materials, including on his list tractors, bulldozers, cranes, power shovels, power scrapers, heavy earth-moving wagons, motor graders and compressors, and such materials as reinforcing bars, structural steel shapes, pipe and fittings, lumber, nails and building hardware and copper wire and copper products.

#### Politics Scrutiny Advised

Managing Director Foreman advised the assemblage in the auditorium of the Greenbrier Hotel to consider political affairs both at home and abroad as vitally important to the construction industry, citing as an example the influence of overseas policies on the amount of steel the domestic construction industry will have for its own business. The Marshall Plan and the defense program, he observed, will probably accelerate as the years go on.

Mr. Foreman forecast curtailment of some construction, if the defense program is enlarged, with resulting increased demands against the country's 64,000,000 tons of usable steel. The country, in his opinion, is faced with "more government" in the next four years, with federal aid very likely extended into the educational building field, in addition to the airport, hospital and highway programs. This may mean a battle to hold to the contract system.

#### Divisions Hold Meetings

Labor relations promise to be no less complicated. The contractor must move to see that his interests are properly represented with regard to labor. The overtime on overtime decision is a problem to be faced. The basing point decision he regards as creating a monopoly for the plant nearest the point of consumption, thus upsetting the purchasing scheme of the construction industry.

Three division meetings were held simultaneously following the general session. The building division met under chairmanship of F. L. Shackelford, of Potter & Shackelford, Inc., Greenville, with an address by Col. J. Norman Pease, of J. N. Pease & Co., Charlotte engineering firm, and remarks by W. A. Snow, manager of the building division of the national association. W. F. Rowe led the highway and public works division and

(Continued on page 61)

*Left—C. R. McMillan, Chief Highway Engineer of South Carolina, and Col. J. Norman Pease, Charlotte engineer, who addressed division meetings at the convention.*





**Left—Top—**Rock excavation for concrete stilling basin below the outlet works on the Benbrook dam and reservoir project. **Lower—**Foundation for the outlet works structure, showing forms for the wing walls of the intake approach channel in the foreground. In the background at the left are the foundations for the 13-foot diameter flood control conduit. The two 30-inch steel pipes shown at the extreme left are for discharge of conservation waters.

## Galveston Engineer District Lets \$4,300,000 Contract for Benbrook Dam Job



**Above — Left —** Col. B. L. Robinson, Galveston district engineer, under whose supervision the Benbrook project is being constructed. **Charles J. Kocian, right,** is resident engineer for the Corps of Engineers. A graduate of West Point, Colonel Robinson has served with the Army engineers in many parts of the world, including Panama and the South and Mid-Pacific areas. In World War II he engaged in seven campaigns and two D-Day landings with the rank of brigadier general. Mr. Kocian is a native of St. Paul, Minn. He entered government service in 1930 after graduating from the University of Minnesota. Since he has worked on many outstanding engineering projects.

**T**O complete construction of the earth embankment and spillway of the Benbrook Reservoir project, the Galveston District of the Corps of Engineers, last month awarded a \$4,300,000 contract to the List and Clark Construction Co. of Kansas City, Mo., it was announced by Col. B. L. Robinson, U. S. engineer of the Galveston District.

The project, which is located on the Clear Fork of the Trinity River about 10 miles southwest of Fort Worth, Texas, is one of four reservoir projects which the Corps of Engineers is presently constructing in the Trinity River Basin for flood control and water conservation. Others are the Lavan, Grapevine, and Garza-Little Elm projects.

When completed the Benbrook project will consist of an earthen dam about 9,200 feet long with a maximum height of 130 feet above the stream bed. The reservoir will cover an area of 7,600 acres at the top of the flood control pool and will control 416 square miles of run off.

Under the direction of the Corps of Engineers, Ottinger Brothers Construction Company is now constructing the concrete outlet works. These will con-

sist of a 100-foot control tower, two gated intake openings, each 6.5 feet wide and 13 feet high and a 13-foot diameter circular discharge conduit. In addition to the flood control outlets, two 30-inch steel pipes will be provided for the release of conservation water.

Construction of the project began in May 1947 when the J. W. Mosley Construction Company began work on the earth embankment. This contract was completed in January 1948.

Other contracts, yet to be completed are those with Phillips and Davis for delivery of service and emergency gates and Consolidated Western Steel Corporation for a 50-ton crane.

Construction of the project which is presently one month ahead of schedule will be completed during the fiscal year of 1952, according to Charles J. Kocian, resident engineer for the Corps of Engineers, who is supervising the construction of the project at the dam site.

Common excavation for the intake tower, conduit and stilling basin was accomplished by the use of two LeTourneau 8 cubic yard scrapers pulled by Caterpillar D-7 tractors. As the excavation approached grade, a one-cubic yard Northwest shovel was employed to remove weathered rock material and to excavate to neat lines the approach to the intake and the stilling basin discharge channel.

The outlet works structure is founded upon a soft dark blue to gray Goodland  
(Continued on page 52)

**Below —** Construction of the 13-foot diameter conduit through which flood waters will be discharged.



# Contractors' Overtime Pay Problem Discussed

CONSTRUCTION of homes, apartments, schools and churches, retail and department stores is not covered by the provisions of the wage and hour law, it was emphasized in a recent address by Harry Weiss, director of the wage determinations and exemptions branch of the Department of Labor, although "instrumentalities of interstate commerce" and facilities used in the production of goods for interstate commerce do come within the scope of the act.

"Instrumentalities of interstate commerce," as defined by Mr. Weiss include highways over which interstate commerce regularly travels, interstate railroad or pipeline facilities, river and harbor facilities, ships, airports and other transportation terminals. "Facilities used in the production of goods for interstate commerce" are the nation's industrial establishments, such as mining, manufacturing or processing plants.

## Five Categories Covered

Employees engaged in five general types of construction activities connected with these "instrumentalities" and "facilities" are covered by the minimum wage and overtime provisions of the Wage and Hour Law, but those engaged in the original construction of buildings are not generally covered, even if the buildings when completed will be used as instrumentalities of commerce or to produce goods for commerce.

Workers engaged in construction of new buildings are considered covered when their work constitutes an enlargement or extension of existing production facilities of commerce instrumentalities. This applies where the new building becomes an integral part of an existing plant producing goods for interstate commerce or where it extends, enlarges or improves an existing means of interstate commerce.

Coverage is predicated on the work of the individual employee but would not be limited only to those employees who work on the site. Included may be office workers, stenographers, bookkeepers, clerical help, payroll workers, time keepers, watchmen and guards, employees who maintain, repair or rebuild machinery and equipment used on the job and employees transporting such equipment to and from the job site.

## Supreme Court Decision's Effect

How the Supreme Court decision in the longshoremen's case affects the construction industry was also discussed by Mr. Weiss, who said "the decision dealt with the application of the overtime provisions of the Act to employees in the longshore industry who received premium payments for working certain specified hours and days during the week. The longshore industry has been characterized by the casual nature of its employment. Because of this, a type of contract developed in that industry which had the purpose, and largely the effect of establishing a concentration of work within

specified clock hours and days, in spite of the number of different employers a man might have during the course of a work week and notwithstanding impossibility of a regular weekly pattern of hours.

## Overtime Hours Specified

"The longshore contracts made no reference to premium payments for hours in excess of a daily or weekly standard, but merely specified the hours which were to be paid at straight-time rates and the hours during which so-called 'overtime' rates were to be paid. Typically, the hours designated as straight-time were the hours between 8 a.m. and 5 p.m. on Monday through Friday, and from 8 a.m. to noon on Saturdays. Work outside these hours or on holidays was to be paid for at premium rates, usually at time and one-half.

"The Supreme Court held that these premium payments, although called 'overtime premiums' in the contract, were not 'true overtime' at all, within the meaning of the Wage-Hour Law. Such higher rates, the Court ruled, must be included in the 'regular rate' of pay for the purpose of computing overtime compensation due under the Act for hours worked over 40 in a week.

"The Supreme Court went on to define what constitutes 'true overtime' under the Act. The Court held that a true overtime premium is an extra payment, in addition to the regular rate, for working in excess of a bona fide daily or weekly standard number of hours. This time overtime pay need not be included in computing the 'regular rate of pay' and may be offset against any overtime pay required by the Wage and Hour Law. There is no problem under it for employers whose employees do not work more than 40 hours a week; nor is there any problem if the employer pays time and one-half for hours worked beyond 40 and makes no other types of extra or premium payments in excess of the employee's straight-time rate."

## Construction Premium Pay

Stating that he understands the construction industry makes it a common practice to pay employees certain daily premiums for work outside the normal working hours and for work on Saturdays, Sundays and holidays, Mr. Weiss said the Court indicated in its decision the circumstances in which premiums paid for work at such times are to be regarded merely as higher straight-time earnings for work performed during undesirable hours or for undesirable work and when they can constitute true overtime.

He said the fundamental principle is that only those premium payments for work on Saturdays or Sundays, or at night, or at other specified times that are contingent upon the employee's having previously worked a specified number of hours or days, in accordance with a bona fide standard, may be considered

true overtime payments within the meaning of the Wage and Hour Law. However, there is no single and exclusive test for what constitutes a standard. It may have been established through collective bargaining or as a result of the employer's established practice.

If the pattern of employment in an establishment, or for a particular group of employees, establishes the fact that the work on Saturdays or Sundays normally falls within the overtime hours set by a contract or practice; that is, if Saturday or Sunday work normally is performed after the employees have previously worked a standard number of hours or days in the same work week—the premium payments for these days may be regarded as true overtime pay for excessive hours of work. "If these are the facts," Mr. Weiss said, "the premiums for Saturday and Sunday need not be included in the 'regular rate' and may be offset against any overtime due under the Wage and Hour Law for hours in excess of 40 a week."

## Normal Work Week

The situation, he explained, typically occurs when the work week begins on Monday and the employees normally work a standard work week of, say, 40 hours, before working on Saturdays and Sundays. In such instances, Saturday and Sunday hours would normally fall within the weekly overtime hours set by the contract or practice in effect at the plant. However, if for example, the work week begins on Thursday and ends on Wednesday, it would be impossible to show that Saturday and Sunday work normally falls after the employees have previously worked on a bona fide standard number of hours or days in that week.

"Under such circumstances, premium pay for work on Saturday and Sunday would have to be included in the 'regular rate.' Furthermore, if the pattern of employment is determined by variable factors which are such that the employment is in fact sporadic and there is actually no standard work week normally worked by employees, it cannot be said that the Saturday or Sunday work normally falls after the employees have previously worked a bona fide standard number of hours in the week."

## Daily Overtime Provisions

Turning to daily overtime provisions, Mr. Weiss stated that premium payments for work in excess of a daily standard of hours are true overtime premiums under the Act. If employees normally work eight hours a day, premium rates for hours in excess of that standard are true overtime under the law. Sometimes, however, premium payments are provided for work before and after specified shift hours. If such premiums for out-of-shift work, commonly known as "clock overtime," are not contingent on the employee's having previously worked a standard number of hours in the day, the

(Continued on page 69)



Above—Perspective showing Blakely Mountain dam as it will appear when finished on the Ouachita River, about three miles west of Mountain Pine, Ark.

## Two Tunnels Being Bored at Blakely Mountain Dam

**T**WO tunnels—one ultimately scheduled for power generation and the other for flood control—are now being driven for the initial purpose of diverting the waters of the Ouachita River 13 miles northwest of Hot Springs, in Garland County, Arkansas, preliminary to construction of the Blakely Mountain dam at the head of Hamilton Lake.

The project when completed will consist of an earth dam approximately 1,500 feet in length and 230 feet in height, a flood control power intake structure, a flood control tunnel and stilling basin, a

power tunnel, surge tanks, penstocks, powerhouse and appurtenant structures. The maximum power pool will cover 40,000 acres with a storage capacity of 1,286,200 acre feet. The maximum flood control pool will cover 48,000 acres with a storage capacity of 617,000 acre feet.

Diversion of the river, prior to construction of the dam embankment is to be accomplished through the two diversion tunnels now under construction. Downstream portions of these tunnels will subsequently be used for power and flood control purposes. The power tun-

nel is 30 feet in diameter and approximately 1,500 feet in length. Diameter of the flood control tunnel is 19 feet and its length about 1,700 feet. Tunneler connections from approximately the midpoint of these tunnels will rise 80 feet to the power and flood control intake structure. Diversion ends of the tunnels will be plugged when no longer needed.

### Contract Totals \$4,446,155

Contract for the construction of the tunnels was awarded to United Concrete Pipe Corp., Chas. L. Harney, Inc., Stolte, Inc., and Ralph A. Bell, all California firms, on June 21, 1948. Amount of the contract is \$4,446,155 and the contract period is 400 days.

Work was started July 12 with open cuts in the stilling basin at the downstream end of the tunnels. First tunnel excavation at the downstream portal of the power tunnel was started August 4 with two exploratory drifts along the spring line. These drifts were carried into the abutment for 60 feet and connected across the tunnel crown by a riser. Douglas fir arch timbers—12- by 14-inch—were set through the drifts and riser beginning at the maximum penetration and backed out to the portal as the drifts were connected by the riser. Work was completed on September 4 without difficulty despite overburden of 15 feet of rotten brown shale at the portal.

Entrance into the flood control tunnel was accomplished in a similar manner. However, five feet of the portal was lost due to caving ground.

### Bench and Header Method Used

The main tunnel excavation was then started by a bench and header method. This method was used for approximately 75 feet in the flood control tunnel and 150 feet in power tunnel. At these penetrations better rock was encountered and full face excavation was started. The larger jumbo used in the 30-foot power tunnel mounts 8 drifter drills and the smaller one in the 19-foot flood control tunnel mounts six.

The headings in both tunnels are being

Left—Jumbo used in the power tunnel.





*Right—Top—Arched finger raiser with first timber arch set in place in the power tunnel. Middle view shows exploratory drift along spring line of 30-foot tunnel. Bottom—Drift and bench along right side of power tunnel.*

drilled to a depth of 12 feet using four-foot drill steel changes. An advance of 10 feet is being made each round. Progress at the present is approximately 10 feet per day in the power tunnel and approximately 15 feet per day in the flood control tunnel. The excavation is in sandstone and shale interbedded with hard dark grey stable shale predominating. Center line of the tunnels is normal to the strike. The bed dips approximately 30 degrees from the horizontal. Driving is into the dip.

A  $\frac{3}{4}$ -cubic yard shovel is being used for mucking in the large tunnel and an overhead tractor loader is being used in the smaller tunnel. The muck is hauled from the tunnel with 6 cu. yd. Koehring Dumpsters.

Estimated date for holing through on the flood control tunnel is March 15, 1949.

Tunnel supports consists of steel ribs horseshoe shape, spaced 2 or 3 feet on centers, depending on the character of the material, with steel liner plates installed on top of the ribs to approximately 45° each side of the crown. Liner plates and ribs are blocked with wood.


Both tunnels will be lined with concrete with concreting operations scheduled to begin early in February 1949.

The work is under the supervision of Col. R. G. Lovett, district engineer, Corps of Engineers, with headquarters at Vicksburg, Miss. Col. J. H. Trescot is resident engineer on the job with William L. Maschmeyer as assistant. Clifford G. Kidwell is general superintendent for the contractor.

#### Blakely Mountain Project Statistical Data

<b>DRAINAGE AREA</b> .....	1,105 sq. mi.
<b>MINIMUM POWER POOL</b>	
Elevation .....	535.0 ft. m.s.l.
Area .....	20,000 acres
Storage .....	864,900 acre-feet
Equivalent runoff .....	14.7 inches
<b>MAXIMUM POWER POOL</b>	
Elevation .....	578.0 ft. m.s.l.
Area .....	40,100 acres
Storage .....	1,286,200 acre-feet
Equivalent runoff .....	21.8 inches
<b>FLOOD CONTROL POOL</b>	
Elevation .....	592.0 ft. m.s.l.
Area .....	48,300 acres
Storage .....	617,000 acre-feet
Equivalent runoff .....	10.5 inches
Design Flood—April 1927	
Estimated peak inflow .....	122,000 c.f.s.
Estimated peak outflow .....	3,000 c.f.s.
Estimated volume .....	686,000 acre-feet
Average rainfall .....	15.6 inches
Average runoff .....	11.7 inches
<b>SURCHARGE POOL</b>	
Elevation .....	610.2 feet, m.s.l.
Area .....	60,500 acres
Storage .....	995,000 acre-feet
Equivalent runoff .....	16.8 inches
Design Flood, Hydrograph A	
Estimated peak inflow .....	418,000 c.f.s.
Estimated peak outflow .....	45,000 c.f.s.
Estimated volume .....	1,163,000 acre-feet
Average rainfall .....	21.5 inches
Average runoff .....	19.7 inches
<b>FREEDARD</b>	
Elevation, top of dam .....	616.0 feet, m.s.l.
Area .....	64,100 acres
Storage .....	361,000 acre-feet
Equivalent runoff .....	6.1 inches
Height .....	5.8 feet
<b>FLOOD CONTROL CONDUIT</b>	
Diameter .....	19.0 feet
Invert elevation .....	399.0 ft. m.s.l.
<b>SPILLWAY</b>	
Width .....	200 feet
Invert elevation .....	592.0 feet m.s.l.





## Baytown Tunnel is Part of \$9,000,000 Gulf Road Change

TEXAS' second tunnel will soon be placed under construction as part of a \$9,000,000, seven and one-half mile project for relocating State Highway 146 between LaPorte and Baytown in the highly industrialized area thirty miles south of Houston. The project involves a three level bridge, roadway approaches in cut and hydraulic embankment, three trestles and the tunnel.

Two ferries operated across the Houston ship channel as part of the state highway system will be eliminated by the proposed subaqueous tube, which is to be the second under that man-made route connecting Texas' great industrial center with the sea. A third tunnel will be part of a similar project spanning nearby Galveston Bay.

With exception of the trestles and tunnel, the facility is being developed as a divided lane highway with design speeds of 50 M.P.H. on the land portions and 35 M.P.H. through the tunnel. Traffic studies revealed that the southern terminus of the project is at a point where there is considerable distribution of traffic. Certain economies would be achieved through the use of a three-level bridge at this point to effectively handle these turning movements.

Approximately three and one-quarter miles of the project will be constructed on hydraulic embankment placed directly during tunnel dredging operations. These embankment sections are to be located in both the San Jacinto and Black Duck bays which are not navigable. Two trestles, each approximately 400 feet in length, are planned in these embankments. These spans will be provided for possible future navigation developments and also to satisfy hydraulic requirements as these bays are tidal. A third trestle approximately 550 feet long will be constructed over Goose Creek, a navigable body of water. Standard design features of the project are in accordance with those of the

Texas highway department and the Public Roads Administration insofar as they may be applied. Pavement, trestle, and tunnel vehicular loadings are based on those recommended by the American Association of State Highway Officials.

Data obtained from the hydrographic and soil surveys of the channel area reveal that the precast subaqueous tube type of tunnel would be most adaptable. Development of a general plan and profile indicated that a tunnel slightly in excess of 3,000 feet between portals with ramp sections beyond these points 500 feet in length would be required.

Two cross-sectional designs have been prepared for the precast subaqueous sections. The first is circular in exterior cross section, and the second of the conventional octagonal shape. It is believed that considerable economy can be effected through construction methods employed during fabrication of the circular section. This section, however, has not been as commonly used, and in view of this, the octagonal section is being offered as an alternate design.

The tunnel portion of the project consists of nine precast sections, each varying in length between 250 and 300 feet. The portal segments are approximately 230 feet long and are constructed by cut and cover methods following the placing of the subaqueous portion. The ramp sections will be constructed simultaneously with the portal segments.

The nine subaqueous segments will be constructed by the trench and precast methods. In this method, a trench will be dredged to a maximum depth of 86 feet below Mean Low Water and the precast tunnel segments of steel and concrete lowered into it.

Ventilation of the tunnel is to be accomplished by employing a single fresh air duct under the roadway, activated by equipment located in the ventilating building located at the north portal. Control

## Second Ship Canal Tube to be Over 3,000 Feet Long, of Precast Design

of the system, including the continuous sampling and recording devices, will be automatic. Tunnel lighting will be provided through the use of a single fixture containing a double line of fluorescent tubes.

Construction of the land portions of the project will be concurrent with that of the tunnel. A total construction period of 18 months has been scheduled. Construction of the channel crossing has been divided into four contracts:

Contract 1 covers fabrication of the precast segments, the preparation of the trench across the channel, the placing of the hydraulic embankment, and the placing of the precast sections.

Contract 2 involves the construction of the cut and cover sections at the portals, the open approaches and the ventilating building.

Contract 3 involves the installation of the mechanical and electrical equipment.

Contract 4 will cover tiling and finishing the facility. Total estimated cost of the project, based on current construction costs, is approximately \$9,000,000, exclusive of right-of-way.

Construction plans for Contract 1 have been completed and are being reviewed by State and Federal officials and pending approvals the contract is expected to be let about the first of the year. Plans for Contract 2 are well advanced.

Plans for the land and bay crossings are being prepared by the Texas Highway Department. Jim Douglas is district engineer at Houston. The firm of Parsons, Brinckerhoff, Hall & MacDonald are designing and will supervise the construction of the tunnel for the department.

# \$18,250,000,000 Construction Value Seen for 1949

THE most significant changes anticipated for construction in 1949 are divergent trends in public and private construction. It is expected that the value of public construction will increase by close to 25 per cent whereas private construction may decline moderately. Consequently, the total dollar value is expected to increase only slightly over the 1948 rate.

Of an assumed total volume of \$18,250,000,000, public construction could account for as much as \$5,000,000,000. The public portion represents 27 per cent of the total, whereas it was only 23 per cent in 1948. However, this is still considerably short of the close to one-third to total ratio averaged in the two decades prior to the war. It appears that state and local public construction volume at \$3,300,000,000 will considerably outweigh Federal construction estimated at \$1,700,000,000. The following table presents the forecast for 1949 by types of public construction, in comparison with the dollar volume for 1948.

## New Public Construction— Forecast 1949

(millions of dollars)

	Forecast Estimate 1949	1948
TOTAL PUBLIC .....	\$5,000	\$4,050
FEDERALLY FINANCED ..	\$1,700	\$1,350
STATE LOCALLY FINANCED ..	\$3,300	\$2,700
Residential .....	100	60
Nonresidential .....	1,325	970
Educational .....	700	550
Hospital & Institutional ..	325	195
Other .....	500	235
Military .....	200	150
Highways .....	1,750	1,540
Conservation & Development	800	610
Sewer & Water .....	525	460
All Other .....	300	260

The increase in public construction may be traced in part to previous postponements. During the war years, it was to channel men and materials to essential war construction. Since the end of the war, public construction has generally been postponed to favor the greatest possible volume of housing and other needed types of private construction. The latter have made additional demands for public works facilities. As a result, vast needs for public projects have accumulated. It becomes increasingly difficult to postpone further the most essential of these pressing requirements.

This is particularly true of school construction, a category in which a sharp increase in volume is foreseen for 1949. The same situation also holds for public hospital construction. A sizable increase also is expected for conservation and development work, including reclamation projects, river and harbor work, and flood control. Increases are also anticipated for sewer and water and other types of public construction. Highway construction of all kinds—Federally-aided, independent state, city and county work—is estimated at \$1,750,000,000, an increase of nearly 15 per cent over 1948

## Rises Expected in Public Work, Private Projects May Decline

by

J. W. Follin

Assistant Administrator,  
Federal Works Agency

volume. Highway work as a whole represents about 35 per cent of the total volume of public construction, a somewhat smaller percentage than was evident in 1948.

These conclusions are drawn by the Federal Works Agency on the basis of a continuous, day-to-day analysis of current contract awards in all public jurisdictions.

### Physical Volume About the Same

In terms of current dollars, the assumed value of new construction for 1949 appears to set a new record, surpassing even the war years. But in terms of physical volume, 1949 will be about the same as 1948. However, it represents a smaller volume of construction than was accomplished in 1941 or 1942, or in any of the years from 1924 through 1929. New construction averaged close to 11 per cent of national income during the period from 1920-1939. This relationship was closer to 8 per cent in 1949 and will probably not rise above that in 1949.

The dollar volume estimated for public construction in 1949 appears to be a new peacetime high. However, the physical volume, while an increase over 1948, is well below the war years and slightly less than in 1939. This fact points out the continued deferment of a sizable volume of public projects and the actual construction of only the most needed facilities in spite of the accumulated deficits.

### Increased Volume of Public Construction Appears Feasible

Is it possible to step up public construction by nearly 25 per cent in 1949? To answer this question, it is necessary to relate the 1949 estimate to the total demands that will be made upon the construction industry.

In the past few years, lack of materials has been a limiting factor. However, output of almost all building materials has increased at a rapid pace during 1949. We may expect output to increase again during 1949 and to provide larger stocks in the hands of manufacturers and on the shelves of local dealers. Shortages of cement, lumber, and metal projects should

be less widespread and less serious in 1949. Hence, there should be an ample supply of materials for public construction.

Our economy is proceeding in high gear and employment is at record levels; the continuation of prosperity is, of course, assumed in this estimate. The current high level of construction employment, the greater number of active, qualified apprentices, plus an increase in labor productivity—all lead to the belief that the labor situation should not preclude the attainment of the estimated volume of public construction.

Indications are that the peak of private capital expansion has been passed. This raises questions as to the trend of private construction. Is a reduction in the volume of private industrial construction in sight? Will commercial construction slacken its upward movement? Will utilities' construction taper off at less than previously expected highs? Again, would a continued tightening of financing adversely affect the number of housing starts? If the cost situation prevents a drop in the sales prices of housing, does this not indicate a decrease in private housing activity?

### Other Modifying Factors

It is difficult to judge if a public housing program will be authorized in time to permit any considerable volume to be put in place in 1949. Another indeterminate factor is the possible extent of the rearmament program. The discontinuance or expansion of the materials allocations program poses questions, as does any action by Congress on the question of F.O.B. pricing. Many items in the consumers' durable goods category are still in strong demand and in competition with many types of construction for the consumers' dollar. Should over-all prices go upward, many individuals could decide against large-scale or long-term construction commitments. The outlook is that construction costs will continue about the same.

## Alabama Power Program Progresses in 1948

Alabama Power Co. last year made substantial progress on its 120,000-kilowatt steam plant at Gadsden. The first 60,000-kilowatt unit is scheduled to go into operation in March and the second unit, four months later.

Engineering work is under way for the addition to the Gorgas plant in the coal fields of Walker County. This unit will have a capacity of 100,000 kilowatts and upon its completion will make the Gorgas plant the largest in the South.

Engineering work is also under way on a new 40,000-kilowatt unit for the Chickasaw steam plant at Mobile, thus making a total of 282,000 kilowatts of capacity either under construction or in the blue print stage, including the 22,000-kilowatt hydro unit at Mitchell dam.

**WHY YOU CAN**

***Depend***  
**UPON P&H...**

● Whether it's digging, or otherwise handling materials — wherever you see a P&H spearheading a job, you can be sure it's being done with all the dependability that can be built into an excavator. Many of the innovations originated by P&H have been revolutionary. Yet every detail of P&H design and construction is based upon *proved experience*. P&H performance is dependable. This is one of the reasons why more and more users have turned to P&H — why many more will.






**THESE**

**P & H**

**POWERFUL CHAIN CROWD —**  
P&H's Planetary Chain Crowd is simple, positive, dependable. It provides full engine power on every bite. P&H's Crowd Chain will outlast from 25 to 30 crowd cables.

**THE END OF CRAWLER TROUBLE**  
— P&H's true tractor-type crawlers are proved in millions of miles of service — the most efficient ever put on an excavator. They cut time losses, reduce maintenance cost, provide smoother, more dependable travel, easier steering.





**P & H**

**for added values**



**TROUBLE-FREE OPERATING CONTROL**—Direct-acting hydraulic control — the same low-pressure principle used in braking systems for trucks for more than 25 years. Its smooth, velvety action cushions shocks, saves repair bills. It's more **positive, more reliable**

**FRAMES WITHSTAND MORE PUNISHMENT** — P&H originated all-welded excavator design — started building them over 15 years ago. With rolled alloy steels used throughout, they're stronger, tougher, more rigid, without bolted joints — without the penalty of useless deadweight.

You can be sure your excavator investment will be most profitable when you have all the added values built into P&H Excavators. See your nearest P&H dealer or write us for information.

**P&H** EXCAVATORS  
4427 W. National Avenue  
Milwaukee 14, Wisconsin

# HARNISCHFEGER

**HARNISCHFEGGER CORPORATION:**  
PHILADELPHIA 3, Pennsylvania, 546 Broad St., Station Building  
WASHINGTON 5, D. C., 1029 Vermont Ave., N.W.  
JACKSONVILLE 4, Fla., 1287 W. Forsyth St.

ATLANTA 2, Georgia, ..... Blalock Machinery & Equipment Co.  
BIRMINGHAM 1, Alabama, ..... J. J. Kelly Machinery Company  
NASHVILLE 2, Tennessee, ..... McCortley, Johnson & Wardlaw  
MADISONVILLE, Kentucky, ..... Minton Machinery and Supply Company  
CHATTANOOGA, Tennessee, ..... Brooks Equip. & Mfg. Co.  
SOUTH BEND, Indiana, ..... The Lodge Aerial Crane Works  
RALEIGH, North Carolina, ..... J. B. Hunt & Sons  
MIAMI, Florida, ..... Neff-Thomas Machinery, Inc.  
TALLAHASSEE, Florida, ..... Panama Machinery & Supply Company  
KNOXVILLE 2, Tennessee, ..... W. H. Williams & Co.  
SUMMIT, South Carolina, ..... Industrial Equip. Co. of S. Carolina



Above—Left—Construction under way on two 42-inch CMP drainage structure at East End-Fourche Bayou drainage project, Little Rock, Ark. At the right is a Northwest dragline digging the channel.

## Little Rock Flood Control Project Protects Large Industrial Area and City Airport

*Below—Construction of levee across Fourche Bayou, looking upstream.*



**M**ORE than eight million dollars worth of property, including the Little Rock municipal airport, will be protected from floods by the \$886,000 project now being pushed by the Corps of Engineers and involving construction of a compacted earth-fill levee, a concrete floodwall, two pumping stations and a diversion channel at the confluence of the Arkansas River and a tributary stream known as Fourche Bayou.

The design involves seven and one-fifth miles of earth levees with a crown width of 10 feet and one on three slopes, one concrete stop-log structure with a 4,800-foot diversion channel to change the course of Fourche Bayou to a route outside the 2,560-acre protected area, two concrete pumping stations for disposal of interior drainage and sanitary sewage during high-water stages, seven drainage structures and a concrete floodwall approximately 500 feet long.

Authorized by the second session of the 78th Congress, the project dates to just after the great flood of May, 1943, when the Little Rock District now commanded by Col. T. A. Lane, made the investigations which showed the economic justification for the work and subsequently resulted in the recommendation for its construction by the Chief of Engineers.

As outlined by Lt. Col. Kenneth H. Newton, executive officer of the Little

Rock engineer district, the project was divided into three lots for construction and one contract by which the Government furnishes pumps, motors and switch gear for the pumping stations.

Construction of Lot I, consisting of five and one-half miles of compacted earthfill levee, channel clearing, and excavation of a diversion channel, performed under a \$289,800 contract by S. K. Jones Construction Co., of Memphis, Tenn., has been completed. For the hauling and

placing of dirt, the Jones Company used a Northwest dragline, Model 80D, with five 11-yard Euclids, two 15-yard Euclids, and three 18-yard Athley wagons (for short hauls at diversion channel), plus the dozers, motor patrols, and other equipment. The work was accomplished under direction of E. K. Jones, partner of the firm, and J. H. McLaurine, superintendent.

Fairbanks, Morse and Co., of St. Louis, Mo., was awarded a contract September 13, 1948, for furnishing and delivering two 22,500 g.p.m. and two 27,000 g.p.m. pumps and motors and required switch gear for the two pumping stations.

A \$389,182 contract was awarded December 2, 1948 to Ben M. Hogan and Co., of Little Rock, for construction of Lot II. This covers the Gregg Street and Bond Street pumping stations, an L-type reinforced concrete floodwall 506 feet in length, installation of government-owned pumps, completion of the one and one-half mile levee embankment, and a stoplog structure. Lot III, consisting of a pressure relief well, is yet to be let by the Little Rock office, which is represented on the project by J. H. Nowell, engineer in charge of construction.

The levee will have an average height of about 10.5 feet and maximum heights of about 35 feet where it crosses Fourche




(Continued on page 36)

# STANDARD ENGINEER'S CASE FILE



## CASE 1028--MAINTAINING LUBRICATING FILM ON CHASSIS BEARINGS UNDER EXTREME PRESSURES.




In the severest truck and bus service RPM Chassis Grease TB stayed on bearings longer than usual period between grease jobs. Improved product made specially for heavy-duty service. Has distinctive gray color. Comes in three grades: Light, Medium, Heavy.

- A. Contains effective anti-wear ingredient - resists wear and prolongs bearing life.
- B. Cushions bearings against shock loads ... improved stringiness additive keeps film on surfaces - provides high adhesion and cohesion properties.
- C. Heavy oil stock assures tough lubricant film - minimizes galling on large bearing surfaces.
- D. Has excellent pumpability in cold weather - Light grade pumps freely in temperatures down to minus 10°F.

RPM Chassis Grease TB is waterproofed, keeps protective collar at outside edge of shackle bearings.

## CASE 1017--REDUCING OVERHAULS IN GASOLINE ENGINES.



When gasoline engines were lubricated with compounded RPM Motor Oil, pistons, cylinders, valve stems and other oil-contacted parts remained clear of carbon, gum and lacquer. Wear was minimized and rusting was not a problem. Recommended for gasoline and butane engines. Five grades: SAE 10/10W to SAE 50.

- A. Contains detergent which loosens and removes carbonaceous matter, keeps it dispersed in the oil so it is removed with drainings. Assures free-working rings, valves and other parts.
- B. Sticks to hot spots - reduces usual wear on upper cylinders and pistons.
- C. Adherence to cylinders when engine is idle minimizes starting wear and prevents rusting - moisture will not cut through oil film.

Other compounds in RPM Motor Oil resist oxidation, prevent corrosion of bearings, and stop foaming.

# THE AUTOLINE OIL CO.

BALTIMORE, MARYLAND

NORFOLK, VIRGINIA



Trademarks Reg. U. S. Pat. Office



Above—Model E Quick-Way, owned by Howard & Goforth Construction Co., Middlesboro, Ky., digging swimming pool for private residence. It has an International U-9 engine.



Above—Model E Quick-Way owned by Howard & Goforth driving concrete piling for new \$50,000 Coca-Cola building at Middlesboro, Ky. It is powered by an International U-9 engine.

# EQUIPMENT WORK

By L. H. Houck



Above—Schramm air compressor, owned by Emory & Richards, Knoxville, Tenn., at Church Street Methodist Church where American Marble Products Co. made alterations.

Below—No. 160 LeRoi compressor and two 85-pound LeRoi jackhammers in use at Kingsport, Tenn., by Wright & Lopez, Inc., Cedartown, Ga. Job is underground conduit ditches for Intermountain Telephone Co.




Below—Caterpillar No. 12 grader, grading a farm road for a private owner in Virginia.

Below—Buckeye rotary ditcher with Buda engine, owned by Morristown, Tenn., ditching new water mains connecting new sub-division housing.








# *the Balance* IS IN YOUR FAVOR WITH MODERN



## ROAD MACHINERY




Huber's versatile Road Maintainer—a lift loader, berm leveler, bulldozer, patch roller, snow plow, or rotary broom all in one.



Huber's always dependable 3-Wheel Rollers—built in sizes, from 5 to 12 tons, suited to any rolling operation.

Today's conditions demand that your operation's budget balance out. Modern Huber road machinery will help you do better than that—the efficient, result-producing Huber line will actually tip the balance in your favor.

Road men, from maintenance crews to new road contractors recognize the "extras" that are built into every piece of Huber equipment. Plenty of power... economical operation... dependable performance... and the ability to do any job are Huber traits that point to more profitable road operations for you. Write today for bulletins on the Huber equipment that will best serve you.



Huber's highly maneuverable Tandem Rollers lend themselves to many special tasks. Variable weight models from 3 to 14 tons.

### THE MFG. COMPANY • MARION, OHIO, U. S. A.

LEARY & OWENS MACHINERY CO., INC.  
Birmingham, Ala.

LEARY & OWENS MACHINERY CO., INC.  
Montgomery, Ala.

W. C. CAYE & CO.

Atlanta 2, Georgia

DEMPSTER BROTHERS, INC.

Machinery Division  
Nashville, Knoxville, Chattanooga, Tenn.

TRI-STATE EQUIPMENT CO.

Memphis 2, Tenn.

TRI-STATE EQUIPMENT CO.

Little Rock, Ark.

MUNICIPAL SALES CO.

Richmond, Va.

FLORIDA EQUIPMENT CO. OF JACKSONVILLE

Jacksonville, Fla. (3)

FLORIDA EQUIPMENT CO. OF TAMPA

Tampa, Fla.

FLORIDA EQUIPMENT CO. OF MIAMI

Miami, Fla.

THE CHESAPEAKE SUPPLY & EQUIP. CO.

Baltimore 18, Maryland

CHESAPEAKE SUPPLY & EQUIP. CORP.

Hyattsville, Maryland

M. R. HAMELL, INC. (Maintainers only)

Charleston, W. Va.



# Southern Construction Projects

## INDUSTRIAL

(Continued from page 13)

Board plans \$6,830,000 improvements.

**TAHOKE** — Lyntec Electric Cooperative has REA loan, \$515,000, for 358 miles line and system improvements.

## VIRGINIA

**CREWE** — Southside Electric Cooperative has REA loan, \$980,000 for 270 miles line and system improvements.

**RICHMOND** — Chesapeake and Potomac Telephone Co. of Virginia, plans expenditures of \$971,300 for improvement and expansion.

**ROANOKE** — Norfolk and Western Railway plans six improvements, including position lights, \$541,000; engine facilities, \$1,514; terminal and station removal, \$455,000; central traffic control, \$308,000; water supply, \$100,000; wash and locker buildings, \$106,000; warehouse, \$1,700,000.

## Contract Stage

### ALABAMA

**PLEASANT GROVE** — Town let contract to Buchanan & Graves, \$301,702, for natural gas distribution system, Pleasant Grove, natural.

### GEORGIA

**ATLANTA** — Graybar Electric Co. received low bid, \$364,463 from Gilbert Beers, 459 Bishop St., N. W., Atlanta, for office and warehouse building.

### KENTUCKY

**LOUISVILLE** — Louisville Public Library, 4th and York Sts., let contract to Whittenberg Construction Co., 224 S. Floyd St., for altering Kaufman Straus Bldg., 427 S. 4th St.; \$290,000.

### LOUISIANA

**ELIZABETH** — Calcasieu Paper Co., has excavation and foundation work started on \$3,000,000 expansion project, with Brunner Co., Rayne, in charge.

### MARYLAND

**FREDERICK** — Board of Directors of Potomac Edison Co. sold \$5,500,000 bond issue to Halsey, Stuart & Co., of New York, to be used for large-scale capital improvements over next several years.

**VIENNA** — Eastern Shore Public Service Co. of Maryland, 1147 Division St., Salisbury, power plant; \$5,000,000.

*Below—Ground is broken for the \$26,000,000 Garza-Little Elm Dam and reservoir project, Dean Skinner, of Cage and Skinner Construction Co., is shown with Col. B. L. Robinson, under whom the work is being done.*



## MISSOURI

**ST. JOSEPH** — Miller Chevrolet Co., 8th and Sylvan Sts., received low bid from Morris Hoffman, Victor Bldg., Kansas City, at \$268,000 for sales and service building, 8th and Jules St.

## NORTH CAROLINA

**SHALLOTTE** — Brunswick Electric Membership Corp. let contract to Boyle Construction Co., Sumter, South Carolina, \$487,336, for 319.8 miles line.

**UNION COUNTY** — Union Electric Membership Corp., Monroe, received low bid, \$215,335, from E. C. Bridges, Heath Springs, for REA lines and improvements.

## OKLAHOMA

Shell Oil Co. has preliminary construction underway in southwest Missouri and elsewhere for \$30,000,000 pipeline from Cushing, Okla., to Wood River, Ill.

## SOUTH CAROLINA

**ANDERSON COUNTY** — Duke Power Co. will begin construction June 1 on \$15,000,000 steam power generating plant in Anderson County, on Saluda River.

## TENNESSEE

**CENTERVILLE** — Meriwether-Lewis Electric Cooperative let contract to L. O. Brayton & Co., Dyersburg, at \$139,677, for 213.84 miles line.

**COLUMBIA** — Monsanto Chemical Co. let contract to Rust Engineering Co., Pittsburgh, Pa., for scrubbing towers of the new unit, which is a smoke-washing unit to eliminate fluorine gas from the smoke emitted from the local phosphorus plant, \$750,000.

**ROGERSVILLE** — Holston Electric Cooperative let contract to Killore Electric Co., Appleton, Wis., for 186 miles line; \$550,000.

## TEXAS

**BELTON** — The Brazos River Transmission Electric Cooperative, Inc., 902 Amicable Bldg., Waco, received low bid, \$553,480, from E. E. Farrow Co., 6509 Fortnes Park Rd., Dallas, for power plant and contiguous structures, Charter Oak Steam Plant.

**DALLAS** — National Industries Corp. let contract to J. L. Rourke & Co., for warehouse and office building, 6214 Cedar Springs Road for American Thread Co., New York, \$375,000.

**DALLAS** — National Industries Corp. let contract to O'Rourke Construction Co., 1001 W. Commerce, for warehouse and office building for United Motors Service Division of General Motors Corp., \$500,000.

**DALLAS** — E. V. McRight & Co., has contract for office and warehouse, 515 S. Latimer at Central Boulevard for Westinghouse Electric Supply Corp., \$800,000.

**HONDO** — Medina Electric Cooperative, Inc., let contract to H. B. Zachry Co., P. O. Box 4570, San Antonio, \$530,489, for Section 1, 249 miles line; Sisco Electric Co., 200 Chambers St., Conroe, \$272,430, for Section 2, 249 miles line.

**HOUSTON** — Trans-Continental Pipeline Co., M & M Bldg., let contract to Ray Fish Engineering Corp., M & M Bldg., for pipeline stretching from Texas Rio Grande Valley, to New York City; \$200,000,000.

**HOUSTON** — Goodyear Tire & Rubber Corp., LaPorte Road, let contract to Consolidated Western Contractors, Inc., M & M Bldg., Houston, for plant facilities, LaPorte Road, \$500,000.

**SAN ANGELO** — Slick-Urschel Oil Co., San Antonio, let contract to Texas Natural Gasoline Corp., San Antonio, for gasoline plant; \$6,000,000.

**SAN ANGELO** — Plymouth Oil Co. let contract to Hudson Engineering Co., Houston, for gasoline plant; \$6,000,000.

**VICTORIA** — Aluminum Company of America, Port Lavaca, let contract to Smith Dredging Co., Port Lavaca, for dredging of a 100-foot channel to its new \$30,000,000 reduction plant at Point Comfort at Lavaca Bay; Ole Peterson & Son, Houston, has contract for dock project.

## VIRGINIA

**RICHMOND** — Philip Morris & Co., Ltd., Inc., let contract to Wise Contracting Co., Inc., Eighth and Grace Sts., at \$222,112, for tobacco warehouse.

## ENGINEERING

### Proposed Stage

### ALABAMA

**BIRMINGHAM** — City formulating plans for possible conversion of Bays 1 and 2 of the Bechtel-McCone Plant, into an administration building, Municipal Airport, estimated cost from \$500,000 to \$2,000,000.

**BIRMINGHAM** — County Commission will hold special bond election January 25, on \$18,000,000 bond issue for sewer connecting sewer main at Legion Field with Pratt City disposal plant.

### ARKANSAS

**FAYETTEVILLE** — City plans lake and reservoir north of Fayetteville and extend water lines; \$800,000 bond issue voted.

### FLORIDA

**JACKSONVILLE** — City approved \$5,000,000 bond issue for water system improvements.

**TAMPA** — City plans sanitary sewer system, \$10,000,000.

### MARYLAND

**BALTIMORE** — City plans for following projects during 1949:

Sludge drying unit at Back River sewage disposal plant, \$1,000,000;

Dundalk auxiliary pumping station, \$250,000;

Sanitary sewer, \$300,000;

Vall Street interceptor; \$350,000;

Storm-water drains in advance of paving, \$800,000;

Jones Falls force main, \$200,000.

**BALTIMORE** — City plans following projects during 1950:

Pressure sewer, \$1,000,000 and \$175,000

gravity sewer in Western Run and Jones Falls;

Preliminary settling tank at Back River plant, \$500,000;

Eastern Avenue turbo-driven centrifugal pump, \$200,000;

Miscellaneous storm water tank to improve drainage conditions, \$100,000;

Storm-water work in advance of paving, \$600,000;

Improvements to Gwynns Falls' sewers, \$200,000.

**BALTIMORE** — City plans following sewer projects during 1951:

Storm water work in advance of paving, \$300,000;

Storm water drain at Allendale Road and North Clifton Avenue, \$150,000;

Low level interceptor for eastern section, \$100,000.

**BALTIMORE** — City plans expenditure of \$240,000 during 1949, \$300,000 in 1950 and \$200,000 in 1951 for modernization of Montebello Filters, using day labor.

**BALTIMORE** — City plans following projects:

Small mains in advance of paving of \$700,000;

48-inch main in Mount Royal and Freeman Avenues, cost \$750,000;

36-inch main in Ensor Street, \$250,000;

In 1950 to expend \$700,000 for small mains in advance of paving, and in 1951, \$600,000.

**BALTIMORE** — City contemplates completion of the Lake Montebello Water Tunnel, to continue its work to complete a large dam on the stream to supplement the Gunpowder Falls supply; in 1949, \$300,000 will be available for land acquisition for new reservoir, in 1950, \$800,000, and in 1951, \$375,000.

**BALTIMORE COUNTY** — Baltimore County plans \$400,000 sewer installation program.

### TENNESSEE

**KNOXVILLE** — Knoxville Utilities Board plans \$1,200,000 water system expansion program.

**NASHVILLE** — R. L. Lawrence, Jr., Director of Waterworks Department, approved \$4,000,000 bond issue for extension and improvement of city waterworks system.

### TEXAS

**BEAUMONT** — City approved \$1,000,000 bond issue for improvements, extensions and repairs to water facilities.

**FORT WORTH** — City plans water mains.

(Continued on page 44)



**Make Plans Now**

**To Attend the**

# **American Road Builders' Association**

## **CONFERENCE and 46th ANNUAL MEETING**

**WASHINGTON, D. C.**

**February 7-8-9, 1949**

**Headquarters and Sessions**

**at**

**MAYFLOWER HOTEL**

Airport Division  
All Technical Committees



**WILLARD HOTEL**

County Highway Officials' Division  
Municipal Division  
American Institute of Local  
Highway Administration



**STATLER HOTEL**

Contractors' Division  
Manufacturers' Division

**BE INFORMED — KEEP UP WITH THE NEWEST DEVELOPMENTS IN  
HIGHWAY AND AIRPORT CONSTRUCTION AND MAINTENANCE.**

**Technical Sessions — Soils Conference — Reports**

**Business Meetings of Divisions — Forums — Addresses**

**Luncheon Meetings Daily — Annual Banquet, February 8, 1949**

**REMEMBER —** Following the inauguration, the Nation's Capital will be full of visitors. Don't delay! To be sure of accommodations, write or wire today for detailed information and official hotel application blanks.

**AMERICAN ROAD BUILDERS' ASSOCIATION**

**International Building**

**WASHINGTON 4, D. C.**

# Southern Construction Projects

## ENGINEERING

(Continued from page 42)  
from Holly Plant to South Side Pump Station, \$509,800.

**SWEETWATER** — City plans dam on Oak Creek in Cooke County and 30 miles of connecting pipeline; \$2,500,000 water bond issue voted.

**WACO** — Baylor University plans stadium, \$1,000,000.

## VIRGINIA

**ALEXANDRIA** — Alexandria Water Co. of Alexandria, plans \$1,500,000 bond issue for refunding outstanding indebtedness, construction, completion and extension of facilities.

**NORFOLK** — City plans to hold special bond election on \$6,250,000 bond issue for water system improvements.

**PORTSMOUTH** — City plans \$1,700,000 sewage disposal plant.

## WEST VIRGINIA

**WHEELING** — Corps of Engineers, Pittsburgh, Pa., plan a \$2,000,000 floodwall and super-highway between Warwood and Benwood.

## Contract Stage

## FLORIDA

**ORLANDO** — City let contract to Ivy H. Smith Co., Jacksonville, \$972,848, for sewage treatment plant.

**TAMPA** — Corps of Engineers, P. O. Box 4970, Jacksonville, let contract to Standard Dredging Co., 80 Broad Street, New York, \$257,510, for construction of dredging in Tampa Harbor.

## GEORGIA

**AUGUSTA** — City sold \$1,850,000 bond issue to Rhyth and Co., 14 Wall St., New York, N. Y., for sewerage expansion and street improvements.

## KENTUCKY

**OWENSBORO** — Owensboro-Davies County Airport Board let contract to Green Construction Co., Owensboro, at \$603,183, for improvements to airport.

## LOUISIANA

**BATON ROUGE** — East Baton Rouge Parish Police Jury received low bids for sanitary sewerage system for sewerage district no. 9 and also for sanitary sewer improvements in Pitchfork sub-division; Red River Construction Co., Shreveport, sections A & B, \$25,600; section C, clay pipe, \$164,916; and concrete, \$162,280; Cormica Construction Co., for Pitchfork sub-division.

**RAPIDES PARISH** — Corps of Engineers, New Orleans, received low bid from Pioneer Contracting Co., Inc., Dyersburg, Tenn., \$375,540, for 2,845,000 cu. yds. of material from the Diversion Channel Bayous, Bouff-Coeudrie, and channel realignment and excavation from Bayous Bouff.

## MARYLAND

**BALTIMORE** — Board of Estimates let contract to Chesapeake Supply and Equipment Co., 1213 E. 25th St., \$877,300 for Contract No. 374, constructing and completing Humus Tank improvements, Back River Sewage Treatment Plant.

## MISSOURI

**NEW MADRID** — Corps of Engineers, Memphis, let contract to McCarthy-Pohl Contractors, Inc., 4903 Delmar Blvd., St. Louis, \$1,021,829, for St. John's Bayou Floodgate Structure.

**ST. LOUIS** — Corps of Engineers, received low bid from Batzle Electric Co., 1807 S. 1st St., Minneapolis, Minn., \$955,300, for installation of power control and lighting system for Locks No. 27, Mississippi River, Chain of Rocks Canal Project.

## OKLAHOMA

**TULSA** — City let contract to Pennington and Winters, 2011 Apco Tower, Oklahoma City, \$284,770 for sewer and force-mains; Roberts and Scisson, Tulsa, \$149,963 for pump station.

## TENNESSEE

**CHATTANOOGA** — City let contract for Div. 1 to Nello L. Tew Company, Durham, N. C., at \$1,078,369, Div. 2 to Dave L. Brown Construction Co., Chattanooga, at \$800,000 and for Div. 3 to William S. Anderson Electric Co., Charleston, S. C., at \$70,421, for improvements to Lovell Field.

**NASHVILLE** — Public Works Director, Warren A. Collidge, let contract to J. B. Michael & Co., Memphis, \$286,961, for storm sewers in Sylvan Park.

**OAK RIDGE** — Atomic Energy Commission let contract to W. L. Halley & Co., 314 32nd Ave., Nashville, \$800,056, for new 30-inch water main to Jackson Square and Road H-1 and connections.

## TEXAS

**FREESPORT** — Corps of Engineers, 606 Santa Fe Bldg., Galveston, received low bid from Continental Construction Co., Port Lavaca, \$949,925, for steel sheet piling guide walls, Gulf Intracoastal Waterway, Road-gates at Brazos River Diversion Channel.

**HOUSTON** — City Council let contract to Russ, Mitchell, Inc., & Wyche & Bruce, P. O. Box 8858, Houston, \$568,306 for North Side sewage treatment plant enlargement, Contract No. 2.

**PASADENA** — City Council sold \$880,000 bond issue to Fridley and Hess of Houston, for public improvements; includes \$450,000 for water and sewer improvements.

**SAN ANTONIO** — City let contract to Reising Construction Co., Edinburg, \$624,442 for many city outfall sewer.

Corps of Engineers, Galveston, received low bid from Russ Mitchell, Inc., and Wyche & Bruce Construction Co., 2394 Old Spanish Trail, Houston, \$1,399,952, for spillway and outlet works, Grapevine Dam and Reservoir, Denton Creek, Trinity River and Tributaries.

## HIGHWAYS, BRIDGES

## FLORIDA

**ST. PETERSBURG** — Board of County Commissioners let contract to W. H. Armstrong & Co., 357 Scotland St., Dunedin, \$1,011,038, for Bellair Beach causeway.

**TALLAHASSEE** — State Road Department received low bids for projects in following counties:

**Pinehas** — Grading and draining 7.13 mi. of Rd. 55, and construction of an overpass at Coachman; H. E. Wolfe Construction Co.,

*Below—Col. David W. Heiman has been assigned to St. Louis as assistant to Col. Clark Kittrell, division engineer of the Upper Mississippi Valley division of the Corps of Engineers. He replaces Col. Richard Lee, who was recently transferred to the Missouri River division to become district engineer of the Fort Peck district.*



St. Augustine, \$333,351.

**Dade** — Grading and draining 7 mi. of Rd. 9 and constructing 2 concrete and steel bridges between Opelucka and Broward county line; H. E. Wolfe Construction Co., \$588,905.

**Orange** — Clearing, grading and grubbing 3.12 mi. of Rd. 539, Hubbard Construction Co., Orlando, \$149,082.

**Alachua** — Paving 1.81 mi. of Rd. 26; Duval Engineering & Contracting Co., Jacksonville, \$129,042.

**Leon** — Hard-surfacing 52.14 mi. of rural Rds.; A. E. Rich Co., \$303,289 and C-E Construction Co., Lakeland, \$262,229.

**Bradford** — Paving 4 mi. of Rd. 18 and constructing 3 concrete box culvert bridges between Hampton and State Rd. 100; James H. Craggs Construction Co., Ocala, \$127,716.

**Taylor** — Grading and draining 10.27 mi. of Rd. 14 and constructing 2 concrete box culvert bridges between Erida and Madison County line; J. D. Manly Construction Co., Leesburg, \$225,748.

**Gilchrist** — Paving 10.42 mi. of Rd. 337 and 6.93 mi. of Rd. 340; Caddell & Jackson, Jacksonville, \$227,269.

**Dixie** — Paving 12.92 mi. of Rd. 349 and 4.5 mi. of Rd. 357; C-E Construction Co., Lakeland, \$481,417.

**Brevard** — Paving 10 mi. of Rd. 3 between Tropic and Georgiana; C-E Construction Co., \$189,252.

**Suwannee** — State Rd. No. 49, roadway, small drainage structures and incidental items; J. D. Manly, Leesburg, \$167,879.

## GEORGIA

**BRUNSWICK** — City let contract to Tide-water Construction Co., Norfolk, Va., \$2,234,210, for reconstruction of existing Brunswick-St. Simons Island Causeway.

## KENTUCKY

**FRANKFORT** — Department of Highways let contracts for projects in the following counties:

**Jefferson** — Louisville inner belt line road, 2,389 miles, grading, drainage and high type surface; Kelly Contracting Co., Louisville, \$175,382.

**Wyane** — Monticello Albany Road, bridge and approaches at Otter Creek; R. R. Dawson Bridge Co., Bloomfield, \$227,714; bridge and approaches at Beaver Creek, Willmer Contracting Co., Winchester, \$221,580.

**Daviess** — Bridge and approaches, Owensboro-Henderson Road; Clarksville Contracting Co., Clarksville, Tenn., \$122,340.

**Pike** — Bituminous concrete pavement on half-mile of Pikeville-Williamson Rd.; Nally & Ballard, Inc., Bardstown, \$165,855.

## LOUISIANA

**BATON ROUGE** — Carnegie & Smith, 3000 A. Dalmayre Dr., Const. Engr., let contract to W. H. Patterson & Co., \$125,337 for street paving and necessary storm sewers for Bellair Subdivision.

**BATON ROUGE** — Department of Highways let contract for projects in following parishes:

**Plaquemines** — Paving 8.7 mi. of Live Oak-Myrle Grove Hwy.; W. R. Aldrich & Co., \$556,437.

**Ascension** — Blacktopping 6.4 mi. of Darrou-Sorrento Hwy.; Carruth Contracting Co., \$247,280.

**LaSalle** — Blacktopping about 2.5 mi. of Nelo Summerville Rd.; J. J. and J. W. McKelhen, Columbia, \$122,353.

**BATON ROUGE** — Louisiana Department of Highways received low bid for projects in the following parishes:

**Iberville** — State Project No. 50-06-10; bridge consisting of 4-30' I-beam spans, 1-30' steel tower span, 1-150' vertical lift span; grading, small drainage structures, portland cement concrete pavement; Austin Bridge Co., Dallas, Texas, \$670,884.

**Plaquemines** — State Project No. 62-05-13; bridge and approaches at Empire on the New Orleans Fort Jackson Highway; W. R. Aldrich & Co., Baton Rouge, \$412,968.

**Iberia** — New Iberia-Lafayette Hwy., State Rd. No. 56, 4.297 mi. of grading, drainage structures; Foreman James Co., Box 911, \$284,228.



**SHREVEPORT** — City Council plans \$750,000 Allen-Batzell-Linwood overpass; E. M. Freeman and Associates, Engrs., Shreveport.

## MARYLAND

**BALTIMORE** — City, Thomas D'Alessandro, Mayor, plans following road projects in 1949:

Extension of Druid Hill Ave. to Centre St., \$500,000.

(Continued on page 46)



## CEMENT IS CHEAP

Any way you look at it, cement gives you more for your money.

Latest available figures\* from the U. S. Bureau of Labor Statistics show that since 1926 the price of cement has gone up only 33.3%—*less than half* the 68.5% increase in the prices of all commodities.

Despite rising costs on every hand, cement still is *cheap*!

\*September, 1948

**Today, more than ever, cement is your best buy!**




**PORTLAND CEMENT COMPANY**  
 Chattanooga Bank Building • • • Chattanooga 2, Tenn.

*Portland — High Early Strength — Air Entraining — Masonry*



# Southern Construction Projects

## HIGHWAYS, BRIDGES

(Continued from page 44)

Extension of Mulberry and Franklin Sts., \$800,000.

Acquisition of property for the widening of Howard St., from Madison St. to Biddle St., \$1,000,000.

Paving of St. Paul St., from University Parkway to Charles St., est. \$300,000.

Paving of new streets under agreements by which builders of housing pay half of cost, \$700,000.

**BALTIMORE**—City, Thomas D'Alessandro, Mayor, plans work to start 1950 for Colgate Creek bridge extension of Broening Highway, including draw span and approaches, \$1,000,000.

**BALTIMORE**—State Roads Commission, 105 E. Lexington St., let contract for following project:

Contract No. B-578-2-415, grading and drainage of a section of York Rd. relocation; Dutcher Construction Co., Queenstown, \$755,192.

**BALTIMORE**—State Roads Commission, 105 E. Lexington St., let contract to Nello L. Iyer Co., Durham, N. C., for eastern approaches to the Chesapeake Bay Bridge; C. J. Langenfelder & Son, Inc., Baltimore, for eastern approaches to the Chesapeake Bay Bridge.

**BALTIMORE**—State Roads Commission received low bids for projects in following counties:

**Anne Arundel**—Contract No. AA-392-1-358; grading, drainage and surfacing of dual hwy. along Friendship International Airport Rd., 0.582 mi.; Wilnot Paving Co., Washington, D. C., \$199,471.

**Somerset**—Contract No. S-156-1-115; grading, drainage and surfacing of a relocated section of the Westover-Marion Rd., State Rt. No. 413, 7.620 mi.; C. J. Langenfelder & Son, \$127,945.

**Caroline-Queen Annes**—Contract No. CQ-173-2-215; two steel beam and concrete bridges; one over Norwich Creek and one over Tuckahoe Creek on the new Queen Anne Hillsboro bypass; both of the bridges are to be supported on precast concrete pile.

**Caroline-Queen Annes**—Contract No. CQ-173-2-215; two steel beam and concrete bridges; one over Norwich Creek and one over Tuckahoe Creek on the new Queen Anne Hillsboro bypass; both of the bridges are to be supported on precast concrete pile.

**Queen Anne-Anne Arundel**—Contract No. CBA-7-1-57; construction of filled causeway approximately 2,283' long and 50' wide across the top, consisting of hydraulic fill retained by stone riprap to form a part of East Approach to the Chesapeake Bay Bridge, the dredging of channel 2,200' long and 200' wide; William A. Harting, Landowne, Md., \$554,250.

## MISSISSIPPI

**JACKSON**—State Highway Commission let contracts for projects in following counties:

**Clarke**—4.573 mi. grading, drainage structures, bridge, stabilized base and double bituminous surface on Hwy. No. 18; Pigford Brothers Construction Co., Meridian, \$229,165.

**Humphreys**—4.750 mi. grading, drainage

structures, gravel surface course and bridges of county hwy.; Gerald Smith Construction Co., \$189,619.

**Copiah**—12.706 mi. grading, drainage structures and bridges on Hwy. No. 20; Anderson-Gregory Co., Inc., Nashville, \$274,169.

**Bolivar**—10.865 mi. grading, drainage structures, gravel surface and box bridges on County Hwy.; Gerald Smith Construction Co., Memphis, \$172,563.

**Attala**—11.562 mi. grading, drainage structures and box bridges on Hwy. No. 35; Anderson-Gregory Co., Inc., Nashville, \$314,746.

**Grenada and Calhoun**—3.848 mi. grading, drainage structures on Hwy. No. 8; Pigford Brothers Construction Co., Meridian, \$568,115.

**MADISON COUNTY**—Public Roads Administration, 365 Medical Arts Bldg., Florence, Ala., received low bid from Smith Engineering and Construction Co., Pensacola, Fla., \$323,785, for Proj. 3X6, 3-0-6, Part B, Natchez Trace Parkway.

## MISSOURI

**JEFFERSON CITY**—State Highway Commission let contracts for projects in the following counties:

**Jackson**—Federal Project No. T1-88(2)A; 0.560 bridge substructure; J. E. Dunn Construction Co., Kansas City, \$647,429.

**Jackson**—Federal Project No. T1-88(2)B; 0.560 bridge superstructure; American Bridge Co., St. Louis, \$1,708,465.

**ST. LOUIS**—City, Milton M. Kinsey, Pres., 301 City Hall, received low bid from Fred Weber Contractor, Inc., 7929 Alabama, \$140,024, for letting No. 5204, improving proposed Gustine Ave.

## NORTH CAROLINA

**RALEIGH**—State Highway Commission received low bids for projects in the following counties:

**Nash-Edgecombe**—Grading soil type base course, concrete pavement and structures of 1.14 miles on U. S. 301; T. E. Brown, Charlotte, roadway, \$121,281; Bowers Construction Co., Raleigh, structures, \$128,652; Curtis L. Rogester, Scotland Neck, moving buildings.

**RALEIGH**—State Highway Department let contracts for projects in following counties:

**Cumberland**—Proj. 3363, etc., roadway and structures; Ziegler-Cline Construction Co., Fayetteville, \$148,804.

**Buncombe**—Proj. 0-154; Suber & Co., Inc., Whitmore, S. C., \$124,166.

**Harnett-Johnston**—Proj. 4387; Boyie Construction Co., Sumter, S. C., \$114,701.

**Jackson**—Proj. 5514; Asheville Paving Co., Asheville, \$120,220.

**Henderson**—Projs. 8280 and 8361; Dickerson Inc., Monroe, \$294,669.

**Buncombe**—3.28 mi. of grading, surfacing and structures, along N. C. 197; H. R. Stewart, \$110,000.

**Pitt Greene**—Proj. 1520; Exum-Cline Construction Co., Rocky Mount, \$151,887.

**Orange**—Proj. 5-351; Kiker & Yount, Reidsville, \$116,659.

## OKLAHOMA

**OKLAHOMA CITY**—State Highway Com-

mission let contracts for projects in following counties:

**Greer**—SH 34, 3.880 mi. grading, drainage, multiple box culvert; H. D. Youngman, Oklahoma City, \$39,222; also SH 34, 6.797 mi. same type of construction beginning 4 mi. north of Jackson-Greer county line; H. D. Youngman, \$69,172; also SH 34, 3.887 mi. stabilized aggregate base, asphalt surface beginning at Jackson-Greer county line; H. D. Youngman, \$132,700; and SH 34, 6.797 mi. same type of construction beginning 3.887 mi. north of Jackson-Greer county line; H. D. Youngman, \$234,442.

**Garfield**—SH 74, 1.554 mi. grading and drainage; S. E. Evans Construction Co., Fort Smith, Ark., \$27,392; also SH 74, 0.639 mi. bridges, 1 multiple box culvert and 3-60 ft. I-beam span structures, same location; R. R. Tway, Inc., Oklahoma City, \$94,636; and SH 74, 7.690 mi. grading, drainage, 4 multiple box culverts beginning 1.593 mi. north of Logan-Garfield county line; Evans Construction Co., \$132,743.

**Johnston**—SH 12, 6.996 mi. grading, drainage, multiple box culvert beginning at Ravia; S. E. Evans Co., Fort Smith, Ark., \$67,397; also SH 12, 7.739 mi. same type of construction beginning 6.888 mi.; S. E. Evans Co., \$121,977.

**McClain**—SH 74, 5.563 mi. grading, drainage, 2 multiple box culverts beginning at South Canadian River bridge; P & H Construction Co., Oklahoma City, \$130,988.

**Tulsa**—2.613 mi. grading, minor drain structure, bridges 0.077 mi. in length, 35.7 mi. on U. S. 66; Standard Paving Co., Tulsa, \$463,305.

## SOUTH CAROLINA

**COLUMBIA**—State Highway Commission, C. R. McMillan, Commr., plans a dual lane highway from Aiken to Savannah River, approx. \$2,000,000, a distance of 17 mi. and including another bridge across the Savannah.

**COLUMBIA**—State Highway Department let contracts for projects in following counties:

**Newberry**—S. C. Docket 36,223; Spotts & Co., Newberry, \$454,750.

**Aiken-Orangeburg**—Dockets 2, 262, etc. (road work); W. M. Reagan & Sons, Inc., Wentworthville, \$150,367.

**COLUMBIA**—State Highway Department received low bids for projects in following counties:

**Aiken**—Grading and drainage on U. S. Rt. 1 of 10.892 mi. for a dual lane roadway; Robert Lee, Inc., Manning, \$463,662.

**Anderson-Greenville**—Grading and bituminous surfacing of 1.969 mi. of Rd. 143 and 4.78 mi. of Rd. 84; Hines, \$111,106.

**Dillon**—Grading and bituminous surfacing of 2.419 mi. of Rd. 50, 5.197 mi. of Rd. 60 and 2.193 mi. of Rd. 28; American Construction Co., Columbia, \$118,192.

**Fairfield**—Grading and bituminous surfacing of 4.334 mi. of Rd. 19 from Rd. 27 by way of Kila to Rt. 119; Hines, \$128,867.

**Oconee**—grading and bituminous surfacing of 7.198 mi. of Rd. 37 and 1.514 mi. of Rd. 115; Dickinson, Inc., Monroe, N. C., \$137,893.

**Florence**—Grading and bituminous surfacing of 2.603 mi. of Rd. 47, 3.46 mi. of Rd. 36 and 2.023 mi. of Rd. 67; Robert Lee, Inc., \$124,331.

**Horry**—Grading and bituminous surfacing of 6.171 mi. on Rd. 33 and 3.492 mi. of Rd. 45; Hubbard Construction Co., Marion, \$134,515.

**Lancaster**—Grading and bituminous surfacing of 5.388 mi. of Rd. 25, 0.291 mi. of Rds. 20 and 40, 2.733 mi. of Rd. 42 and 1.374 mi. of Rd. 54; Blankenship Brothers, Charlotte, \$223,899.

**Lexington**—Grading and bituminous surfacing of 6.503 mi. of Rds. 9 and 35, 2.267 mi. of Rd. 101 and 0.763 mi. of Rds. 119, 125 and 129 and 179; American Construction Co., \$125,265.

**Spartanburg**—Grading and bituminous surfacing of 3.140 mi. of Rd. 31 to Rd. 46 near Cowpens, 1.343 mi. of Rd. 96 to Rd. 2 and 4.161 mi. of Rd. 43 to Rd. 58 near Buck Creek School; Dickinson, Inc., \$119,834.

## TENNESSEE


**NASHVILLE**—State Highway Department let contracts for projects in following counties:

**Shelby**—Concrete pavement for U. S. 51 from the Mississippi state line to end of concrete pavement north of Whitehaven; Bowyer & Johnson, Jackson, \$633,582.

**Tipton-Haywood**—Resurfacing with bituminous materials of U. S. 50 from the Tipton-Fayette county line to Brownsville; Memphis Stone & Gravel Co., Memphis, \$734,717.

**Maury**—Bowyer & Johnson, Jackson, \$212,711.

**NASHVILLE**—State Highway Department



Cedarapids Pitmaster Gravel Plant crushing and sizing gravel in Missouri. Owner is John D. Petrik, of Iberia, Missouri.

received low bids for projects in following counties:

**Sullivan**—Grading, drainage and bridges on 3.2 mi. of State Rt. 1; A. B. Burton, Lynchburg, Va., \$268,067.

**Jefferson**—Grading, drainage and bridges on 7.6 mi. of State Rt. 34; Ralph Mills, Inc., Franklin, Ky., \$477,080.

**Rutherford**—Construction of bridges over Stewart Creek, Overall Creek and Stones River on State Rt. 1; C. F. Rule Construction Co., Nashville, \$430,555.

**White**—Grading, drainage, bridges and concrete paving of 1.2 mi. of State Rt. 1; Stacy Brothers Co., Johnson City, \$579,227.

**Grundy**—Grading, drainage, base and surfacing of 3.1 mi. of secondary No. 4325; Brown Brothers, Chattanooga, \$123,267.

**Marshall-Williamson-Rutherford**—Proj. No. 523-E, widening and resurfacing with bituminous material of section of State Rt. No. 11, 18, 123 mi.; Ralph Rogers Co., Nashville, \$390,796.

**Williamson-Davidson**—Proj. No. 523-F, widening and resurfacing with bituminous material of section of State Rt. No. 11, 25.24 mi.; Wright Construction Co., Columbus, Ga., \$485,721.

**Knox**—Extension of arch bridge and paving with concrete of Broadway between Grainger and Cecil; J. B. Michael Co., Memphis, \$107,591.

**Marion**—Paving with concrete State No. 2 near Martin Springs and Montague; Wright Contracting Co., Columbus, Ga., \$16,506.

**Wilson**—Grading and drainage, including 3 bridges and surfacing with crushed stone secondary Rd. No. 161, Marion Construction Co., \$108,225.

**Landon**—Grading, drainage and paving with concrete of 1.5 mi. of Broadway in Lenoir City; Wright Contracting Co., \$345,694.

**Sumner**—Paving with concrete State No. 6; J. B. Michael Co., \$463,173.

**Knox-Jefferson**—Grading and drainage including extension of box-type bridge on State No. 34; Pullen & Owens, \$198,137.

**Shelby**—Construction of underpass and approaches at Southern Railway crossing on Iowa Ave, Construction Co., Memphis, \$430,676.

**Hamilton**—Grading, drainage and paving with concrete of State No. 2, on Brainerd Rd. in Chattanooga for 2 mi.; Foster & Creighton, \$654,672.

**Hamblen-Hawkins-Greene**—Widening and resurfacing with bituminous materials State No. 34 for 40 mi.; Wesco Paving Co., Chattanooga, \$784,502.

**Rhea-Roane**—Widening and resurfacing with bituminous materials 35 mi. of State No. 29; Wesco Paving Co., \$723,800.

**Marshall**—Grading, drainage, including 5 bridges, and surfacing with crushed stone, State No. 11; R. E. Martin, \$415,504.

**Sevier**—Grading, paving and drainage of 44 mi. of State No. 71 in Gatlinburg; Stacy Brothers Co., Johnson City, \$235,475.

**Anderson**—Grading, drainage and paving with bituminous concrete 2 additional traffic lanes and resurfacing of existing pavement on 3.7 mi. of State No. 9 near Clinton; R. B. Tyler Co., Louisville, Ky., \$657,135.

## TEXAS

**AUSTIN**—State Highway Department plans projects in following counties:

**Webb**—State Hwy. 202 from 22 mi. north-east of Laredo to Duval County line, approx. 24 mi., estimated cost \$240,000.

**Duval**—State Hwy. 202 from Webb County line to Freer, approx. 13.4 mi., estimated cost \$134,000.

**Trinity**—Three state-to-market hwy., \$142,400.

**Webb**—46 mi. of construction authorized on State 202 near Laredo, \$460,000.

**Brewster**—20 mi. of construction on State 118 south of Alpine, \$210,000.

**AUSTIN**—State Highway Commission let contracts for projects in following counties:

**Karnes**—Proj. No. V 1121-1-1, Hwy. FM 792; Killian-House Co., P.O. Box 1981, San Antonio, \$136,533.

**Andrews**—Proj. No. V 1127-1-1, Hwy. No. FM 781; Ernest Loyd, P.O. Box 1120, Fort Worth, \$190,439.

**Harris**—Proj. No. F1 324-1, Hwy. US 75; R. P. Farnsworth & Co., P.O. Box 74, Houston, \$170,549.

**Rusk**—Proj. No. F 203 (11), Hwy. US 79; E. W. Habbe & Sons, Corsicana, \$265,817.

**Duval**—Proj. No. 8 401(2), Hwy. St. 202; W. S. Crawford Co., 4817 Montrose Blvd., Dallas, \$124,869.


**Jasper and Orange**—Proj. No. V 710-1-1, etc., Hwy. FM 113; John F. Buckner & Sons, P.O. Box 76, Cleburne, \$140,267.

**Concho**—Proj. No. V 570-4-1, Hwy. FM 765; Thomas & Ratliff, Rogers, \$10,192.

**Denton**—Proj. No. C 353-2 10, Hwy. St. 114;

(Continued on page 48)

# Why the LIMA Type 604 develops the greatest capacity per lb. of weight



Main machinery of LIMA Type 604, showing position with relation to center of rotation.

More than two-thirds of the cab and all of the main machinery are well back of the center of rotation for maximum counterbalancing effect.

● The LIMA Type 604 shovel, crane and dragline is engineered to produce greatest capacity with minimum weight. This is achieved by placing as much weight as possible behind the center of rotation—eliminating the need for excessive counterweight. Hook rollers on which the machinery base revolves eliminate strain from the center pintle—permitting continuous, safe operation at full capacity.

The simple, compact design of the main machinery, using the fewest number of shafts to accomplish the various operations, further contributes to efficient, trouble-free service.

These are only a few of the features which make the LIMA 604 a favorite with owners and operators. The Lima Line includes shovels  $\frac{1}{2}$  to 6 yards, Cranes 13 to 110 tons and Draglines variable.

## LIMA EQUIPMENT SOLD AND SERVICED BY

OUR DALLAS OFFICE: 1304 McKinney Avenue, Dallas, Texas  
OUR MEMPHIS OFFICE: 79 McCall Street, Memphis, Tennessee

### Sales Agents:

Albuquerque, N. Mex., Contractors Equipment & Supply Co., Springer Building  
Baltimore 3, Md., Henry H. Meyer Co., Inc., 110 S. Howard St.  
Baton Rouge, La., General Equipment Inc., 435 Richland Ave.  
Birmingham, Ala., G. C. Phillips Tractor Co., 1909½ First Ave. No.  
Clarksburg, W. Va., West Virginia Mine Supply Co., Box 872  
El Paso, Tex., Contractors' Equipment & Supply Co., 1420 Myrtle St.  
Fort Smith, Ark., R. A. Young & Son, Inc., 301 So. 10th St.  
Houston 1, Tex., McCall Tractor & Equipment Co., 3714 Navigation Blvd.  
Kansas City 8, Mo., Buchanan Co., 1710 Grand Ave.  
Knoxville 1, Tenn., Martin Machinery & Supply Co., 4100 Chapman Highway  
Louisville 2, Ky., Emmett C. Watson, Seelbach Hotel  
North Little Rock, Ark., R. A. Young & Son, Inc., 900 W. 2nd St.  
Palatka, Fla., McLean Machinery Co., 220 N. 7th St.  
Roanoke, Va., J. W. Burress, 1701 Shenandoah Ave. N.W.  
San Antonio, Tex., Acme Iron Works, Colebra Ave. at Expressway N.W.  
Savannah, Ga., Morgan's, Inc., 111 W. Broad St.  
Stevensville, N. C., Interstate Equipment Co., West Bldg.  
St. Louis 10, Mo., E. F. Marsh Co., 4030 Chouteau Ave.  
Tyler, Tex., D. M. McClure Equipment Co., 1321-26 W. Erwin St.  
Waco, Tex., Richards Equipment Co., 910 Franklin St.

## Lima Shovel and Crane Division

LIMA, OHIO

OTHER DIVISIONS: Lima Locomotive Works Division; Miles Tool Works Co.; Hooven, Owens, Rentschler Co.



# Southern Construction Projects

## HIGHWAYS, BRIDGES

(Continued from page 47)

**Public Construction Co., P.O. Box 380, Denton, 804,410.**

**Pala Pinto**—Proj. No. F 414(3), Hwy. US 281; Wallace & Bowden, 5513 E. Grand Ave., Dallas, \$190,967.

**Conike**—Proj. No. F1 214(7), Hwy. F 87; Worth Construction Co., P.O. Box 531, Fort Worth, \$642,280.

**Freestone**—Proj. No. S 1111 (1), Hwy. FM 188; W. O. Polphrey, 1714 Electric Bldg., Fort Worth, \$135,951.

**Ector**—Proj. No. F 235 (6), Hwy. F 80; H. L. Butler & Son, P. O. Box 7112 Dallas, \$170,907.

**Mason**—Proj. No. F 203 (2), Hwy. F 87 and St. 151; Dean Word Co., P.O. Box 351, New Braunfels, \$240,371.

**Wheeler**—Proj. No. F41 (15), Hwy. F 86; Bell, Braden, Barker & Gilvin, Inc., Herring Hotel Bldg., Amarillo, \$103,003.

**Moore and Hartley**—Proj. No. V 727-6-1, Hwy. No. FM 721 & 722; Bryan & Hoffman, 421 Seages Bldg., Plainview, \$235,535.

**Karnes**—Proj. No. V 1122-1-1, etc., Hwy. No. FM 791 and 744, H. R. Henderson & Co., P.O. Box 313, Marshall, \$114,063.

**Jim Hogg**—Proj. No. S 329-1-1, Hwy. FM 649; Thomas & Ratliff, Rogers, \$104,131.

**Bee**—Proj. No. F 451 (9), Hwy. No. US 59; Southern Contracting Co., 1801 Meadow Brook Dr., Austin, \$144,816.

**Case**—Proj. No. S 1023(1), Hwy. No. FM 250; Dew Construction Co., Inc., P.O. Box 641, Tyler, \$170,778.

**Swisher and Belcon**—Proj. No. V 357-6-1, etc.; Hwy. No. FM 146; R. W. McKinney, P. O. Box 190, Nacogdoches, \$146,963.

**FORT WORTH**—City, W. O. Jones, Mgr., received low bid from Brown & Root, Inc., \$125,974, for paving on West Rosedale Ave.

**HOUSTON**—City, M. H. Westerman, Sec., let contract to Russ Mitchell, Inc., 2302 Jefferson St., \$163,960, for relocating and paving South Houston-Garden Villas Rd., approx. 17 mi.

**LULING**—City, John N. Brigrance, Mayor, plans street improvements, \$500,000.

## VIRGINIA

**RICHMOND**—State Highway Department received low bid for projects in following counties:

**Nelson**—U.S. 29 and State Rt. 6, 1.12 mi. of new meadow Rd. and bridge over Rockfish River at Wood's Mill; Albert Brothers Contractors Inc., Salem, \$108,560.

**Charlotte**—Rt. 672, 8.16 mi. grading and surfacing; Highway Paving Co., Richmond, \$110,221.

## WEST VIRGINIA

**CHARLESTON**—State Roads Commission received low bids for projects in following counties:

**Calhoun**—Proj. S 352 (1), Adam Rockdale Rd., Odum Construction Co., Huntington, \$127,555.

**Marion**—Proj. S 517(1), Katy Junction, Sec. 21, P. F. Earp, Fairmont, \$118,576.

**Freston**—Proj. S 523(1), Brandonville Rd.; Stickley Brothers, Keyser, \$143,492.

**Netzel**—Proj. S 578(1), Littleton, Rt. 7; Keeley Construction Co., Clarksburg, \$101,108.

**Wood**—Proj. F 158(16), Parkersburg Vt. Hamilton Rd., Andersons, Inc. & W. Va. Black Rocker, City, \$673,820.

**Wirt**—Federal Project No. S 546(1); Green-castle Bridge No. S 1770 over Hughes River, two 95 ft. and 120 ft. continuous steel I-beam spans on concrete substructure; W. R. Orders, St. Albans, \$109,785.

## PRIVATE BUILDING Proposed Stage

### ARKANSAS

**BLATHEVILLE**—First Baptist Church plans church, 8th and Walnut Sts.; \$250,000.

### DISTRICT OF COLUMBIA

**WASHINGTON**—Berla & Abel, Architects, plan apartment, 17th and Massachusetts Ave., N. W., next to Bay State Apartments; \$2,000,000.

**WASHINGTON**—Adas Israel Congregation plans \$1,250,000 temple, Connecticut Ave. and Porter St., N. W.

## FLORIDA

**FORT LAUDERDALE**—O. M. O. Corp. plans \$500,000 hotel.

**ST. PETERSBURG**—Sears, Roebuck & Co. soon lets contract for department store alterations; \$450,000.

## GEORGIA

**AUGUSTA**—P. S. Knox plans \$14,000,000 housing project.

**COLUMBUS**—St. Paul Methodist Church plans \$500,000 project in Wildwood area.

## MARYLAND

**SALISBURY**—The Boulevard Apartments Co., Inc., plans 48-apartment development in Camden area, fronted by Monticello Ave., South Blvd., Smith St. and Hanover St.; cost between \$350,000 and \$400,000.

## MISSISSIPPI

**JACKSON**—Ellis W. Wright, Y.M.C.A. Pres., plans campaign to raise funds for Y.M.C.A. building; \$550,000.

## MISSOURI

**KANSAS CITY**—Applemore Home for Aged Jews plans \$500,000 Home for Aged, 78th and Holmes Sts.

## TEXAS

**AUSTIN**—Corps of Engineers, Galveston District, plans 104-unit housing project at Bergstrom Air Force Base; \$1,500,000.

**BEAUMONT**—First Baptist Church plans building, housing chapel, Sunday school, recreation and nursery facilities; \$350,000.

**CAMP HOOD**—Corps of Engineers, Galveston District, plans housing project; \$3,400,000.

**DALLAS**—East Grand Avenue Baptist Church, 1106 Graham, plans \$600,000 auditorium-education building at Glasgow and Grand Aves.

**FORT WORTH**—University Baptist Church plans church, Forest Park Blvd. and Park Hill Dr.; \$350,000.

**HOUSTON**—Deepwater Homes Development Co., Inc., plans 700 residences, \$3,700,000, and community center, \$500,000.

**HOUSTON**—James H. Edmunds, Oak St., plans 200 residences, between Bellair Blvd. and Race Burn Dr.; \$2,750,000.

**HOUSTON**—Windsor Park, Inc., plans residential subdivision north of Ship Channel; \$2,500,000.

**HOUSTON**—J. Weingarten, Inc., plans \$8,500,000 expansion program in Harris County and Gulf Coast area.

**HOUSTON**—Battelstein's Department Store plans \$1,000,000 expansion.

**HOUSTON**—Fairview Co., Inc., plans shopping center on Silber Rd. between Westview Terr. and new development; \$350,000; also 50 dwellings, Westview Terr.; \$375,000; and 100 dwellings near Silber and Long Point Rds.; \$750,000.

**HOUSTON**—Home Owned Properties, Inc., Seaman Bldg., plans 265 residences north of Ley Rd., east of Seitzgate Rd. and north by Halls Bayou; \$1,000,000.

**HOUSTON**—Meadowbrook Co. plans 350 residences in Section 2; \$3,236,000.

**HOUSTON**—William G. Farrington, 1719 Sunset Blvd., plans residences in Tanglewood subdivision; \$1,250,000.

**RANDOLPH FIELD**—Corps of Engineers, Galveston District, plans housing project, Randolph AFB, Bee Base; \$1,000,000.

**SAN ANTONIO**—Corps of Engineers, Galveston District, plans housing project, Lackland Air Force Base; \$1,000,000.

**SAN ANTONIO**—National Hotel Co., Anico Bldg., plans Menager Hotel addition and remodeling; \$1,000,000.

**TEXAS CITY**—R. W. Davis, L. B. Christensen and Dee Walker plan hotel building; \$1,000,000.

## WEST VIRGINIA

**WHEELING**—Edgewood Park Methodist Church plans church, educational units and parsonage; \$500,000.

## ALABAMA

**BIRMINGHAM**—Joseph H. Canter and Marvin Warner let contract to J. H. West, 4210 Ave. N., for 45 apartment units; \$500,000.

**MONTGOMERY**—Bragg Apartments, Inc., let contract to Algernon Blair, First National Bank Bldg., for 50 apartment units; \$400,000.

**MONTGOMERY**—Turner Brothers let contract to Algernon Blair, First National Bank Bldg., for 100 duplex homes; \$500,000.

## FLORIDA

**MIAMI**—Miami Stadium, Inc., let contract to Taylor Construction Co., 1776 Purdy Ave., Miami Beach, for baseball stadium and sports center, NW 10th Ave. and 23rd St.; estimated cost \$500,000; to be leased to Magic City Baseball Club, Inc.

**NORTH MIAMI**—Morris Builders, Inc., 1100 NW 7th Ave., will build 62 residences; \$500,000.

**ST. PETERSBURG**—Master Mode Homes will build 22 residences; \$450,000.

## GEORGIA

**ALBANY**—Sowega Enterprises, Inc., will build 100 residences; \$350,000.

**ATLANTA**—M. J. Merritt, 211 Sisson Ave., N. E., will build by force account, 50 residences; \$350,000.

**AUGUSTA**—Knox Corp., Thomson, will build 250 residences in Fleming School Community; \$750,000.

**AUGUSTA**—R. E. Clarson, Inc., St. Petersburg, Fla., awarded contract at approximately \$340,000 by F. W. Woolworth & Co., for store building.

**FORT OGLETHERPE**—East Tennessee Co., Dick A. Hunt, Pres., plans 400 residences; \$3,200,000.

## LOUISIANA

**NEW ORLEANS**—South Lake Realty Co. of Chicago, Frank Dane, 510 Conti St., New Orleans, let contract to B. Swartz, 105 W. Monroe Ave., Chicago, Ill., for \$2,500,000 hotel on lakefront.

**NEW ORLEANS**—Lake Shore, Inc., 4400 Paris Ave., let contract to Shelby Construction Co., 4523 Paris Ave., for 12 apartment buildings at Mirabeau and Duplessis Sts.; \$425,000.

**NEW ORLEANS**—California Oil Co., Canal Bank Bldg., announced contract award to Keller Construction Corp., 7000 Palm St., for \$2,000,000 office building, Tuland Ave. and Elks Pl.

**NEW ORLEANS**—General Enterprises, Inc., T. Hewson Lynch, Canal Bank Bldg., Bldg. Mgr., let contract to Keller Construction Co., 7000 Palm St., for \$2,000,000 office building.

**SHREVEPORT**—Nell & Samdal, Architects, City Bank Bldg., competing plans for \$500,000 store on Milam and McNeil Sts., for Estate of W. Harry Johnson.

## MISSOURI

**KANSAS CITY**—Alexander Hamilton Apartments, Inc., let contract to Metcalfe-Hamilton Construction Co., Railway Exchange Bldg., at \$350,000, for apartment building, Armour Blvd. and Holmes St.

## SOUTH CAROLINA

**COLUMBIA**—H. R. Burg has construction underway by M. R. Kahn Construction Co. for \$1,000,000 apartment building, southwest corner Marion and Senate Sts.

**FLORENCE**—First Baptist Church, received low bid, \$415,776 from Crosland Construction Co., Columbia, for church.

**GREENVILLE**—Berk Simpson Co., received low bid, \$367,121, from McKoy Werry Co., Spartanburg, for alterations and additions to store.

## TENNESSEE

**NASHVILLE**—Evans & Morris, 816 8th Ave., S., will build 226 residences; \$1,417,500.

**NASHVILLE**—Herschel Green, 229 Union St., will build 291 residences; \$1,750,000.

## TEXAS

**BAYTOWN**—Memorial Baptist Church received low bid from Telleson Construction Co., 3900 Clay Ave., Houston, at \$404,444, for building.

**DALLAS**—Merchandise Mart, Inc., negotiated contract with George P. O'Rourke Construction Co. of Dallas for merchandise mart building, cost \$7,000,000.

**FORT WORTH**—Ridgley Housing Corp., P. O. Box 965, will build 98 frame residences; \$480,000.

**HOUSTON** — South Main State Bank let contract to Benson Co. for new structure, Main and Rosalie; \$325,000.

**HOUSTON** — F. A. Hunter, 5007 Telephone Rd., will build apartment buildings, Lum Terrace; \$1,100,000.

**HOUSTON** — C. O. Beeler, 5047 Marietta Lane, will build 25 residences, Riverside Terr., Section 22; \$340,000.

**HOUSTON** — Home Owned Estates and Affiliated Building Companies, 1001 Market St. Rd., will build 150 residences, Greens Bayou area on Houston-Port Arthur Hwy.; \$550,000.

**LUBBOCK** — Broadway Church of Christ let contract to JMEP Construction Co., 1915 Avenue Q, Lubbock, at \$634,800, for church.

**PORT NECHES** — Wilton Hebert, will build 60 residences; \$390,000.

**SAN ANTONIO** — Johnnie Chuoke, 116 Tuttle Rd., will build by force account, 18 residences, east of Broadway; \$475,000.

**SAN ANTONIO** — L. E. Fite & Co., 1001 Donaldson St., will build 150 residences in Jefferson Area; \$320,000.

**WICHITA FALLS** — Floral Heights Methodist Church let contract to Taylor Howell, Box 395, Wichita Falls, for church; \$457,238.

#### VIRGINIA

**HENRICO COUNTY** — Duke Construction Co. awarded \$3,500,000 contract for apartment project on north side Horseshoe Rd. in Crest-View.

**HENRICO COUNTY** — B. C. Cobb awarded contract for \$1,350,000 apartment houses, northwest corner Spring Dr. and Hilliard Rd., in Lakeside Area.

**QUANTICO** — Bureau of Yards and Docks received low bid, \$499,540, from Home Building Corp., Sedalia, Mo., for Spec. 21452, 60 houses.

### PUBLIC BUILDING Proposed Stage

#### ALABAMA

**BIRMINGHAM** — City plans 10-story city hall, \$2,500,000.

**DECATUR** — Board of Education will receive bids sometime in February for \$1,000,000 junior-senior high school.

#### DISTRICT OF COLUMBIA

**WASHINGTON** — Dr. George D. Strayer recommended to Congress a \$38,000,000 school construction program.

**WASHINGTON** — Ways & Means Committee, Rear Admiral C. R. Train, U.S.N. (Retired), Chmn., announced construction of new Children's Hospital, 13th and W Sts., NW, \$1,808,000.

#### FLORIDA

**MIAMI BEACH** — City Council plans bond election early in February on \$1,500,000 for public improvements.

**PENSACOLA** — Baptists, Rev. Aubrey R. Allen, pastor of the Olive Baptist Church, Chmn., has financial campaign underway to raise money to help finance Baptist Hospital, estimated cost \$1,200,000.

**ORLANDO** — Navy Department, Charleston, S. C., laboratory, including power house, 2 piers, \$1,120,000.

#### GEORGIA

**ATLANTA** — Fulton County Board of Education plans \$5,000,000 bond issue for school buildings.

#### LOUISIANA

**BATON ROUGE** — East Baton Rouge Parish School Board approved \$5,000,000 bond issue for school building.

**CROWLEY** — Acadia Parish Police Jury approved issuance of \$1,000,000 bond issue for courthouse.

**SHREVEPORT** — Hospital Board of Directors have plans ready about April or May, 1949, for \$5,000,000 Confederate Memorial Hospital.


#### MARYLAND

Maryland Council of Education, Dr. Thomas J. Pullen Jr., State Supt., of Schools, outlined five year school building program, \$129,800,000.

Dr. Thomas G. Pullen, Jr., State Supt. of Schools, request a public schools budget totaling \$31,987,880 for 1950 fiscal year.

**BALTIMORE** — City plans to have work underway in 1949 for new People's Court Building, \$1,000,000.

(Continued on page 50)



MODEL 90M  
6 inch

MADE IN ALL SIZES  
7M - 10M - 15M - 20M  
30M - 40M - 90M - 125M

## GORMAN-RUPP'S NEW PUMPS

### CHALLENGE ANY PUMP TO MATCH THEIR PERFORMANCE

With a new complete line of Contractors' Pumps, Gorman-Rupp has topped their own past high record of performance with a better pump—

#### QUICKEST PRIMING—HIGHEST PRIMING PUMPS MORE DIRTY WATER

Compare them for priming speed: The new Model 15M (3") primes at 25 ft. suction lift in 61 seconds.\* The new Model 90M (6") primes at 25 ft. suction lift in 44 seconds.\*

And the Gorman-Rupp is still the most simple pump—no ports, no valves, no clean-out plates, nothing to cause stoppages.

\*SEA LEVEL

### THE GORMAN-RUPP Guarantee

Our distributor's are authorized to put a Gorman-Rupp Contractor's Pump on any pumping job, anytime, anywhere, alongside any other make pump, size for size. The Gorman-Rupp pump is guaranteed to pump more dirty water, more hours, using less gasoline, to prime quicker and at higher suction lifts than any other self-priming pump. If it isn't the best all around pump, our distributor will accept the return of the Gorman-Rupp pump and pay the user any installation expense incurred.

Write for the new Contractor's  
Bulletin SCP-11

#### DISTRIBUTED BY:

Little Rock Road Machinery Co., Little Rock, Ark.  
Miller G. Williams Machinery Co., Montgomery & Birmingham, Alabama.  
Florida Equipment Co., Jacksonville, Miami & Tampa, Fla.  
W. C. Caye & Co., Atlanta, Ga.  
Brandels Machinery & Supply Co., Louisville, Ky. & Evansville, Ind.  
Fletcher Equipment Co., New Orleans, La.  
Dalrymple Equipment Co., Amory, Miss.  
State Machinery & Supply Co., West Columbia, S. C.  
Wilson-Weener-Wilkinson Co., Nashville & Knoxville, Tenn.  
Rish Equipment Co., Charleston & Clarksburg, W. Va., Richmond & Roanoke, Va., Bluefield, W. Va., Cincinnati, Ohio.  
H. B. Owsley & Son, Charlotte, N. C.  
D. C. Elphinstone, Inc., Baltimore, Md. and Washington, D. C.  
Tag Equipment Co., Inc., Chattanooga, Tenn.  
Ingersoll Corporation, Shreveport, La.

THE  **GORMAN-RUPP COMPANY**  
MANSFIELD, OHIO



## PUBLIC BUILDING

(continued from page 49)

**BALTIMORE**—City plans home for the aged at City Hospitals, \$3,000,000.

**BALTIMORE**—City plans new tuberculosis sanatorium at City Hospitals, \$2,226,000.

**BALTIMORE**—Corps of Engineers, plans 300-bed tuberculosis hospital at Loch Raven Boulevard and the Alameda, for Veterans' Administration, \$5,000,000.

**BALTIMORE**—Board of Estimates approved transfer of property, to Department of Health, as sites for Health District Buildings, \$1,000,000.

**BALTIMORE COUNTY**—Baltimore County Board of Education plans \$10,000,000 school building program.

**HAGERSTOWN**—Board of Trustees of Washington County Hospital, launched campaign underway for a \$1,650,000 expansion program.

**ROCKVILLE**—Montgomery County School Board, H. Stanley, plans \$9,000,000 school program for next two years.

**WESTMINSTER**—Carroll County School Board approved \$1,500,000 bond issue to improve school buildings.

## MISSISSIPPI

**GULFPORT**—Harrison County approved issuance of \$175,000 bond issue as the County's share for \$1,000,000 100-bed hospital.

**HATTIESBURG**—School Board of Trustees, has approved \$1,500,000 enlargement program for Mississippi Woman's College.

**JACKSON**—Martin Miller, Meridian, recommended a program to Board of Trustees, of state institutions of higher learning, to provide 23 additional dormitories at Mississippi Universities and colleges, \$9,000,000.

**JACKSON**—State Building Commission announced that 20-acre tract in Old Asylum area, north of Jackson, has been set aside, as site for \$3,000,000 Jackson Memorial Hospital.

**JACKSON**—Hinds County Board of Supervisors, contemplates \$1,000,000 County Hospital.

## NORTH CAROLINA

**GREENVILLE**—Board of Trustees plans 120-bed \$1,440,000 Community Hospital.

## OKLAHOMA

**NORMAN**—Central State Hospital plans addition and alterations to hospital, \$780,000.

**NORMAN**—University of Oklahoma, plans expansion of Oklahoma Memorial stadium on Owen Field, \$1,000,000.

## TENNESSEE

University of Tennessee plans pathology building at Memphis; chemistry building, girls' dormitory and college of business building at Knoxville, \$8,000,000.

**JACKSON**—City plans two new elementary school buildings \$1,000,000.

**KNOXVILLE**—University of Tennessee, plans \$24,000,000 school building program, for 13 buildings.

**NASHVILLE**—Tennessee Conservation Commission contemplates expenditure of \$5,000,000 for improvements to State Parks.

**NASHVILLE**—State plans Library Building, \$1,500,000.

## TEXAS

**AUSTIN**—State Board of Control, seeking \$21,000,000 to finance an expansion program for Elementary Institutions.

**DALLAS**—Southern Methodist University's Board of Trustees plans \$15,000,000 expansion.

**EL PASO**—Providence Memorial Hospital plans 200-bed Memorial Hospital and Nurses' Home, \$1,000,000.

**HOUSTON**—M. D. Anderson Hospital for Cancer Research plans hospital, \$1,712,000.

**HOUSTON**—University of Houston, plans student religious center building, includes library building, \$1,200,000, and student religious center building, \$500,000.

**HOUSTON**—Methodist Hospital plans 300-bed general hospital, Texas Medical Center, \$3,000,000.

**HOUSTON**—Dr. David Greer, c/o Texas Children's Foundation, plans 200-bed hospital for Children, Texas Medical Center, \$3,000,000.

**HOUSTON**—Harris County plans Court-house and general remodeling of present building, \$7,500,000.

**HOUSTON**—Glenn McCarthy has offered city a 100-acre site near Playland Park, for a 100,000-capacity Memorial Stadium, \$5,000,000.

**HOUSTON**—Memorial Hospital, 602 Lamar St., plans addition to present hospital, Lamar

at Louisiana, \$2,000,000.

**LAMARQUE**—Galveston plans County Mainland Hospital, \$1,000,000.

**LUBBOCK**—Lubbock County, plans courthouse, \$1,500,000 bond issue approved.

**MARSHALL**—Bishop College plans combination classroom-science hall and college chapel school, \$1,000,000.

**SAN ANTONIO**—Robert B. Green Memorial Hospital plans addition and alterations to hospital, \$1,200,000.

**SAN ANTONIO**—Bexar County, has application approved by Public Health Service for expansion and alterations to Robert B. Green Hospital, \$1,200,000.

**WACO**—Providence Hospital, Daughters of Charity of St. Vincente DePaul, Sister Mary Callahan, plans 100-bed addition, \$1,050,000.

## VIRGINIA

**LYNCHBURG**—State Hospital Board, Richmond, approved drawings and specifications for \$2,000,000 construction at Lynchburg Colony.

**PRINCE GEORGE**—Prince George County School Board proposes \$25,000,000 school program.

**ROANOKE**—City plans voting March 1, tentative date, on \$5,000,000 bond issue for school improvement program, also \$25,000 library and \$250,000 health center.

**SPOTSVYLVANIA**—Spotsylvania County School Board of Education plans high and elementary school for colored, \$575,000; and elementary school for white, \$425,000.

**STAUNTON**—State Hospital Board, Richmond, authorized Western State Hospital to proceed with preparation of working drawings for a new receiving unit \$2,000,000.

## WEST VIRGINIA

**WEIRTON**—City plans \$3,000,000 municipal hospital.

## Contract Stage

## ALABAMA

**AUBURN**—Alabama Polytechnic Institute, received low bid from Raymond M. Lee Co., 1004 Edgewood Avenue, Atlanta, Ga., \$173,658, for addition to stadium.

## ARKANSAS

**BENTON**—Arkansas State Hospital, Little Rock, let contract to Lindeberger Construction Co., 115 N. Spring St., Little Rock, for ward and infirmary building, Benton Unit, \$1,450,000.

## DISTRICT OF COLUMBIA

**WASHINGTON**—Howard University received low bid from F. H. Martell Co., Washington, \$1,554,000, for women's dormitories; Otis Elevator, Washington, \$59,795 low for elevator and dumbwaiters.

**WASHINGTON**—District Commissioners, District Bldg., let contract to Cramer Vollmerhusen 2601 Connecticut Ave., N.W., at \$1,274,000 for garage and shops for Division of Sanitation.

**WASHINGTON**—Public Buildings Administration received low bid from Brava Corp., Pittsburgh, Pa., at \$1,614,840 on Bid 1 and at \$870,260 on Bid 2, constructing additional boilers, West Central Heating Plant.

## FLORIDA

**Clearwater**—Board of Pinellas County Commissioners, received low bid from Paul Smith Construction Co., Tampa at \$525,000, for Pinellas County Jail.

**GAINESVILLE**—University of Florida let contract to C. A. Fieldland, Inc., Tampa, \$982,800, for office building.

**LANTANA**—Florida State Improvement Commission, Delray Beach, let contract to Arnold Construction Co., 7 Murray Bldg., Palm Beach, for tuberculosis sanatorium U.S. Highway, \$1,538,325.

**TALLAHASSEE**—Florida State University let contract to Paul Smith Construction Co., Tampa, \$497,265 for science building.

**TALLAHASSEE**—State Board of Control, Orlando, let contract to Beers Construction Co., 20 Ellis St., N.E., Atlanta, Ga., at \$1,574,000 for hospital for Florida A & M College for Negroes.

## LOUISIANA

**BATON ROUGE**—East Baton Rouge Parish School Board let contract to Keller Construction Co., 7000 Palm St., New Orleans, \$479,945, for Louise High School, at \$1,574,000.

**NEW ORLEANS**—St. Donnie Church received low bid from Lionel F. Favre, 937 Gravier St., New Orleans, \$476,346 for parochial school.

## MARYLAND

**CHESTERTOWN**—Kent County School Building Commission received low bid from William F. Sutter, Newesoeck, Pa., \$914,000, for Chestertown High School and Garnett High School in Chestertown; Rock Hall High School in Rock Hall; Galena Elementary School in Galena.

**ODENTON**—Board of Education of Anne Arundel County, Annapolis, let contract to Consolidated Engineering Co., Inc., 20 E. Franklin St., Baltimore, \$1,492,000 for Odenton School.

## MISSISSIPPI

**BATESVILLE**—Batesville Special Consolidated School District, let contract to Consolidated Contractors, Memphis, Tenn., \$410,808 for new high school.

## MISSOURI

**OVERLAND**—Ritenour Consolidated School District, let contract to Lectioner Construction Co., 4303 Delmar Blvd., St. Louis, \$428,974, for school.

**SPRINGFIELD**—Frisco Employees' Benefit Hospital Association, received low bid from H. B. Deal & Co., 1211 Olive St., St. Louis at \$631,877, for hospital; Southard Engineering Co., Land Bank Bldg., Springfield, low on plumbing and heating at \$34,382.

## NORTH CAROLINA

**RALEIGH**—North Carolina State College of Agriculture and Engineering, let contract to J. A. Jones Construction Co., Charlotte, \$948,700, for general engineering laboratory building.

## OKLAHOMA

**STILLWATER**—A & M College received low bid from J. J. Bollinger Construction Co., Braniff Bldg., Oklahoma City, \$967,600 for residence hall.

**TULSA**—Tulsa County School Board let contract to W. R. Grimeshaw Co., 1328 Hunt Bldg., Tulsa, \$1,440,000 for school.

## SOUTH CAROLINA

**GREENVILLE**—Board of Trustees of School District of Greenville, let contract to Daniel Construction Co., Greenville, \$561,769 for alterations and additions to Sterling High School.

**GREENVILLE**—Greenville County Board of Commissioners let contract to Daniel Construction Co., Greenville at \$674,100, for Courthouse and Office Building.

## TENNESSEE

**CHATTANOOGA**—State, Purchasing Agent and Tuberculosis Commission, Nashville, let contract to Foster & Reighton, Nashville at \$182,600 for tuberculosis hospital.

**NASHVILLE**—State Purchasing Agent, let contract to C. F. Rule Construction Co., Nashville, at \$722,255, for dormitory building, Central State Hospital.

## TEXAS

**AUSTIN**—University of Texas, Board of Regents, Math Bldg., No. 104, received low bid from Nathan Wohlfield, P.O. Box 7084, Dallas, low at \$2,079,336, for science building and \$962,733, for student health center.

**DALLAS**—Dallas Independent School District let contract to Nergard and Shaw, 2933 N. Henderson, \$673,675, for C. F. Carr Elementary School.

**DALLAS**—Board of Education received low bid from Nergard and Shaw, 2933 N. Henderson, Dallas, \$498,000, for addition to Maple Lawn Elementary School.

**HOUSTON**—Corps of Engineers, Galveston District, Galveston, received apparent low bid from Robert E. McKee, Dallas, at \$18,317,000, for 1089-bed neuro-psychiatric hospital, Old Spanish Trail and Alameda Road, for Veterans Administration; Westinghouse Electric Corp. Elevator Div., Jersey City, N. J., submitted bid of \$170,350 for elevators and dumbwaiters.

**SAN ANGELO**—San Angelo Independent School District let contract to Templeton and Cannon, 208 Central National Bank Bldg., San Angelo, \$508,720, for junior high school.

## VIRGINIA

**ALEXANDRIA**—Board of Education received low bids for additions to Maury Elementary School and for additions to MacArthur Elementary School; Lee T. Turner, Washington, D. C., \$229,877, for Maury School; Rogers and McGrath, Inc., Washing-

(Continued on page 60)

# Equipment and Material Makers' News

## Allis-Chalmers Announces BD-3 Motor Grader



Allis-Chalmers BD-3 Motor Grader

A new BD-3, the most powerful motor grader in its class and the third new grader to be introduced by Allis-Chalmers Manufacturing Co. in six months, has been announced by the company's tractor division. This powerful 19002 pound unit embraces many famous features of earlier Allis-Chalmers graders in addition to new developments designed to assure maximum performance for contractors, state, county and municipal highway departments, and other users of grader equipment.

Matching the rugged structure of the new BD-3 is a 78 brake h.p. General Motors 2-cycle diesel engine. This instant starting 3-cylinder engine provides the power to move capacity loads at increased speeds. Unit injection, 4 way cooling and readily available engine parts that are interchangeable with all other General Motors "71" series engines expedite economic field and shop service, an important factor which governs the success of most operations.

The BD-3 is recommended for both construction and maintenance operations. A tubular frame gives the unit a strong rigid backbone and also permits enclosed controls which cannot be knocked out of commission. Mechanically controlled front mounted lift cases provide direct down pressure which, in turn, maintains rigid blade settings measured to a fraction of an inch. A 28 inch throat clearance enables the BD-3 to handle bigger windrows. An involute design of the famous and exclusive Allis-Chalmers "Roll Away" mudboard expedites handling of bigger windrows because material is rolled, not pushed. The blade has a full 200° swing which enables the operator to grade either forward or reverse. A shorter turning radius makes the BD-3 ideal for narrow roads and streets.

## Largest Shovel Capacity Made Still Bigger

Capacity of the world's largest shovel is being made 5 cubic yards greater in a spectacular experiment just begun in southeastern Ohio's coal stripping fields. A 45 cubic yard dipper has just been installed on a Marion 5561 shovel owned by Hanna Coal Co. to probe the "economic ultimate" of modified armor plate steel in power shovel dipper design and construction.

The joint experimenters are Marion Power Shovel Co., of Marion, Ohio, long time

## Marion Type 5561 45-Yard Dipper



builders of the world's largest power shovels, and the Hanna Company. The big new dipper was delivered by truck late in October, and has been in use since December 1.

If the experiment is a success, a five cubic yard load of earth and rock will be able to "hitch-hike" a free ride every minute as the shovel strips away overburden to uncover seams of coal lying as deep as 80 feet under the earth's surface. The five-yard increase in dipper capacity, incidentally, is the equivalent of an average size dump truck load. By adding this much capacity to each of the one-minute digging cycles of the Marion 5561, the two companies hope to increase greatly the amount of stripping the big shovel can handle.

Just two years ago, Marion made world news by fabricating war-developed modified armor plate steel into a 40 cubic yard dipper. Prior to that, a 35-cubic yard dipper had been the world's largest, and only by using the new stronger steel in lighter sections could the increase to 40-yard capacity be achieved. Since that time, nine of the big 40 yard dippers have been built and placed in service. With their practicality fully proved and with field experience on hand to indicate that the new five-yard increase in capacity may be practical, the Marion and Hanna companies jointly undertook the experiment to "make the new steels work a little harder" and learn whether a 45-yard dipper might prove as practical as a 40 yard.

Adrien E. Busick, Jr., Marion chief engineer, pointed out that "economical ultimate" of the modified armor plate steels being used will be learned through study of several factors. One of these factors is weight. The new 45-cubic-yard dipper, fully loaded, weighs no more than the 35-cubic-yard dippers of three years ago, fully loaded. Consequently, the weight factor appears to be solved, provided the new dipper has sufficient strength in all of its component parts.

## Link-Belt Issues Catalog on Trolley Conveyors

Link-Belt overhead trolley conveyors "Make Ceilings Pay Dividends" is the title of a new 28-page, illustrated Book No. 2330, published by Link-Belt Co., Chicago. Some 80 illustrations depict a great variety of actual installations and show the flexible adaptability of this type of conveyor.

Among the more unusual uses is a trolley conveyor with rods hanging from the trolleys to assist fired miners up a hillside when they come out of the mine at the end of a day's work.

Trolley conveyors that are electrified with bus bars along conveyor track, to provide current for continuous testing of such articles as electric fans and freezer boxes, are shown. Another interesting feature is the great variety of specially made hangers that are used for suspending the product from the endless conveyor chain.

## 70-pound Paving Breaker by Independent Pneumatic

A new 70-pound pneumatic paving breaker is announced by the Independent Pneumatic Tool Co., of Aurora, Ill., manufacturers of Thor portable power tools. The new Thor "24" breaker is a companion machine to the widely used Thor 84-pound breaker, the Model "25," and answers a demand for a demolition tool just under the heavy-duty class. The new breaker has a 28-inch overall length; 1 1/2 inch by 6 inch (1 1/2 inch by 6 inch optional) chuck sizes for collared steels; 3/4 inch hose size; and 3/4-inch hose inlet pipe thread.

## Southern Steel Changes to O'Neal Steel Works

Southern Steel Works Co., Birmingham, Ala., steel fabricators, announce the name of the company has been changed to O'Neal Steel Works Co. By this move, the firm takes the name of its president, Kirkman O'Neal, who founded the company in 1922 and has directed its management since. There will be no change in management, ownership, policy, or service. At the same time, the name of the subsidiary Southern Steel Co., dealers in warehouse steel, is changed to O'Neal Steel Co. Offices of both companies are at 745 North 11st Street.

## Wooldridge Scrapers, Bulldozers

Three new models of cable-controlled earthmoving equipment are currently in production at the Wooldridge Manufacturing Co. of Sunnyvale, Calif. These include the Models BB-85 and BB-120 four-wheel scrapers and the BHD-19 bulldozer.

Offering a wide, unobstructed front apron opening of 60 inches, the new scrapers feature rear-draft fulcrum leverage and pivot-tilt bowl to assure faster, more efficient loading and dumping of greater volume. The BB-85 has a capacity of 8.5 cu. yds. struck



Wooldridge BB-85 Scraper

and 11.0 cu. yds. heaped, while the BB-120 carries 12.0 cu. yds. struck and 14.2 cu. yds. heaped.

Other engineering advances include higher yoke clearance and greater ruggedness throughout. Cable is easily accessible, reeved in straight lines without reverse bends for increased life and easy replacement. Shorter wheelbase insures quick turning in crowded quarters. All sheaves are mounted away from dirt and load.

Optional on the BB-85 scraper are four 16.00 x 20 tires or six 14.00 x 20 tires. Approximate shipping weight is 16,000 lbs. The BB-120 may be equipped with four 16.00 x 24 or four 18.00 x 24 tires, and has an approximate shipping weight of 19,500 lbs.

The Wooldridge BHD-19 bulldozer for Allis-Chalmers' big HP-19 tractor is designed for rugged service in straight bulldozing operations. Heavy push arms, fabricated from formed channel, telescope for knock-down shipment. Cable to power control unit follows side of tractor frame from a sturdy engine-mounted assembly, providing operator with full visibility.

## Contractor Combines Tractor Jobs for Efficiency

Hauling excavated dirt was a double-duty operation in the work pattern of Miller Excavating Co., Omaha, Neb., recently, when the company arranged a profitable transfer of dirt from residential to industrial building sites.

The firm was simultaneously digging basements for a number of homes and constructing a raised fill for the foundation of a new implement store. Dirt had to be hauled away from the homesites and dirt was needed for the fill at the store location.

Miller's trucks moved the unwanted dirt from residential excavations to the other site. Thus, the haul and dump phases of a number of small jobs were made productive operations in a large one, a good case of economical earthmoving practice.

An International TD-9 Diesel crawler with one yard Hough Bulldozer-Shovel dug the basements and loaded the trucks. Dirt was spread and compacted at the store site by another International, a TD-6 with Isaacson dozer and a sheepsfoot tamping roller.

(More on page 32)

## TD-9 International with Hough Shovel excavating basement.



## New Tunneling Folder

"Tunneling for Profit and Convenience" is the title of a 4-page folder recently published by Armo Drainage & Metal Products, Inc. Stress is placed on tunneling as an economical means of avoiding inconvenience to traffic and loss of business to merchants and others. Use of light-weight corrugated liner plates has simplified tunneling procedure.

Other advantages described are less excavation, fast assembly, greater safety above and below ground, no hindrance from bad weather, no destruction of expensive pavements or railway roadbeds, and freedom from settlement and future maintenance. Uses illustrated are for new sewers, relining of failing sewers and culverts, service tunnels for utility lines and pedestrian and livestock underpasses.

Copies may be obtained from Armo Drainage & Metal Products, Inc., General Offices, Middletown, Ohio, or any of the Division Offices.

## Newly Revised Bulletin On Single-Acting Hammers

A new edition of the McKiernan-Terry single-acting pile hammer bulletin, provides added information of interest to engineers and contractors. Revised specifications and an added listing of component parts for all sizes of these single-acting pile hammers bring this bulletin up to date.

The text explains the special purposes and uses of the single-acting type of hammer. A concise tabulation lists exclusive advantages and superiorities claimed for McKiernan-Terry hammers, including underwater driving. Operating instructions have been revised and elaborated, and a formula is given for computing the bearing capacity of piles, with application to each of the five standard sizes. Copies can be obtained from McKiernan-Terry Corp., Dept. MR, 15 Park Row, New York 7, N. Y.

(More on page 54)

## B-G Designs New Small Snow Loader



Barber-Greene B-G Snow Loader.

On the market for the first time this year, is a new small Snow Loader designed specifically for small cities, towns, and industrial plant storage and loading areas. Fast and efficient snow removal has over and over been proved to be a very economical means of meeting snow conditions. Manufactured by Barber-Greene Co., Aurora, Ill., producer of portable road building machinery and constant flow material handling equipment, the new snow loader is said to be the most economical machine that can be used to do the job.

A test proved the Model 522 snow loader will load a five-cubic yard truck in one minute, while the labor of four men is required for 20 minutes to do the same job. Figures at \$4.75 per hour for truck and driver at the 5 cubic yard per minute rate give a saving of \$1.50 per 5 cubic yard load in trucking costs alone, among other economies.

The Model 522 snow loader is one-man operated and self feeding with a capacity up to 5 cubic yards per minute for economical and practical snow removal. For a negligible cost, the new B-G snow loader can be converted to an all year round loader for a variety of bulk loading applications.

Low clearance is a feature of the new snow loader, as is its quick portability and maneuverability.

Many Barber-Greene advantages have been incorporated into the Model 522, such as: Automatic overload release, which protects the machine. Floating boom, eliminating stress on boom or chassis. Individual steering and crowding clutches, controlling driving, crowding and braking. Spiral feeding device for capacity loading and breaking of lumps and ice.

## Gardner-Denver Announces Automatic Line Oiler

A new line oiler that protects against running rock drills or other air actuated equipment without adequate lubrication has just been announced by Gardner-Denver Co., Quincy, Ill. Known as the L012 automatic line Oiler, this new device shuts off the line air automatically when all the oil in the reservoir has been used. Thus there is no chance, the manufacturer states, for equipment to operate without proper lubrication.

In operation, the L012 oiler delivers a metered flow of atomized oil from any position, either vertical or horizontal and all of the oil is consumed. The flow of oil is metered so that any pneumatic equipment using from 25 to 500 cubic feet of air per minute can be efficiently lubricated. The oil capacity of the L012 Line Oiler is one pint, and it is not necessary to shut off the line air, or to stop the machine to which it is attached, in order to refill the reservoir.

The manufacturer reports that special construction of the L012 makes it impossible for oil in the chamber to become emulsified and mixed with water. And the L012 is said to be easy to service, for all parts may be withdrawn by hand, once the bushing on the inlet end has been removed.

## Sales Manager Named

Charles L. Haslup has been appointed sales manager of the field operations for the Reading-Pratt & Cady division of American Chain & Cable Co., Inc., with headquarters at Reading, Pa. Mr. Haslup brings to the position a long experience in sales supervision in the valve industry and a wide knowledge of distribution problems and distributor-manufacturer relations.



City fathers of North Platte, Nebraska, can tell you about sewer pipe. They learned through honest experience. Today they are replacing many of North Platte's sanitary sewer lines, using durable Dickey vitrified glazed clay pipe.

The secret of Dickey pipe's endurance lies in two factors:

First: It is made of vitrified glazed clay. It is flint hard. Neither the caustic bite of acids and alkalis, nor the ceaseless scouring of grit can harm it.

Second: It is made by men who are not content to make pipe that is "just as good." Dickey workmanship has led the field for 63 years. It does not stop with ASTM standards. It surpasses them.

When you choose clay pipe, choose Dickey vitrified glazed clay pipe.

## W. S. DICKEY CLAY MFG. CO.

Kansas City 6, Mo., Birmingham 1, Ala., Chattanooga 2, Tenn.


San Antonio 7, Tex., Texarkana, Tex.-Ark.

IF IT'S MADE OF CLAY IT'S GOOD... IF IT'S MADE BY DICKEY IT'S BETTER

## HOW TO BUILD SAFE SCAFFOLDING

Faster at Lower Cost

**GOLD MEDAL  
SCAFFOLDING**



IN ATLANTA IT'S GOLD MEDAL SCAFFOLDING—AGAIN

Safety Scaffolding, Machines and Tubular Steel Sidewalk Canopy installed at Franklin Simon Store, Atlanta. George A. Fuller Co., contractor; Herbert B. Beidler, Atlanta, architect.

### COMPLETE STOCKS for Sale or Lease

Contractors who demand safe equipment for their workmen use GOLD MEDAL Scaffolding... designed by engineers to eliminate many of the hazards found in ordinary equipment.

GOLD MEDAL Scaffolding is not only safer—but it saves time because fewer man hours are needed to erect and dismantle it, and money, because men do more work in less time on a safe scaffold.

There is a type of GOLD MEDAL Scaffolding to meet every need—with greater safety and efficiency.

GOLD MEDAL Tubular Steel Scaffolding  
GOLD MEDAL Suspended Masons' Scaffolds  
GOLD MEDAL Junior Swinging Scaffolds  
GOLD MEDAL Steel Sidewalk Bridges  
"Trouble Saver" Sectional Steel Scaffolds  
"Trouble Saver" Steel Scaffold Brackets  
"Trouble Saver" Adjustable Steel Trusses

Write for catalogs and full information

**THE PATENT SCAFFOLDING CO., Inc.**

38 Haynes St., N. W.  
Atlanta 3, Ga.

93 N. E. 20th Street  
Miami 37, Fla.

## 2,733 SALES PROSPECTS

### 1949 Edition To Be Ready Soon

Most complete and up-to-the-minute list of the month's new plants and expansions to existing plants—compiled by states and cities—ready for instant reference.

NEW AND EXPANDING PLANTS is of immense value to any company that sells to Southern industry; an excellent sales prospect list that's made to order for you.

**YOURS FOR ONLY \$1.00 A COPY**

Send check or money order today  
for your copies of the 1949 Edition of  
**NEW AND EXPANDING PLANTS.**


A BUSINESS SERVICE PUBLICATION OF

**MANUFACTURERS RECORD**

Baltimore 3, Maryland

## ELECTRIC HAND SAWS

*are  
Best!*



**FIRST—built to last!**

Special Fred W. Wappat-designed and correctly cut gears, deep-groove sealed ball bearings, one-point lubrication, air-cooled motors, keep saws running smoothly hour after hour, in any climate. Mechanical parts easily accessible for checking, cleaning, etc.

**EASY on the operator!  
SAFE for the operator!**

**It Doesn't Cost You  
A Penny To Try A  
Fred W. Wappat  
Electric Hand Saw!**

Ask your dealer to order one for you, without any obligation. If you don't agree that it's the best electric hand saw you can buy, return it, and it hasn't cost you one cent! If your dealer can't supply you, write direct to Fred W. Wappat, Inc., Mayville, New York.

Many Fred W. Wappat Saws are still in everyday use after 20 years' service—still showing a profit for their owners. Proven design and construction make them dependable—make Fred W. Wappat Saws their own best salesmen! Ask any Fred W. Wappat user!

**MAINTENANCE problems  
MINIMIZED!**

Fred W. Wappat Saws are carefully balanced for fatigue-free operation—even with one hand! Operate perfectly in any position! Instantaneous cut-off switches, fool-proof telescoping blade guards protect even the most inexperienced operators at all times!

**MODEL A-9**  
3-7/16" Capacity

**\$135.00**

**MODEL A-8**  
2-5/8" Capacity

**\$115.00**

**BOTH  
SAWS  
ADJUST  
FOR  
DEPTH  
AND  
BEVEL  
CUTS**

**Fred W. Wappat, Inc.**  
149 Valley St., Mayville, N.Y.



# Equipment and Material Makers' News

## Midget Pavement Breaker with New Features

The Rapid Pavement Breaker Corp., maker of the Mighty Hubid pavement breaker announces a number of new features which are now being incorporated into the machines. It is claimed that the improvements permit greater ease of handling and that the new machines show important gains in yardage of concrete broken in a day's operation.

Controls are within easy reach of the operator's seat which is placed directly behind the machine, allowing the operator to see exactly where and how the hammer contacts the pavement at all times. A conventional steering wheel has been added which fits alongside the machine and is readily reached. Worm drive tends to hold the front wheel much steadier under difficult conditions. New higher wheels allow the machine to run through broken concrete and remain on a straight course, without sinking into the concrete.

## Nordberg Diesel Bulletin

Bulletin 161 covering Nordberg diesel engines of the FS-9 and FS-13 series is announced by Nordberg Manufacturing Co., Milwaukee 7, Wis. The new bulletin gives design and operating features of four-cycle diesel engines in 9-inch and 13-inch cylinder sizes providing a power range from 150 to 1,370 H.P. for a wide variety of services ranging from self-contained portable power units to permanent installations and auxiliary units for cargo and passenger ships and tankers. Specifications and dimensions of FS-9 and FS-13 engines are also given in this 12-page bulletin.

## Tractors for India

Eight men stood watching as the last of eleven crates was loaded on the flat car. The U. S. Tractor Corp., Warren, Ohio had brought its production rate of tractors up to where it could spare a carload for shipment to India.

Warren Smith, president of U. S. Tractor Corp., felt like cheering. Since September he'd been driving himself and his staff at top speed to get into production after moving his entire operations from Peoria, Ill., to Warren, Ohio.

Things were looking up. "Production will hit 1,000 a month by January," said Mr. Smith. "Bulldozers, angle dozers and snow plows are starting to roll off the production line. It looks as if we're finally getting set to make a dent in our mountain of orders."

The little 3,425-pound Ustrac is an adaptation of the portable Clark airborn tractor that proved itself in wartime service. Only 92 inches long, 42 1/2 inches wide, the little tractor maneuvers where larger tractors cannot go, stops and turns on a dime. It delivers 20.4 horsepower at the drawbar from a 4-cylinder Continental gas engine.

## Distributor Sells 55 Hubers to State of West Virginia

Within a period of six months this year, M. R. Hamill, Huber Manufacturing Co. distributor in Charleston, W. Va., completed two sales involving the acquisition of 55 Huber road maintainers by the West Virginia State Road Commission. The first sale, for 30 machines, was completed last spring, and in mid-September the state purchased 25 more.

West Virginia now has a Huber maintainer in operation in each of its 35 counties. The work of these machines includes the shaping



Huber Road Maintainer

of gravel and dirt secondary roads, and shoulder stabilization and other improvements on both primary and secondary roads. Mr. Hamill is president of M. R. Hamill, Inc. of Charleston, a concern which he formed last August after several years' association with other equipment supply firms in the Charleston area.

In addition to Huber, which has its main offices and factory in Marion, Ohio, Mr. Hamill served as distributor for the New Holland Manufacturing Co. of Mountville, Pa., builders of crushers, conveyors and screening equipment.

## New LeTourneau Appointments

R. G. LeTourneau, Inc., Peoria, Ill., has appointed three district sales representatives in the southern territory. M. B. (Jack) Crowley, long experienced as a miner and engineer in coal and metal mines, will assist LeTourneau distributors in Virginia, West Virginia and the Carolinas. His headquarters will be at Raleigh, N. C. Fran W. Duke, formerly associated with LeTourneau dealers, has been named district representative for lower New York, upper New Jersey, Pennsylvania and Maryland. Jim Sevek is the new district representative for Oklahoma, Arkansas, Mississippi, Louisiana and western Tennessee. In those states he will give sales assistance to Kessler-Simon Machinery Co., Tri-State Equipment Co., Inc., and Watkins-Aldridge Equipment Co., Inc.

## Transall "Unitized" Conveyors

Ball bearings, Neoprene mounts, sealed-in lubrication and self-cleaning rolls are features of the new "unitized" conveyor system being marketed by Transall, Inc., 109 N. Eleventh St., Birmingham 4, Ala.

The idlers have precision ball bearings in each roller and are lubricated with high quality, non-oxidizing non-emulsifying lubricant sealed in at the factory. This combination, say Transall officials, "gives the freest turning rolls, less wear and lower starting movement," thus eliminating "troubles with 'cold morning' starting."

Resiliency of the Neoprene mountings is aimed at eliminating shock on the bearings, reducing vibration and providing automatic self-alignment of the bearings. The frame of the idler has a clearing edge toward the roller, which removes any build-up of sticky materials greater than one-quarter inch.

Other features of the Transall system are: Minimum heights of head section, main chassis and tail section; spill shields for belt protection in place of dead plates; compact drive and power unit; self-cleaning tail pulley; short, maneuverable tail section, return idlers assembled in composite unit with trailing idlers.

The Transall conveyors are recommended for installation where frequent moving is required. Advantages of the system are emphasized for coal mining, although it can be used for all types of conveying operations.

## Madden Made Vice President of Haiss Company

E. J. Seifert, president of Pettibone Mulliken Corp., Chicago, and subsidiary corporation, George Haiss Manufacturing Co., Inc., New York City, has announced appointment of W. E. Madden to vice president of the Haiss concern. Mr. Madden was appointed sales manager of the Haiss conveyor division last year and has been responsible for the outstanding development of Haiss conveyors for coal, aggregates and package handling.

Pettibone Mulliken Corp. divisions also manufacture Haiss bucket loaders, snow loaders, coal loaders and clamshell buckets; Universal, rock and aggregate, crushing, washing and screening plants; Beardsley and Piper, foundry equipment.

Pettibone Mulliken Corp., the parent company, manufactures railroad track products, shovels, clamshell buckets, highway speed-loaders and asphalt plants.

## Oil Resistant Steam Hose

United States Rubber Co., Rockefeller Center, New York 20, has developed an oil resistant, high pressure steam hose for pile drivers used in building wharves, bridges, railroad trestles and other heavy construction work. The hose—called Matchless Pile Driver Hose—is especially designed to withstand the deteriorating effects of a combination of steam and hot oil which occurs when lubrication is applied to pile driving tools through steam pressure lines.

Braided wire construction gives the hose an unusually high bursting strength and acts as an armor to withstand heavy external abuse, both important safety features for operators handling pile driving equipment, the company said. The hose is constructed of a rubber core especially compounded for oil resistance, two or three plies of braided steel wire, depending upon the diameter of the hose, one ply of asbestos cord, and a heat resistant rubber cover.

## Rotary Concrete Drill

A new and improved rotary concrete drill with exclusive design features has been announced by the Tilden Tool Manufacturing Co., 1965 N. Fair Oaks Ave., Pasadena 3, Calif.

With a unique core drill design and a side exhaust slot which permits core particles to escape, the Tilden drill penetrates concrete at the rate of two inches or more per minute in diameters of from 1/2 to 2 inches. Specially treated sintered carbide cutters, located around the perimeter of the core where they operate at the most efficient speed, exert a cutting, pulverizing action which drills holes faster and leaves them straighter and cleaner. The Tilden drill bit is designed for use with ordinary electric drill motors. The cutters can be re-sharpened on any ordinary grinder used for tungsten carbide.



Above—Officials of U. S. Tractor Corp. and Federal Machine and Welder Co. watch shipment of tractors to India. Left to right are A. J. Stobbe, R. Peterson, A. R. Kelso, M. S. Clark, R. N. Lietzel, W. E. Ruck, W. Terry, J. R. Barefoot.

## Road Builders to Meet Next Month

The American Road Builders Association will hold its forty-sixth annual meeting February 7 to 9, when a record-breaking attendance is expected for the numerous meetings and conferences, as well as to elect new officers for 1949.

*Below—Col. E. R. Needles, of the engineering firm of Howard, Needles, Tammen and Bergendoff, is the nominee for president of the American Road Builders Association.*



Col. Enoch R. Needles, of the consulting engineering firm of Howard, Needles, Tammen and Bergendoff, has been named to succeed J. T. Calloway, who has occupied the A.R.B.A. presidency for two years.

Four regional vice presidents have been nominated to succeed themselves. These are: Paul B. Reinhold, of Pittsburgh, Pa.; Charles W. Smith, of Pensacola, Fla.; W. A. Roberts, of Milwaukee, Wisc., and T. E. Stanton, of Sacramento, Calif.

Directors for terms ending in 1952 include Paul L. Andrews, executive secretary of the Georgia Highway Contractors Association; Robert B. Brooks, of St. Louis; Bernard L. Gray, of New York; Robert M. Reindollar, chairman of the Maryland State Roads Commission; Paul B. Rynning, of Medford, Ore.; Charles H. Sells, of Albany, N. Y., and A. R. Taylor, of Pittsburgh.

Jennings Randolph, who also has been named for the treasurer's position, will be nominated as president of the airport division.

New airport vice presidents are to include: Maj. Gen. C. R. Moore, of Baltimore; E. W. Bentley, of Jacksonville, Fla.; Robert Dewey, of Springfield, Ill.; Brig. Gen. T. B. Herndon, of Baton Rouge, La.; J. D. Ramsey, of Lincoln, Nebr.; O. J. Porter, of Sacramento, Calif.; and Frank W. Wiley, of Helena, Mont.

Nominated for directors of the airport division will be Gen. Donald Connolly,




*Above—Nello L. Teer, Jr., vice president of Nello L. Teer Co., Durham, N. C., is the choice for president of the contractors division, American Road Builders Association.*

Baltimore; Louis Grashot, of Memphis; O. W. Merrell, Columbus, Ohio; Col. Roy D. Burdick, of Little Rock, Ark.; R. F. McKee, of Denver; W. A. Buggee, of San Francisco; Louis Wasmer, of Spokane, Wash.

Nello L. Teer, Jr., vice president of Nello L. Teer Co., of Durham, N. C., has been selected to head the contractors'

(Continued on page 56)

## O.K. HOISTS MEET *Your* SPECIFICATIONS



**DRUM:** Single, Double, Three or 2 Drum Slack

**POWER:** Gasoline, Electric or Diesel

**SPEEDS:** Ft. Per Min.—24, 150, 200, 240, 280, 500

**CAPACITY:** Lbs.—1300, 2000, 3200, 5000, 7000, 9000, 12500, 15500, 19000

**HORSE POWER:** 8, 18, 28, 50, 65, 80, 105, 125, 150, 175, 185, 200

For light work or heavy work in all fields—giving satisfaction since 1903—and sold with a written guarantee.

Write for **FREE** bulletin or name of your nearest dealer.

**O.K. CLUTCH & MACHINERY CO.**  
1942 FLORENCE STREET, COLUMBIA, PENNA.

## Road Builders' to Meet

(Continued from page 55)

division. Vice president will be Joseph D. Bonness, of Milwaukee. Directors will include:

R. P. Bayard, of New York; John L. Flanagan, Jr., of Brooklyn, Md.; E. E. Hoebel, of Madison, Wis.; P. F. Hollinger, Akron, Ohio; L. W. Lamb, Holland, Mich.; P. J. Walsh, Charleston, W. Va.; E. V. Williams, Norfolk, Va.; W. W. Young, Macon, Ga.

Directors-at-large will be: Wyatt B. Hodges, Fort Lauderdale, Fla.; Rudolph Kraemer, Plain, Wisc.; Austin E. Page, Meriden, Conn.; R. B. Potashnick, Cape Girardeau, Mo.; H. W. Riehe, Lansford, Pa.; E. D. Sloan, Greenville, S. C.; Herbert M. Warren, of Birmingham, Ala.

President of the county highway officials division will be Alan N. Buck, Decatur, Ill., succeeding Ben T. Collier, Clarksdale, Miss. For vice-presidents are: L. P. M. Gaylord, Lowville, N. Y.; A. W. Hinderman, Wapello, Iowa; Scott Candler, Decatur, Ga.; Chris P. Fauerso, The Dalles, Ore.

For county official directors are: Otto S. Hess, Grand Rapids, Mich.; Earl J. Mattis, St. Massena, N. Y.; Walter T. Jacobs, Columbus, Ohio; Paul B. Rynning, Medford, Ore.; A. N. Sollee, Jacksonville, Fla.; E. S. Ward, Willmar, Minn.; Wayne S. Talbott, Lapwai, Idaho. H. H. Kranz, of Cincinnati, Ohio, is to succeed J. B. Wilson, of Louisville, as president of the municipal division; Vice presidents will be: H. F. Clemmer, Washington, D. C.; D. L. Erickson, Lincoln, Nebr.; W. E. Shedd, Jacksonville, Fla.; W. N. Frickstad, Oakland, Calif.

For municipal division directors include: Robert A. Mitchell, Philadelphia, Pa.; Ralph B. Slippy, Waterloo, Iowa; W. W. Deberard, Chicago, Ill.; W. L. Chilcote, Baltimore, Md.

**Below—Bryson Christliff, of Stuart M. Christliff & Co., has been elected president of the Baltimore chapter of Associated Equipment Distributors. Also chosen were C. D. Edwards, of McCung-Logan Equipment Co., vice president, and Ridgely A. Frey, of Free State Equipment Co., Inc., secretary.**



## Letters

December 6, 1948

Mr. Samuel A. Lauver  
Manufacturers Record Pub. Co.  
Baltimore (3), Maryland

Dear Sir:

Reference is made to your letter which deals with the continued rising cost of construction. You requested comments from us as to what steps we thought might be taken to improve the general situation.

We have given the matter considerable thought and it is my feeling that a major portion of the trouble can be summed up in the one word "Escalation." The dictionary defines escalation as applying to both "ascending" and "descending" but one would never realize that fact in its present day application.

Proposal forms prepared by Federal, State, and Municipal Agencies prohibit escalator clauses and bids containing such clauses are usually thrown out. The Contractor, therefore, has to bid "firm prices" which must hold good throughout the life of the project. In some cases this may be a matter of months; in others, two or three years.

Let us place ourselves for a moment in the position of the Contractor as he prepares his bid for a large bridge project. This project, let us say, requires a large tonnage of steel, a considerable quantity of cement, and electrical equipment, etc. Is it possible for him to obtain firm prices on any of these materials? Absolutely, no! On the other hand the quotations of the firms producing these materials, by innuendo, or otherwise, contain, in the wording of their escalator clauses, dire forebodings of rising prices to come. Our experience has been that, after securing orders containing such clauses, they usually take advantage of them and raise their prices before the order is completed.

After the Contractor reviews these quotations he is placed in such a hesitant frame of mind, is it any wonder that he turns to his estimate of the labor costs and decides that perhaps he, also, had better protect himself? If steel, cement, and the like should go up in price, he knows naturally that wages in those industries will also increase and in turn such increases will cause trouble in his own wage field.

In summary, it is my belief that when the day arrives that the producers of construction materials quote firm prices to the Contractors, then, and not before, you will see construction costs levelling off. How this can be accomplished is the problem at hand. Until then the unfortunate Contractor is left "holding the bag" and who can blame him for trying to protect himself as best he knows how.

Very truly yours,  
S. E. LILES, JR.  
Executive Vice President,  
Tidewater Construction Co.

## Little Rock Flood Control

(Continued from page 38)

Creek and about 21 feet over the remainder of the alignment. To be constructed in the vicinity of the Little Rock Packing plant, the floodwall will have an average height of 11 feet.

Two pumping stations will be constructed to provide a means of disposal of storm and sanitary sewage during periods of high-river stages. One will be located at the foot of Bond Street and the other on Harahan Ditch, near the foot of Gregg Street. Sanitary sewage will also be disposed of by the existing municipal pumping station, and the operation of this station will not be affected by the levee project.

Capacity of the Gregg Street pumping station will be supplemented by the storage that will be available in a borrow area approximately 3,000 feet long located immediately downstream from the pumping station. The flood-carrying capacity of Fourche Creek downstream from the diversion channel will be increased by clearing the channel and banks of the creek. Existing storm and sanitary sewers will be altered or extended as required to connect to the pumping stations.

Interior storm run-off will also be disposed of by means of three gravity drainage structures within the reach of levee extending along the Arkansas River, and by utilizing natural storage for ponding storm run-off and constructing four gravity drainage structures in the reach of levee extending along Fourche Creek.

These structures will be equipped with hand-operated slide gates placed in concrete gate wells located on the riverside of the levee. Each structure will also be provided with an automatic flap gate located on a concrete headwall at the outlet end. The gates will prevent the entrance of backwater during high river or creek stages.

In addition to the work performed by the Corps of Engineers, certain relocation work must be performed by local interests to meet their obligations under the provisions of Congressional legislation. This work includes moving power lines, telephone lines, pipe lines, and the railroad at the Little Rock Packing Co. The 24-inch "Big Inch" pipe line crosses the levee alignment at two points and the Fourche Creek diversion channel, and the 20-inch "Little Inch" pipe line also crosses the levee alignment at two places.

At all of these points line elevations were revised. The Pulaski Drainage District Number 2, which was established by order of the County Court of Pulaski County, has issued the necessary bonds to finance this part of the work. Officials directing the activities of the drainage district are: G. B. Oliver, Jr., Frank B. Gregg, Jr., and Fred J. Venner, members of the Board of Commissioners, and L. P. Biggs, the district's attorney.

The entire project is scheduled for completion by December 1, 1949. The rest of the city of Little Rock is above the flood plane of the Arkansas River and is therefore considered safe from any

known flood. Flood protection for the city of North Little Rock, across the river, from this estimated maximum flood of 800,000 cubic feet per minute has been previously provided by means of a flood-wall and pumping plants which were finished in 1939. Last year, because of caving banks and erosion, the Little Rock engineer office constructed emergency bank-protection works to safeguard this floodwall at a cost of \$194,512. Markham and Brown and L. L. Sanders, of Cape Girardeau, Mo., did the work.

## Benbrook Dam Award

(Continued from page 30)

limestone. This material was line drilled to specified neat lines by use of wagon drills and loosened by dynamiting. Since the exposed material will soften and disintegrate when subjected to the elements, it was necessary to protect the limestone with an application of bituminous compound.

Blaw-Knox steel forms are used in the construction of the 4-foot thick, 13-foot diameter concrete discharge conduit, while economy panel forms are being employed to construct the intake tower. Absorptive form lining is being used and is held to the steel forms by use of a heavy grease or silicon sulphate.

Concrete aggregate is being shipped to a railroad siding where it is stock piled for subsequent batching and hauling by trucks to the site, 2½ miles distant. Southwestern Stone Co., is furnishing two-inch maximum sized crushed limestone from their quarry near Chico, Texas, while Jabco Gravel Co., supplies one-inch maximum sized gravel as well as the sand from their Brazos River quarry. Type II cement is being used with an air entraining agent added at the mixer. Use of this latter admixture increases the durability of the concrete and permits the placement of 1-inch slump concrete due to the increased workability of the mixture. The contractor uses two one-cubic yard paving mixers and places the concrete into the forms with a 1½ yard Lima crane which is generally operated at the edge of the cut. The trucks used to haul the batched material have three separate compartments effecting three charges of the mixer at one haul.

For the construction of the intake tower it is planned to place the upper portions of the 100 foot structure by use of a boom and crane operating on embankment fill material immediately downstream of the tower, supplemented by temporary fill in order to obtain required reach. Ottinger Brothers are contractors for the outlet works.


Completion of the embankment is well under way due to favorable weather conditions. The contractor has on the site a Euclid loader and 7 Euclid wagons supplemented by 4 La Plante-Chouteau rotolized scrapers for the placement of the 6,000,000 cubic yards of rolled earth fill. Construction of the spillway is scheduled to start next April. A 34E paving mixer

will be used to mix the concrete with placement to be handled by use of a 2 cubic yard crane. List & Clark, Kansas City, are the contractors.

## Gar Wood Appointments

Gar Wood Industries, Inc., Wayne, Mich., has appointed two new district managers, D. J. Byrd in the Southeast region embracing Alabama, Georgia, Florida and Eastern Tennessee and W. E. Toensing in the Virginia, North Carolina, South Carolina and District of Columbia area.

Mr. Byrd will be responsible for sale and distribution of Wayne division hoists, bodies, winches, cranes and load-packers; Findlay division ditchers, shovels, spreaders and fine-graders, highway wideners and tractor equipment and St. Paul division hoists, bodies and truck patios. In South Carolina he will be responsible for sale and distribution of Findlay division products only.




D. J. Byrd

W. E. Toensing

Mr. Toensing will be responsible for sale and distribution of Gar Wood truck and tractor equipment, Buckeye ditchers, shovels, fine-graders and spreaders and St. Paul truck equipment, as manufactured by the three Gar Wood Divisions.


Prior to his new appointment, Mr. Toensing was service manager for the St. Paul division and Mr. Byrd, salesman at the Washington branch of Gar Wood Industries, Inc.



The LULL SHOVELLOADER plus Log Lifting Forks — the new indispensable production unit for loggers and lumbermen.

Other SHOVELLOADER attachments — quickly interchangeable — include Material Buckets, Coal and Snow Buckets, Concrete Buckets, Lifting Cranes and Bulldozers which increase profits the year around.

SHOVELLOADERS are built in 3 sizes — all are equipped with **LIFETIME** pistons and rings — every model designed for cab installation except extra-high lift SHOVELLOADERS.



See Your Industrial Tractor Distributor or Write

**LULL MANUFACTURING CO.**

MINNEAPOLIS 6, MINN.



## Fort Gibson Dam Plant Described

(Continued from page 27)

with one band saw, two circle saws and a planing machine. The form lumber is oiled with a non-staining mineral oil in a dip vat located at the carpenter shop. All lumber that is too long to be dipped is stacked above the vat and sprayed. Drain boards, made of corrugated metal, catch all drippings from the spraying operation and return the oil to the vat. After the lumber is oiled, it is stacked in such a manner as to permit air circulation and is allowed to stand for a period of time to obtain maximum penetration of the oil.

Absorptive form lining is used on forms where the concrete surface will be exposed. In order to prevent wrinkling of the lining, which occurs when the weather is damp and the lining is exposed for a relatively long period before concrete placement, the 3 by 5-foot sheets of lining are stapled to the forms only a short time in advance of actual concrete placement. A neat appearing surface is being obtained through the use of form lining because the amount of entrapped air and water, usually present where unlined forming is used, is greatly reduced.

All panel forms are cleaned and oiled after stripping in preparation for further use.

### Concrete

The cement used in concrete on this project is of Type II, moderate heat of hydration. The bulk cement is transported directly to the job site in railroad cars. A screw conveyor transfers cement from the cars to a 7,500-barrel storage silo and from the silo to a bin in the batching plant.

Fine and coarse aggregates are produced by M. O. Weaver, Inc., Des Moines, Iowa, from a quarry located approximately 4½ miles from the dam site. Sand, as specified by contract specifications, is manufactured from limestone by means of ball-mills, cone crushers, and air separators as shown on the appended aggregate plant flow chart. Specification requirements and average gradations are as follows:

Specification Requirements	Average Gradation Screened
Size	Per cent Passing
¾	100
8	81.3
16	52.0
30	33.5
60	15.7
100	6.6
200	3.4
FM	2.4 to 2.9

Segregation of fine aggregate is overcome by the addition of 2 per cent moisture to the finished product by means of a

water spray as the aggregate is loaded on trucks to be transported to the stockpiles.

Four sizes of coarse aggregate are manufactured at the crushing plant. Cedar-rapids crushing equipment is used along with Sturtevant air separators for the crushing operation. Aggregate sizes 3 to 6-inch, 1½ to 3-inch, ¾ to 1½-inch, and #4 to ¾-inch are being produced at present.

The appended table gives the material proportions as used in the four classes of concrete placed.

One of two types of air entraining agent is used in all classes of concrete. "Darex," manufactured by the Dewey and Almy Chemical Co., Cambridge, Mass., and "Protex," made by the Autolene Lubricants Co., Denver, Colo., have been used successfully. Increased workability and lower water demand are some of the beneficial results obtained by the use of air entraining admixtures.

Concrete mixing water is taken directly from the Grand River, heated, refrigerated or frozen as required to maintain a concrete temperature of 56 to 60 degrees Fahrenheit at time of placement. In addition to heating the concrete mixing water, it is necessary to heat the aggregate when spells of prolonged cold weather occur. This is done by passing steam through pipe coils embedded in the aggregate bins on the batch plant.

During the summer months when prevailing ambient temperatures are 90°F. and above, the mixing water contains

## You Can't Beat Welded Construction

### WELLMAN Williams Type BUCKETS

- Wellman pioneered welded rolled steel construction for longer life and greater service. It's the extra strength that gives the extra, low-cost digging power. Whatever your requirements... whether for Multiple Rope, Power Arm, Dragline, Power Wheel or Special Service—specify Wellman! ¾ to 16½ yd. capacity.

SEND FOR BULLETIN

THE WELLMAN ENGINEERING COMPANY  
7006 CENTRAL AVENUE  
CLEVELAND 4, OHIO



over 50 per cent ice. The ice is produced by three Vogt tube ice machines, 60-ton capacity each, manufactured in Louisville, Ky. Ice, cut in about 3/8-inch rings, 2 inches in diameter, is fed into a weighing hopper in the batching plant by a screw conveyor. The ice hopper is equipped with a drain that eliminates the water caused by melting ice and insures that the amount of ice added to a batch of concrete is dry weight.

#### Concrete Batch Plant

The concrete batch plant is approximately 80 feet in height with the aggregate storage bin at the top of the tower. The aggregate conveyor belt, which is inclined at about 17 degrees from horizontal, empties into the storage bins at the 80-foot height. Batching hoppers, where the various materials are weighed, are located on the next floor 26 feet below the top of the storage bins. Also located on this floor is the batch plant instrument control panel. Four Koehring tilting type mixers, capacity of 2 cubic yards each, are located on a floor level 16 feet below the control floor. The mixers are arranged on the perimeter of a circle in order to permit charging of the mixers through one central chute. A cone-shaped hopper receives the concrete dumped from the mixers and flat bed Euclid trucks, carrying 2 Blaw-Knox concrete buckets, 2 or 4 cubic-yard capacity each, transport concrete from the hopper to the forms. The batching plant was designed by C. S. Johnson Co., Champaign, Ill.

#### Steam Gantry Cranes Used

By the use of two steam gantry cranes mounted on rails located at the downstream limit of the gravity monoliths and supplemented by crawler-type cranes, the concrete buckets are hoisted from the trucks to the forms. The concrete placement crew, present at the forms, using two-man vibrators consolidates the concrete as it is dumped from the buckets. Mass concrete pours are made with a slump average of approximately 2 inches and vibration is held to a minimum consistent with proper consolidation of the concrete mass.

In all monoliths based on gravity type design, a standard five foot lift is used in raising the structure, with the exception of the first four pours. Each monolith foundation area is covered by a minimum of four 2 1/2 foot lifts and then the standard lift is used in constructing the remainder of the monolith. It is required by the contract specifications that 120 hours time elapse between placement of successive 5 foot lifts in any one monolith.

#### 14-Day Concrete Cure

The concrete is water cured for a period of 14 days. All exposed surfaces are kept moist by a sprinkler system that is installed on or near the concrete within 2 to 5 hours after completion of pouring operations. During the curing period, concrete surfaces are never allowed to become dry after placement. The contractor

has a curing and laitance cutting crew assigned to a maximum of 2 monoliths per man to insure that curing requirements are properly carried out.

In cases where water curing is not practicable and no additional concrete is to be bonded to the surface, a surface membrane type curing compound is used. The compound is sprayed on the surface immediately following the final finishing operation. Concrete surfaces to which the curing membrane has been applied are protected from all foot and vehicular traffic for the specified curing period.

In the winter when the ambient temperature drops below freezing, the concrete is covered with canvas stretched

over wooden frames approximately 20 by 40 feet. These panels are supported above the concrete a convenient distance, depending upon the location, to form an air space. Then tubes from 100,000 BTU gasoline heaters are inserted under the canvas paneling through which sufficient heat is supplied to maintain an air temperature next to the concrete of from 50 to 70 degrees F. for the first five days and a temperature above freezing for the remainder of the specified curing time.

#### Tainter Gates

The spillway discharge will be controlled by thirty tainter gates 40 feet long

(Continued on page 60)

## Dig Deep **FAST!** WITH AN OSGOOD



#### Get MORE Yardage . . . Even In Tight-Fit, Hard-To-Get-At Corners

Move an agile Osgood hoe right up to the job—and into it—with no lost motion. Its reputation is built on superior speed, mobility, power, and a high and far reach that allows the operator to pick up a load anywhere and to drop it accurately—wherever he wants it.

Yes, whatever the job, you can move more dirt, faster, with an Osgood—Shovel, Dragline, Crane, Clamshell, or Hoe. Gasoline, Diesel or Electric powered—3/4 to 2 1/2 cu. yds. Write for descriptive literature and specifications.

POWER SHOVELS • CRANES • DRAGLINES • CLAMSHELLS • BACKHOES • PILE DRIVERS

THE **OSGOOD** CO. **O-G** THE **GENERAL** CO.  
EXCAVATOR

MARION, OHIO

DIESEL GASOLINE OR ELECTRIC POWERED • 3/4 TO 2 1/2 CU. YD. • CRAWLERS & MOBILCRANES

## Fort Gibson Dam Plant Described

(Continued from page 50)

and 35 feet high. These gates are located on the spillway weir between the piers supporting the bridge. With all gates in a raised position, the maximum discharge will be 919,000 c.f.s. The gates are being fabricated by Brown Engineering Corp., Houston, Texas. They will be constructed, principally, of semi-corrosion resisting steel and will be of arc welded construction.

The gate operating machinery is being furnished by Lakeside Bridge and Steel Co., Milwaukee, Wisc. Each gate is equipped with a 7.5 HP, 440 volt, 3 phase

hoisting motor which is individually controlled. The electrical and mechanical control features are such that the gates are opened in increments of 9 inches until the half-open point is reached. From the position of half-open the gates are raised in one continuous operation. The gate closing operation is also continuous. At any position along the traverse the gates may be stopped and held during either the opening or closing operation. The tainter gate operating machinery is located on the bridge piers immediately below the roadway.

### Penstock Gates

Two catpillar type gates are provided for closing the penstock supplying water for each generating unit in the powerhouse. The effective opening to be closed is 14 feet 6 inches by 20 feet 2 1/4 inches. Under the present contract, gates will be installed in eight of the twelve conduits and destructible concrete bulkheads will be placed in the remaining four.

The penstock gates and operating machinery are being fabricated by Consolidated Western Steel Corp., Los Angeles, Calif. Each 14 foot 6 inch by 20 foot 2 1/4 inch vertical lift gate will be operated by individual electric-powered hoists. The gates are self-closing and are operated by cable drum type hoists. The cable is reeled on the drum by power provided through a chain of reduction gears and a ring gear fitted to the drum. A mechanical shoe-type brake holds the machinery when power is off, and releases it when power is provided. This brake can also be released mechanically for manual operation of the hoist. Limit switches stop the gate at closed, full conduit opening, dogging, and maximum raised positions. The gate hoisting machinery is designed to lift the gate at the rate of 2 1/2 feet per minute. All of the eight gates are now on the project site but as yet no installations have been made.

### Project Management

Fort Gibson Dam is being built under the direction of Col. C. H. Chorpeneing, district engineer, Tulsa District, Corps of Engineers. Frank M. Newell is resident engineer on the project and Frank F.

Wingo is office engineer. O. S. McCormick is project manager and H. M. Haugenson is chief engineer for Johnson-Winston-Kiewit, joint contractors. The co-adventure firm is a combination of Al Johnson Construction Co., Minneapolis, Minn., the sponsoring company, Winston Brothers Co., Minneapolis, and Peter Kiewit Sons Co., Omaha, Neb. It is estimated that the dam will be completed during the summer of 1950.

## Fiske-Carter Incorporated as South Carolina Firm

Fiske-Carter Construction Co. of South Carolina has been incorporated with a capitalization of \$400,000. As in the former company of the same name, which the new corporation supplants, W. L. G. MacKenzie is president; William T. Adams, secretary; A. M. Lander, Jr., vice president and assistant treasurer; M. B. Phipps, vice president and assistant secretary, and S. L. Rhodes, vice president. The corporation maintains offices in Greenville, S. C. in the Masonic Temple, at Spartanburg, S. C. on Dunbar Street and at Worcester, Mass. The southern offices specialize in textile and water works projects; the northeastern office, in machine shops and wire works. Fiske-Carter Construction Co. was first formed at Worcester in 1908.

## PUBLIC BUILDING

(Continued from page 50)

ton, D. C., \$219,000 for MacArthur School.  
**BLACKSBURG**—Virginia Polytechnic Institute let contract to Doyle and Russell, Richmond, \$1,145,320 for dormitories A, A-1 and B.


**RUSSELL COUNTY**—Board of Education let contract to Armstrong Construction Co., Kingsport, Tenn., \$736,700 for Castlewold, High School.

**ROANOKE**—Veterans Administration, Richmond, let contract to Virginia Engineering Co., Newport News, at \$508,000 for addition and alterations to dining hall and kitchen for Building No. 4 for Veterans Administration Hospital.

**STAUNTON**—Board of Trustees let contract to Irons & Reynolds, Inc., Washington, D. C., at \$2,054,000 for King's Daughters' Hospital.

### WEST VIRGINIA

**CHARLESTON**—West Virginia University has funds released by Board of Public Works, for completion of new classroom building and new biology building; Baker and Combs, Inc., Morgantown, awarded contract at \$1,523,400 for biology building.



Cost records from job after job prove that Economy's system of Form Engineering and Rental Service means substantial savings in TIME—MATERIAL—MONEY for GREATER PROFITS.

### ECONOMY FORMS CORP.

Home Office • Des Moines

BRANCH OFFICES: Dallas, Tex.; Decatur, Ga.; Fort Wayne, Ind.; Metuchen, N. J.; Los Angeles, Cal.; Denver, Col.

## UNDERPINNING & FOUNDATION CO., INC.

### FOR FORTY YEARS

**Hercules Piles — Arresting of Foundation Settlement  
Caissons — Cofferdams • Shafts — Tunnels — Subways —  
Excavations • Engineering Construction of All Types**

**FREE CONSULTATION • SEND FOR CATALOGUE**

### ENGINEERS & CONTRACTORS

155 East 44th Street

New York 17, N. Y.

## Carolinas Contractors Hold Big Meeting

(Continued from page 29)

Van D. Lott, the associate membership meeting.

Principal addresses at the highway and public works meeting were made by C. R. McMillan, chief highway commissioner of South Carolina, and W. Vance Baise, state highway engineer of North Carolina. Archie N. Carter, manager of the A. G. C. highway division discussed the national picture. Ralph C. Barker, of the Budd-Piper Roofing Co., Durham, N. C., talked at the associate membership meeting.

### Industry's Responsibility

Commissioner McMillan spoke on the public responsibility of the highway construction industry, stressing his view that the democratic victory is an unmistakable trend in the United States toward more governmental regulation and control of private industry where industry itself does not impose its own restraints and regulations from within and give greater emphasis to the public interest.

Stating that its ethics are higher today than ever before, Mr. McMillan said highway construction today is big business. His department alone has let construction contracts totaling \$58,413,756 since the war, this work paid for by the more than 450,000 automobile users of South Carolina. "There is simply no way

to avoid the very important fact that both the highway department and the construction industry are jointly accountable to the public for every act and phase of the construction program," with each depending upon the full cooperation of the other.

Both the highway departments and the contractors must work together to bring down costs through improvement methods and practices and the contractors are entitled to a fair margin of profit on the job, but they do not have any vested interest in any proportion of the highway dollar by reason of their businesses, he observed, continuing: "The outlook for future construction in South Carolina is good, if we do a good job. The demand for new construction is greater now than ever before and, as long as the motor vehicle serves as our chief mode of travel, demands for more construction are going to continue to exceed accomplishments."

### Baise Reviewed Progress

Mr. Baise reviewed highway progress in North Carolina since hostilities ceased, placing the value of construction, stabilization and maintenance in that period at \$191,528,000. Of the total, 584 projects for new work cost \$78,525,000 and 158 projects involving resurfacing cost \$7,008,000. State forces did 1,810 miles of

new work at a cost of \$18,104,000, placed 5,937 miles of resurfacing at \$7,368,000 and 14,870 miles of stabilization at an estimated cost of \$14,114,000. Maintenance involved an expenditure of \$44,815,000.

The last two years have seen the largest construction program in the history of the North Carolina State Highway and Public Works Commission. Construction in 1947 cost \$43,000,000; in 1948, \$45,000,000. Approximately 5,000 miles of additional roads have been paved with bituminous or higher type surface. Greatest emphasis has been placed on developing and further improving the secondary systems "to get people out of the mud." Mr. Baise feels that this policy should be carried further until all of the rural areas are accessible to a good road, either hard-surfaced or stabilized to make it serviceable throughout the year.

Mr. Baise revealed some interesting statistics on recent North Carolina traffic surveys. More than 70 per cent of rural traffic is on the rural state system and only about 30 per cent is on the rural secondary system, thus making not more than 20 per cent on the rural secondary system, when judged by the total traffic in the state. A total of 9,046 miles of unpaved highways were carrying more than 100 vehicles daily and 37,497 miles of rural highways were carrying less than

(Continued on page 62)

# POWERFUL

**THE TOUGHER THE JOB  
THE MORE YOU NEED A BAKER**

The sensational performance of the giant Allis-Chalmers HD-19 teamed up with the Baker Hydraulic Bulldozer has rocked the entire earthmoving industry — set a new high in production — a new low in cost. Compare the Baker with any bulldozer on the market — you get direct lift; direct down pressure; engine mounting, 5-position adjustable blade tilt; interchangeable bulldozer or grade-builder blades; blade pitch adjustment; smooth, fast, dependable hydraulic control, plus extra rugged construction which has made Baker famous throughout the world.

**BAKER MFG. CO., SPRINGFIELD, ILL.**



# BAKER



**BULLDOZERS • GRADE BUILDERS • SNOW - PLOWS**

## BULLDOZERS — GRADEBUILDERS — SNOW PLOWS

# Carolinas Contractors Hold Big Meeting

(Continued from page 61)

100 vehicles a day.

The rural county system in 1947 earned approximately \$11,000,000, based on the vehicle usage. Expenditures on the system in the same period amounted to \$35,000,000 and in the last fiscal year, slightly less. "The difference," Mr. Baise pointed out, "obviously represents earnings of the primary highway system used to subsidize the secondary county system." Such a subsidy is necessary, he stated, on some state highways through sparsely settled areas, as well as on county roads in order to have a well integrated state and county system.

Most of North Carolina's primary roads were paved under the bond issue of the 1920's and are from 20 to 25 years old. There are about 800 miles of 16-foot pavement and 3,600 miles of 18-foot pavement that should be widened to take care of present day traffic and a large amount that should be relocated and rebuilt. The secondary system, while in need of additional paving and stabilization, is one of the best in the South or in any rural state in the Nation.

North Carolina has a total of 11,362 miles on the state system and about 52,000 miles on the secondary system, making a total of 63,362 miles, or a length that will stretch two and one-half times around the earth. This is understood to

be the largest system of roads being maintained by any state of the Nation and probably the largest being maintained by any organization in the world. Of the entirety, more than 16,500 miles have been paved or are under contract for paving.

North Carolina highway authorities have spent \$320,000,000 on construction of new roads since 1921 and many other millions for maintenance. "I am sure all realize," Mr. Baise concluded, "the need for protecting this great investment and expanding it so as to take care of the heavy increase in highway traffic. What we need in North Carolina is a balanced highway system" and to obtain it will require development and expansion of the secondary system and also development and improvement of the primary system.

## Highway Needs Cited

Mr. Carter, who climaxed the program of the highway division meeting, cited the need for \$22,000,000,000 worth of new highway construction. In a short but invigorating talk, he pictured the present construction situation and described the part the airport and rural electrification programs will play in the immediate future. The American people, he stated, are sold on solving the stream pollution problem. Soil conservation is also an up and coming field for the construction industry with many contractors already participating in the work.

At the building division meeting, with P. L. Shackelford, presiding, Mr. Pease declared that one of the most serious problems today is that of costs. Where present prices will stabilize, he declined to predict but using mill construction costs as an example, he cited the \$1.25 per square foot in 1915, the \$2.50 per

square foot from 1920 to 1939 and the \$4.50 to \$5.00 cost in 1945, and stated that after each war the price doubled and then leveled off. He expects the current high prices to follow the same pattern.

## Material Flow to Improve

No reduction in labor rates was forecast. In fact, increases are seen, with declines in the prices of some materials as they drop from the critical list. No improvement was forecast by Mr. Pease in the steel situation. As the flow of materials becomes more plentiful, he said, and the contractor can schedule his labor and materials to avoid costly job shutdowns, then can a substantial saving be made with its consequent reduction in costs. However, the change will not occur before April.

Asserting that the country is "not going into a tailspin," the Charlotte engineer emphasized the necessity for the public to recognize a new level of construction prices before there can be a great increase in commercial and industrial building. Further, industry cannot afford to pay prices for floor space on which it cannot pay dividends. Emergency building and housing are catching up with demand. Except for government aid projects and public works for which bonds have been issued, there are few new projects, he said.

## Accomplishments Reviewed

Mr. Snow reviewed congressional legislation affecting the building industry, the \$400,000,000 veterans' hospital construction, the federal aid hospital program, and the federal mortgage insurance program, the labor situation and basing point decision and listed accomplishments of the national A. G. C. during the past year. The A. G. C.-A. I. A. committee, settlement of jurisdictional disputes, apprentice training, effect of the draft law, bidding procedure, were among these. For 1949 he predicted anti-inflation measures, modifications in the Taft-Hartley law, slightly increased dollar volume of construction, no appreciable increase in construction costs, and perhaps an easing in the skilled labor shortage.

The address scheduled for delivery to the second general session of the convention by Dexter C. Martin, director of

## THE NEW LOOK for the MIGHTY MIDGET



## BREAK WITH POWER, SPEED, ECONOMY

The MIGHTY MIDGET reduces the cost of breaking asphalt and concrete to a minimum cost that is unequalled by other methods. Tamps backfill at an unbelievable pace; gives high density. All controls within operator's reach. Operates on 105 C.F.M. compressor.

Ask your dealer or write for complete information.

**R.P.B. CORPORATION**  
2751 EAST 110 STREET - LOS ANGELES, CALIFORNIA

**ATLAS  
CONCRETE  
FORMS**  
Walls • Cylinders • Floors • Sewers  
**Irvington**  
FORM & TANK CORP.  
Irvington, N. Y.

## Cut your Asphalt Costs on those small mix jobs!

The Foote Kinetic Asphalt Mixer with its new mixing method will give you eight to ten batches more per barrel of asphalt.

This will soon pay for the mixer! It can be towed behind any truck or car, handles any cold mix without additional equipment and can handle hot mixes in conjunction with kettles.

Capacity 3 cu. ft. in 30 seconds. Ask for Bulletin K-100.



**the FOOTE**  
*Kinetic*  
mixer

**THE FOOTE CO., INC.**

1906 State St., Nunda, New York  
Subsidiary of Blaw-Knox Co.

**A BLAW-KNOX PRODUCT**



the South Carolina Aeronautics Commission was read by Dabney R. Yarborough, chief of planning for that agency. He disclosed that if appropriations are made for the next seven years as contemplated by the Federal Airport Act, the Carolinas will get \$12,228,074 for airport construction, which when matched by local funds will make more than \$25,000,000 available.

#### Airport Program Slow

Lack of momentum in the airport construction program was attributed to no definite financing policy on the part of the sponsors. Federal money is available, but is not being used, the South Carolina official said. In his state alone, about \$800,000 in federal funds is still unclaimed and other states have similar situations. Some cities do not have the money and others have more pressing projects.

Cities of South Carolina in the past have furnished less than one per cent of the total funds expended by airports and those who would carry out such projects are now faced with putting up fifty per cent of the funds unless some other arrangement is made. The state legislature has been asked to authorize the State Aeronautics Commission to match federal funds. Under the proposal the commission would issue bonds totaling \$1,256,000 for airport construction, with the aviation gasoline tax pledge to amortize the loan. This would give the South State \$2,500,000 for airport construction.

#### State Action Urged

Answering the question "Is the construction of airports the responsibility of the cities," the speaker pointed out that the airplane is a vehicle that never enters the city limits. It is a means of transportation between cities, not within them. Cities in the past have had to take the initiative because the states have not assumed their rightful obligation, he declared, urging every possible step to foster and develop airport facilities.

Executive Secretary Robert Patton read the report for Henry O. Strohecker, Jr., on the progress made on the army affiliation program. William Muirhead, past president of both the Carolinas Branch and the National A. G. C., presented the report of the educational program, which he termed "an investment in your own industry." Apprentice training was described in the report by Hal S. Crain, who said his committee's work was directed at the boys who can't go to college. More than \$58,500 has been raised for the two programs—\$20,000 for apprentice training and \$38,500 for the engineering educational endowment fund.

#### Separate Bids Opposed

Mr. Shackelford's report of the building division brought out that the A. G. C. is opposed to bidding the mechanical items separate from the general contract proposal. A comparison of 29 jobs, it was stated, showed only five that favored the separate award procedure. A resolution was passed urging the members to start their work-week on Monday and pay off

(Continued on page 64)

## 2 CUMMER PLANTS Location:--Columbus, Ohio


Smaller plant is 10 years old, equipped with one-ton mixer and 40-ton bin—60 tons per hour.

Larger plant is 3 years old, equipped with two-ton mixer and 60-ton bin—80 to 90 tons per hour.

Both plants equipped with Cumber two-fire Combination Dryers and Dust Collection equipment.

### The F. D. Cumber & Son Company

East 17th & Euclid, Cleveland 15, Ohio



DOES IT  
WITH A  
ROGERS

DOES IT  
WITH A  
ROGERS

### ECK MILLER OF OWENSBORO, KENTUCKY



using a Rogers Model D-35-D and a Rogers Pole Type Trailer loaded with 80,000 lbs. of steel tank 67 feet in length. The conventional trailer mounts a fifth-wheel type of bolster which supports the front of the load and tows the pole trailer which carries the rear of the load.

### A. B. BURTON Co., Inc.

OF LYNCHBURG, VA.



Moving this heavy Northwest power shovel from job to job presents no problem to the A. B. Burton Co. when they have their D-50-D Rogers semi-trailer to rely upon.

**and YOU CAN DO IT WITH A ROGERS** trailer, whether the jobs involved require the hauling of light, medium or heavy equipment. Why not learn in detail just what Rogers has to offer? Write TODAY for your copy of the NEW CATALOG.



### ROGERS BROTHERS CORPORATION

DESIGNERS and BUILDERS of HEAVY DUTY TRAILERS  
SINCE 1915

222 ORCHARD ST. ALBION, PENNA.



## Carolinas Contractors Hold Big Meeting

(Continued from page 63)

at the end of the week. A second resolution, also unanimously adopted, requested the State of North Carolina to discontinue the use of prison labor and force account and return to the contract system.

The highway division was the largest and best attended since it was started, it was reported by William F. Rowe, its chairman. The four points he emphasized were wage stabilization and premium pay, steps to obtain firm prices on cement, steel and other materials, the availability of equipment and the possibility of securing the cooperation of the Associated Equipment Distributors, and cooperation between engineers and contractors.

### Subcontractors Lauded

Mr. Barker's address to the associate membership division recognized the efforts of the sub-contractors and material firms, and the difficulties caused by shortages. Other points in his talk were substitutions, the "cement case" and its perplexities, at the same time urging closer

cooperation between contractors.

He sees little hope that prices will drop under present conditions with the complications of shortages of materials, high wages and "none too efficient operation by the trades people." Present per-bed costs of \$8,000 to \$10,000 were contrasted against the previous hospital construction costs of \$3,000 per bed, with government institutions ranging from \$18,000 to \$25,000 per bed.

### Associate Members' Report

The report of the associate membership division was delivered by Lloyd D. Mumaw, of Easterby & Mumaw, of Charlotte, in the absence of Chairman Lott. Apprentice training and the low efficiency of the G. I. training program, the success of the A. G. C. program, overtime on overtime were among the subjects covered. Marret Wheeler, of Charlotte, was elected chairman of the advisory committee; Tom Boyle, of Columbia, vice chairman and Collier Cobb, Jr., of Chapel Hill, a new member. The terms of Messrs. Craven and Cagle run for another year.

### Banquet Climaxes Convention

Colorful climax of the convention was the banquet held Saturday evening, with George A. Bowie, author and lecturer, the guest speaker. Other hours between and after business meetings were occupied by the traditional bingo game held Friday evening after the buffet supper attended by the conventioners, a golf tournament, ladies' luncheon and tour of the spacious hotel where the convention was held, as well as a showing of "Highway U.S.A.," the color film of America's scenic beauty developed by Barber-Greene Co.

The list of those present, as issued by the Carolinas Branch included the following:

Mr. & Mrs. W. Elliott Abbot  
Mr. & Mrs. R. C. Alken  
E. G. Alford  
Mr. & Mrs. T. C. Anderson  
Mr. & Mrs. Charles W. Angie  
J. B. Archer  
Mr. & Mrs. Reuben B. Arthur

Mr. & Mrs. W. Vance Baise  
Mrs. Margaret Ballenger  
C. P. Ballenger  
Mr. & Mrs. T. C. Ballou  
Mr. & Mrs. Ralph C. Barker  
B. E. Barksdale  
Howard Batts  
Mr. & Mrs. J. H. Bell  
George Bethune  
Mr. & Mrs. D. J. Bethuram  
Mr. & Mrs. Donald E. Bither  
F. J. Blythe  
Mr. & Mrs. F. J. Blythe, Jr.  
Mr. & Mrs. W. C. Boren, III  
Mr. & Mrs. Robert F. Bowe  
Mr. & Mrs. William F. Bowe  
Mr. & Mrs. Homer W. Bowers  
George A. Bowie  
Mr. & Mrs. Edwin B. Boyle  
Mr. & Mrs. Thomas B. Boyle  
Mr. & Mrs. Richard A. Bradshaw  
Mr. & Mrs. Spencer S. Brewer  
Mr. & Mrs. E. H. Brown  
Mr. & Mrs. W. F. Brown, Jr.  
Glenn C. Browning  
Mr. & Mrs. R. F. Brownee  
Miss Lillian Brunson  
Mr. & Mrs. Raymond A. Bryan  
Mr. & Mrs. T. A. Burton

Wilkins Cagle  
W. C. Caltun  
Mr. & Mrs. A. L. Carr  
Ray L. Cargill  
Archie N. Carter  
Mr. & Mrs. H. M. Caskey  
Mr. & Mrs. T. W. Cecil  
Mr. & Mrs. J. Keith Chilton  
Mr. & Mrs. J. L. Christian  
P. D. Christian, Jr.

(Continued on page 66)

## •• DREDGES ••

### HYDRAULIC • DIPPER CLAMSHELL

Bolted sectional steel hulls  
for landlocked, inland waters

If you need a dredge, write us!

**AMERICAN STEEL DREDGE CO. INC.**  
FORT WAYNE 1 - INDIANA - U.S.A.

DESIGNERS AND BUILDERS OF DREDGING EQUIPMENT SINCE 1905

### TINNEY DRILLING COMPANY Diamond Core Drilling

CORE BORINGS for Foundations, Dams, Bridges and  
all Heavy Structures — GROUT HOLES  
Grafton, West Virginia

Foundation  
Test  
Borings  
& Grouting

## PENNSYLVANIA ★ DRILLING CO. ★

Pittsburgh 20, Pa. Walnut 5816

Industrial  
& Municipal  
Water  
Development

### MOTT CORE DRILLING COMPANY

Diamond Core Drilling Contractors  
Diamond Core Test Borings for Bridges, Dams, Buildings.  
High Pressure Grouting by Contract.  
Foundation Testing, Dry Core Samples.  
Wash Borings and Soundings.

MAIN OFFICE & SHOPS, HUNTINGTON, W. VA.

PHONE 7121

### VIRGINIA ENGINEERING COMPANY, INC.

Government — INDUSTRIAL — Municipal  
GENERAL CONTRACTORS  
NEWPORT NEWS, VIRGINIA

### SYDNOR PUMP & WELL CO. INC.

ESTABLISHED 1891

We Specialize in Water Supply and in Pumping Equipment

1305 BROOK ROAD, RICHMOND 22, VA.

## PINE HALL BRICK AND PIPE COMPANY

INCORPORATED

Manufacturers of  
VITRIFIED CLAY PIPE

WINSTON SALEM, NORTH CAROLINA

## SALEM ELEVATORS

for Vertical Transportation  
Passenger and Freight

Electric or Hand Power

Quality Gray Iron Castings and Machine Work

SALEM FOUNDRY & MACHINE WORKS, INC., SALEM, VIRGINIA



COMPANION TO  
THOR'S  
GREAT "25"

Here's a new Thor breaker so good it will "sell in pairs!"

It's the Thor "24"—a completely new 70-pound breaker that answers a big demand for a demolition tool just under the heavy duty class.

More than this, two of the new Thor "24's" will operate at full efficiency off one 105 cubic foot compressor . . . another popular demand!



The Thor 84-pound "25" leads the heavy duty field . . . the Thor 59-pound "23" outpowers the light duty class. NOW Thor places a great new leader in the 70-pound class.

Watch for full details soon from your Thor distributor.

#### INDEPENDENT PNEUMATIC TOOL COMPANY AURORA, ILLINOIS

600 W. Jackson Blvd., Chicago 6, Ill. Phone: STate 2-3960.  
1411 Third Ave. N., Birmingham 4, Alabama. Phone: 3-5801.  
1701 Fairmount Ave., Philadelphia 30, Pa. Phone: STevenson 4-6804.

**Thor** PORTABLE POWER  
**TOOLS**



2" to 10" sizes

Extra powered, conservatively rated and sure-primed by two simultaneous priming actions, Jaeger Pumps have the capacity to dewater faster and the stamina to pump until the job is done. Overall enclosures protect from weather. See your Jaeger dealer.

**THE JAEGER MACHINE COMPANY**  
Columbus 16, Ohio

regional offices: 1504 Widener Bldg. 226 N. La Salle St. 235 American Life Bldg.  
Philadelphia 7, Pa. Chicago 1, Ill. Birmingham 1, Ala.

COMPRESSORS • MIXERS • HOISTS • PAVING EQUIPMENT



### White Front End Loaders Have Extensible Booms

The extending boom feature of White Loaders is highly commended by all users. It permits loading trucks without hand spreading or coming close to truck body. Can fill high bins or extend over walls.

Bucket is close to wheels when loading. At top it moves forward to discharge 2 1/2' ahead. Can be dumped at any point in lift.

Mechanical operation, from front of engine. Backfiller blade goes in bucket seats.

Made ONLY for Oliver 88; Case DI, SI, CI; Minn-Moline UTI; International I-6, ID-6, I-30, =20.

Write for Catalog

Elkhart **White Mfg. Co.** Indiana

## Carolinas Contractors Hold Big Meeting

(Continued from page 64)

Mr. & Mrs. Collier Cobb, Jr.  
H. L. Coble  
Miss Jean Coble  
Mr. & Mrs. Leon G. Coble  
Robert W. Coleman  
Mr. & Mrs. Frank H. Conner  
Mr. & Mrs. E. L. Cook  
Mr. & Mrs. G. F. Cooper, Jr.  
William N. Cox  
Mr. & Mrs. Hal S. Crain  
Ashbury E. Craven  
Dean H. Crawford, Jr.  
Mr. & Mrs. John Crosland  
Mr. & Mrs. Wm. P. Crosland

Mr. & Mrs. Starr Davis  
Guy L. Dawson  
W. D. Dean  
Mr. & Mrs. Oscar Deuring  
Mr. & Mrs. L. A. DeHarden  
Mr. & Mrs. E. M. Denbo  
Mr. & Mrs. I. Denemark  
Mr. & Mrs. C. R. Dial  
Mr. & Mrs. L. W. Dickerson  
Mr. & Mrs. N. K. Dickerson, Jr.  
Mr. & Mrs. James F. Dixon  
Mr. & Mrs. Frank Dowd  
Mr. & Mrs. Sam C. Dreyfus

Mr. & Mrs. F. C. Easterby  
Mr. & Mrs. S. D. Easterby

Francis Fearon  
O. B. Fisher  
H. E. Foreman  
Selwyn L. Flournoy  
Mr. & Mrs. A. J. Fox

Joe A. Garrett  
Mr. & Mrs. C. V. Garth  
W. D. Garvin  
Mr. & Mrs. Craig Gaskell  
Mr. & Mrs. Roy E. Gelse  
Mr. & Mrs. Clyde D. Goforth, Jr.  
Mr. & Mrs. Roy L. Goode  
Mr. & Mrs. Sim W. Grady  
Mr. & Mrs. C. T. Hagan  
Mr. & Mrs. James F. Hagood  
R. F. Handley  
Ira H. Hardin  
Mr. & Mrs. Frank M. Harris

Mr. & Mrs. James J. Harris  
Mr. & Mrs. Morgan C. Harris  
Mr. & Mrs. M. S. Hayworth  
Robt. C. Heffron  
Mr. & Mrs. L. C. Heslep  
Mr. & Mrs. A. J. Hewett  
E. G. Higgin  
Mr. & Mrs. C. A. Hines, Jr.  
Mr. & Mrs. E. H. Hines  
Mr. & Mrs. T. M. Howell  
William F. Huber  
Mr. & Mrs. Robert N. Hunter  
Mr. & Mrs. J. B. Hutter, Jr.  
A. A. Hyatt

D. J. Jones

Mr. & Mrs. Irwin Kahn  
Mr. & Mrs. M. B. Kahn  
Mr. & Mrs. George W. Kane  
Mr. & Mrs. C. A. Keppler  
Miss Marion Kiker  
Mr. & Mrs. W. B. Kiker  
Mr. & Mrs. Walter W. King, Jr.  
A. H. Klein  
Mr. & Mrs. Charles J. Kuhn  
Miss Virginia F. Kuhn

Mr. & Mrs. James F. Lalanne  
Mr. & Mrs. S. M. Lankin  
W. C. Landis  
Sam A. Lauer  
Mr. & Mrs. Frank Law  
Mr. & Mrs. Harry N. Levey  
Ray F. Long  
Mr. & Mrs. Harry W. Loving

Hardy McGrath  
Warren J. Mann  
C. Wilbur Marshall  
O. M. Marvin  
Miss E. Millan  
Mr. & Mrs. L. G. Mishoe  
Mr. & Mrs. E. E. Moore  
Thomas A. Moore  
Mr. & Mrs. Frank P. Morris  
Mr. & Mrs. R. V. Moss  
Mr. & Mrs. William Muirhead  
Mr. & Mrs. L. G. Mumaw  
Col. & Mrs. R. L. Mundy  
George W. McAlpin  
Mr. & Mrs. F. A. McCleneghan  
D. D. McDaniel  
Miss Josephine McDaniel  
Mr. & Mrs. V. J. McDaniel  
James McKee  
Mr. & Mrs. T. R. McMeekin  
Mr. & Mrs. C. R. McMillan

George E. Norman  
Mrs. Newton E. Nowell

M. L. O'Neale

Mr. & Mrs. Ralph W. Parks  
Mr. & Mrs. Borlet Patten  
Mr. & Mrs. R. Lewis Patton  
Col. J. Norman Pease  
W. W. Peterson  
Mr. & Mrs. R. H. Pinnix  
Mr. & Mrs. J. Gregory Poole  
James F. Pou  
Robert J. Prentiss

Mr. & Mrs. T. A. Ramsey  
W. T. Ragland, Jr.  
Mr. & Mrs. E. O. Ridehuber  
Gene Rife  
Mr. & Mrs. Ray E. Ritchie  
Mr. & Mrs. Frank W. Robertson  
W. M. Roof  
Mrs. Orah M. Russell

Miss Ruth Sale  
D. E. Saunders  
Mr. & Mrs. J. H. Schlag  
Mr. & Mrs. T. M. Sewell  
Mr. & Mrs. F. L. Shakerford  
Henry M. Shaw  
Mr. & Mrs. H. E. Shelby  
R. B. Shepard  
Mr. & Mrs. C. G. Shockley  
Mr. & Mrs. C. E. Silling  
Mr. & Mrs. E. D. Sloan  
Mr. & Mrs. Walter L. Smith  
W. A. Snow  
Charles A. Snyder  
Mr. & Mrs. E. M. Spang  
Mr. & Mrs. Harvey H. Stewart  
Mr. & Mrs. C. P. Street  
Mr. & Mrs. Ben C. Sutherland

H. P. Taylor  
H. Kirk Taylor  
Mr. & Mrs. A. S. Thomas, Jr.  
Mr. & Mrs. Donald H. Thomas  
Mr. & Mrs. J. B. Thomas, Sr.  
Mr. & Mrs. J. B. Thomas, Jr.  
Mr. & Mrs. C. V. Thomason  
F. N. Thompson  
Mr. & Mrs. J. W. Thompson  
Mr. & Mrs. W. A. Thompson  
Mr. & Mrs. L. G. Tucker  
Mr. & Mrs. Guy M. Turner

Mr. & Mrs. James A. Vaughan

Mrs. Kate Wallace  
Wm. H. Wallace  
Mr. & Mrs. W. W. Wannamaker, Jr.  
Mr. & Mrs. Stem Warren  
Mr. & Mrs. W. H. Weaver  
Mr. James M. Wells, Jr.  
Mr. & Mrs. J. R. West  
Mr. & Mrs. R. Marret Wheller  
Mr. & Mrs. J. Wellford White  
W. R. Whiteley  
Mr. & Mrs. Beaumont Whitton  
Mr. & Mrs. E. L. Whitton  
Mr. & Mrs. John W. Whitton  
Mr. & Mrs. E. I. Williams  
Frank D. Williams  
M. P. J. (Mark) Williams  
Mr. & Mrs. Robert E. Wilson  
Mr. & Mrs. Dwight W. Winkelman  
Master Peter Winkelman

J. W. Yates  
Mr. & Mrs. Dabney R. Yarbrough

### NEW ACCOUNTS WANTED

We are distributors of material handling equipment and are interested in securing additional lines particularly for contractors, oil field and industrial accounts.

RALPH LEE COMPANY

P. O. Box 4178, Houston 14, Texas

## To DISTRIBUTORS and MANUFACTURERS

*If you want new accounts or representatives  
and distributors, write fully to—*

BALTIMORE 3



MARYLAND


Covering the sixteen Southern States

### West Virginia Contractors Attend Greenbrier Meet

A delegation of West Virginia contractors attended the Carolinas branch convention held at White Sulphur Springs. Among them were Ray E. Ritchie, of Boso & Ritchie, of Ravenswood; A. J. Fox, of Thompson & Street Co., Clarksburg; O. B. Fisher, of O. B. Fisher & Sons, Logan; Frank W. Robertson, of Robertson-Henry Co., Huntington; Charles J. Kuhn, and Miss Virginia Kuhn, both of Kuhn Construction Co., Charleston; Homer W. Bowers and J. Keith Chilton, of Bowers & Chilton, South Charleston; Col. R. L. Mundy, South Charleston; Evan L. Harris, Jr., of E. L. Harris & Son, Charleston; W. Elliott Abbott, of W. A. Abbott Co., Charleston, and Eugene H. Brown, executive secretary of the Associated General Contractors of West Virginia.

Mr. Ritchie, who is vice president of the West Virginia branch, welcomed the Carolinas branch to his state. Guests from West Virginia were C. E. Silling and L. G. Tucker, of the Charleston architectural firm bearing their name; M. L. O'Neale, chief engineer, and George W. McAlpin, chief construction engineer of the West Virginia State Road Commission.

# SLASH YOUR DREDGING COSTS with **ELLICOTT** HYDRAULIC DREDGES



- Ellicott is the only organization with the experience and equipment to build any size dredge from 6 to 30 inches. Shown is a 16-inch, deep channel Diesel-powered Dredge.

**W**HATEVER your requirements, whether dredging a river channel, filling a swamp, or producing sand and gravel, your cost per cubic yard of material goes way down with an Ellicott Hydraulic Dredge.

That's because each Ellicott Dredge, from 6-inch to 30-inch machines, is designed to meet your needs. It has the right cutting head for material to be worked, the proper pump for length of the line to the disposal area—completely engineered from stem to stern to operate at the lowest cost.

Ellicott has built hydraulic dredges since 1885 and is the only organization in the world devoted exclusively to hydraulic dredge construction. When you specify Ellicott you get operating economy, because all dredge components are designed, built and delivered by Ellicott—all under one contract!

No matter if you wish to assemble your dredge from Ellicott components and plans, or want the dredge delivered complete, Ellicott is prepared to submit estimates without obligation. Write today for full information on Ellicott Dredges.

- COMPLETE LINE from 6 to 30 inch equipment for all dredging requirements.
- 63 YEARS OF EXPERIENCE with hydraulic dredges.

- UNDIVIDED RESPONSIBILITY... designed, built, delivered under one Ellicott contract.
- PROVED PERFORMANCE in the U.S.A. and abroad.



## HYDRAULIC DREDGES

any type—any size—any service


**ELLICOTT MACHINE CORPORATION**

1609 Bush Street, Baltimore, Maryland, U. S. A.

JANUARY, 1949

the Hoists that make all others obsolete

## JAEGER TWO SPEED HYDRO-HOISTS



1. JUST SHIFT A LEVER to high gear for speed with lighter loads.



2. **HYDRAULIC CONTROL**—just like \$25,000 cranes.



3. **AUTOMOTIVE TRANSMISSION** provides interchangeable use of standard gas, electric or diesel power at efficient 1800 rpm.

4. **FABRICATED STEEL THRUOUT**—no broken side frames, drum flanges.

5. **Instant releasing hydraulic clutches** with single adjustment, air-cooled hydraulic brakes, self-aligning bearing blocks, many advanced features.

POPULAR PRICED 25-40 HP "UTILITY" MODELS: Gas or electric, 1 or 2 drums. Ask for Catalog HU-8.


60-100 HP "ERECTOR" MODELS: Gas, electric, diesel; 1, 2, or 3 drums. Ask for Catalog HE-8.

### THE JAEGER MACHINE CO.

Main Office and Factory  
Columbus 16, Ohio

REGIONAL OFFICES: Philadelphia 7 Chicago 1 Birmingham 1  
1504 Widener Bldg. 226 N. La Salle St. 235 American Life Bldg.

**COMPRESSORS • PUMPS • MIXERS • PAVING MACHINERY**



**MAXIMUM EFFICIENCY**, low cost and easy installation are the outstanding advantages of **TENSULATE Mineral Wool**, available in batt, granulated and loose wool form.

Installed in attics, roof areas and sidewalls, **TENSULATE**... with its millions of dead air cells... reduces summer temperatures as much as 15 degrees, saves up to 40% in fuel consumption in winter.

**TENSULATE** has stood all tests of practical use for over two decades. Permanent and lasting as stone... fireproof, sound-proof.

Call or write for full information and prices.

**Tennessee Products & Chemical Corp.**

Nashville 3, Tennessee



## PRIVATE BUILDING

(Assembly, Commercial, Residential, Office)

	December, 1948	Contracts Awarded	Contracts to be Awarded	Contracts Awarded Twelve Months 1948
Ala. ....	\$2,644,000	\$550,000	\$18,361,000	
Ark. ....	64,000	530,000	11,068,000	
D. C. ....	2,000,000	5,850,000	11,596,000	
Fla. ....	8,446,000	4,591,000	171,691,000	
Ga. ....	6,157,000	15,420,000	31,221,000	
Ky. ....	100,000	1,300,000	564,000	
La. ....	8,903,000	2,530,000	43,052,000	
Md. ....	1,340,000	1,064,000	69,693,000	
Miss. ....	641,000	2,150,000	8,389,000	
Mo. ....	1,149,000	745,000	35,589,000	
N. C. ....	775,000	2,130,000	29,129,000	
Okla. ....	3,534,000	3,190,000	20,315,000	
S. C. ....	1,868,000	150,000	18,940,000	
Tenn. ....	5,518,000	1,894,000	44,510,000	
Tex. ....	13,055,000	27,740,000	185,666,000	
Va. ....	5,898,000	1,420,000	25,589,000	
W. Va. ....	555,000	.....	9,333,000	
<b>TOTAL</b> .....	<b>\$62,000,000</b>	<b>\$72,419,000</b>	<b>\$733,200,000</b>	

## ROADS, STREETS, BRIDGES

	December, 1948	Contracts Awarded	Contracts to be Awarded	Contracts Awarded Twelve Months 1948
Ala. ....	\$.....	\$910,000	\$12,952,000	
Ark. ....	.....	.....	1,431,000	
D. C. ....	.....	.....	4,188,000	
Fla. ....	3,802,000	180,000	22,106,000	
Ga. ....	964,000	850,000	34,469,000	
Ky. ....	174,000	.....	20,709,000	
La. ....	2,470,000	2,182,000	42,816,000	
Md. ....	2,275,000	5,315,000	41,505,000	
Miss. ....	3,176,000	280,000	15,411,000	
Mo. ....	162,000	4,510,000	27,350,000	
N. C. ....	2,565,000	1,290,000	28,969,000	
Okla. ....	3,296,000	2,490,000	27,387,000	
S. C. ....	2,963,000	2,100,000	24,821,000	
Tenn. ....	4,574,000	1,460,000	16,753,000	
Tex. ....	7,609,000	2,590,000	132,753,000	
Va. ....	51,000	290,000	8,924,000	
W. Va. ....	1,753,000	.....	10,617,000	
<b>TOTAL</b> .....	<b>\$35,834,000</b>	<b>\$24,730,000</b>	<b>\$469,193,000</b>	

## PUBLIC ENGINEERING

(Dams, Drainage, Waterworks, Sewers, Etc.)

	December, 1948	Contracts Awarded	Contracts to be Awarded	Contracts Awarded Twelve Months 1948
Ala. ....	\$468,000	\$5,825,000	\$12,152,000	
Ark. ....	465,000	5,525,000	22,469,000	
D. C. ....	313,000	390,000	3,419,000	
Fla. ....	2,331,000	6,540,000	28,757,000	
Ga. ....	356,000	62,070,000	11,807,000	
Ky. ....	71,000	3,730,000	10,262,000	
La. ....	2,467,000	4,965,000	41,779,000	
Md. ....	1,071,000	3,591,000	25,228,000	
Miss. ....	544,000	2,995,000	10,808,000	
Mo. ....	2,468,000	4,375,000	13,586,000	
N. C. ....	508,000	3,065,000	16,578,000	
Okla. ....	1,284,000	3,076,000	23,562,000	
S. C. ....	2,122,000	2,522,000	13,583,000	
Tenn. ....	3,897,000	7,615,000	17,756,000	
Tex. ....	9,219,000	29,185,000	118,176,000	
Va. ....	270,000	4,090,000	31,219,000	
W. Va. ....	.....	20,000,000	8,421,000	
<b>TOTAL</b> .....	<b>\$28,094,000</b>	<b>\$169,919,000</b>	<b>\$410,325,000</b>	

## South's Contract Value at Peace High

(Continued from page 11)

not only for the current year but for a number of years to come, as there still exists a tremendous demand for new construction.

Large volumes of resource development construction such as flood control, reclamation and water power are expected, as are increased programs in the fields of hospital and school construction, as well as airport work. The latter is being stimulated by federal aid, although in some areas lack of local funds has slowed the program considerably.

Highway construction supervised by state highway departments last year, including federal aid work, probably amounted to one and one-quarter billion dollars last year, Thomas H. MacDonald, commissioner of public roads, estimated that this year's construction expenditures will be close to one billion, four-hundred-million dollars.

The supply of building materials and labor is predicted to be sufficient to carry out the eighteen billion dollar construction program for this year, as well as for seven billion dollars worth of repair and maintenance activity. James M. Ashley, president of the Producers' Council says that aside from the supply of iron and steel, no serious shortages of materials are now seen.

Iron and steel products should be as plentiful as during 1948 and millwork, which last year was troublesome, should be more readily available. Sash and door mills are catching up with back orders. Cement may remain tight, due both to expanded volume of public works and to distribution problems created by the baring point decisions. Other materials will be produced in ample quantities.

The tight labor supply may ease this year. Continuation of the large volume of construction will prevent any surplus, with the inroads of the military draft acting as an added factor against any excess. The slight reduction in some fields of construction may have the effect of retiring some of the older workers and the weeding out of some of the less competent younger ones, according to some authorities.

Total value of new construction in 1949

as forecast jointly by the Departments of Commerce and Labor will approximate \$18,750,000,000, or an increase of five per cent over the government estimate for last year. The physical volume, however, will remain at about the same level as in 1948. New private construction is seen at \$14,750,000,000; new public construction at \$5,000,000,000, the latter to be a twenty-four per cent increase.

Figures for 1949 residential construction show the number of starts at about 875,000 permanent dwelling units. Practically all of the total will be privately-

## INDUSTRIAL

(Including Private Utilities)

	December, 1948	Contracts Awarded	Contracts to be Awarded	Contracts Awarded Twelve Months 1948
Ala. ....	\$937,000	\$63,085,000	\$61,425,000	
Ark. ....	1,139,000	1,350,000	18,750,000	
D. C. ....	.....	.....	.....	
Fla. ....	481,000	430,000	13,708,000	
Ga. ....	307,000	814,000	13,475,000	
Ky. ....	5,200,000	1,020,000	21,008,000	
La. ....	8,740,000	870,000	54,453,000	
Md. ....	5,961,000	1,125,000	27,637,000	
Miss. ....	5,252,000	3,325,000	17,551,000	
Mo. ....	10,000,000	1,200,000	35,661,000	
N. C. ....	486,000	116,517,000	37,704,000	
Okla. ....	15,330,000	850,000	28,162,000	
S. C. ....	18,514,000	306,000	35,303,000	
Tenn. ....	6,016,000	11,211,000	29,181,000	
Tex. ....	45,200,000	160,626,000	149,354,000	
Va. ....	422,000	5,338,000	18,664,000	
W. Va. ....	5,000,000	1,105,000	24,477,000	
<b>TOTAL</b> .....	<b>\$134,985,000</b>	<b>\$369,175,000</b>	<b>\$587,971,000</b>	

## PUBLIC BUILDING

(City, County, State, Federal; Schools)

	December, 1948	Contracts Awarded	Contracts to be Awarded	Contracts Awarded Twelve Months 1948
Ala. ....	\$533,000	\$5,787,000	\$25,018,000	
Ark. ....	927,000	1,500,000	25,063,000	
D. C. ....	5,631,000	2,395,000	26,927,000	
Fla. ....	4,412,000	6,435,000	35,665,000	
Ga. ....	1,367,000	1,875,000	30,322,000	
Ky. ....	384,000	2,228,000	11,623,000	
La. ....	5,308,000	2,555,000	32,291,000	
Md. ....	1,467,000	57,119,000	39,501,000	
Miss. ....	1,371,000	19,071,000	28,815,000	
Mo. ....	1,964,000	3,110,000	22,910,000	
N. C. ....	2,834,000	3,899,000	34,193,000	
Okla. ....	3,680,000	8,117,000	26,994,000	
S. C. ....	770,000	736,000	14,077,000	
Tenn. ....	1,845,000	44,000,000	42,140,000	
Tex. ....	27,827,000	41,637,000	166,374,000	
Va. ....	4,065,000	5,365,000	28,030,000	
W. Va. ....	1,593,000	784,000	19,296,000	
<b>TOTAL</b> .....	<b>\$64,724,000</b>	<b>\$204,582,000</b>	<b>\$629,349,000</b>	

OFFICE PHONES: MUlberry 8775—8776. Long Distance 266

# RENTAL EQUIPMENT COMPANY

We Rent Construction Equipment of All Kinds

5515 BULWER AVE. - ST. LOUIS 7, MO.

(5600 North—One Block East of Broadway)

owned, with the number of publicly financed units placed at only 30,000, mostly in state and municipal programs and in military establishments. The 1948 volume is about 925,000 units, of which 15,000 are publicly owned.

New construction put in place in 1948, according to the Departments of Commerce and Labor, was valued at \$17,606,000,000, of which \$13,631,000,000 was for private work, and \$4,035,000,000 for public construction. The peak was August's \$1,799,000,000; the low point, the \$1,009,000,000 for February.

## Bethlehem Steel Installing Floating Dock at Beaumont

Bethlehem Steel Co. will construct a 600-foot pier at its Beaumont, Texas, yard where preparations are being made to install the four sections of a recently acquired floating dry dock which upon its engagement will be capable of lifting any vessel normally arriving at that Gulf of Mexico port.

The pier will be fitted with a 20-ton crane and all services such as water, air and power. In addition to its construction, the company will dredge a basin alongside to permit the mooring of two of the largest tankers. The floating dock was purchased from the Industrial Plants Corporation and was part of a plant at Tampa, Fla.

Completion of the project early in 1949 will place the Beaumont yard in a position to do any type of major repairs. E. C. Rehtin, manager of Bethlehem's Gulf district, in announcing the project, emphasized its importance to the locality. He believes the payroll at Beaumont will be substantially increased upon its completion.

## Overtime Pay Problem

(Continued from page 31)

premiums paid for this "clock overtime" must be included in the "regular rate" of pay and cannot be credited toward overtime pay due under the Wage and Hour Law.

Higher rates paid for "clock overtime" may be regarded as true overtime under certain conditions. Where practice or agreement calls for premium payments for hours worked before or after the employee's regular shift and also calls for overtime pay after a standard number of hours worked in a 24-hour work day beginning at the start of the employee's shift, the premium rates paid for work outside the normal shift hours would qualify as true overtime pay if the employee normally work the specified number of hours in the work day before performing the "clock overtime" work.

Premium pay for work performed on holidays must be included in the regular rate and cannot be offset against any overtime compensation due, according to Mr. Weiss, who gave the reason that the premiums for holiday work are not paid because the employee has previously worked a specified number of hours in the day or week, since holidays as a rule do not fall consistently on any fixed day of the week and even if a particular holiday may happen to fall within hours for which overtime is paid, the premium for the holiday must be included in the regular rate of pay.



**DON'T BE BOTHERED BY COLD CONCRETE**  
You can BUY or RENT torch type concrete heaters, hot water type, oil burning salamanders, boilers, etc. from E.C.A.

Air Compressors	Light Plants
Backfillers	Locomotives
Bins and Batches	Machine Tools
Blocks	Mixers
Boilers	Motors
Blowers	Pneumatic Tools
Buckets	Pumps
Cableways	Rollers
Cars	Saws
Cages	Scales
Conveyors	(Wheelbarrow)
Cranes	Screens
Crushers	Shovels
Derricks	Towers
Drillines	Trenchers
Drills	Track
Elevators	Tractors
Engines	Vibrators
Finishing	Wagons
Machines	(Crawler)
Generators	Welders
Graders	Wellpoint
Hammers	(Equipment)
Hoists	Whirleys

## PARSONS TRENCHER

PERFECT CONDITION

Model 250 Ladder Type  
Digs 12'6" Deep  
Two Sets Buckets  
Cut up to 42" Width  
Extension for Conveyor  
New 1946  
Price on Cars \$10,000

O'CONNELL & SWEENEY  
Kellogg & Tennyson Sts.  
Cincinnati, Ohio

**EQUIPMENT CORPORATION**  
of **AMERICA**

CHICAGO 12 1167 S. Washenaw Av.	PHILADELPHIA 2 1509 Race St. Schaff Bldg.
PITTSBURGH 30 P. O. Box 933-A	NEW YORK 7 30-A Church St.

### DEPENDABLE USED MACHINES

Unit full revolving shovel, \$1750  
Northwest No. 2 crane  
Morris 10 inch gravel pump  
B-G Model 522 loader  
Hughes-Keenan Roustabout crane  
Cat RD7 with bulldozer  
Butler Carcoop  
**TRACTOR & EQUIPMENT CO.**  
3508 W. 51st. St. CHICAGO 32, ILL.

### WATER PUMP FOR SALE

Practically New; 24 inch suction, 24 inch discharge; delivering 10,000 GPM at 320 RPM. Pump can be inspected at the Greenville Mfg. and Machine Works, Greenville, Miss. Interested Parties write:

**INLAND CONSTRUCTION CO.**  
Rosedale, Mississippi.

### SUPERINTENDENT WANTED

By contractor in New York area. Must be experienced in both building and heavy construction work. Immediate job is one of about three years' duration, located in the Great Lakes area, but the right man can count on continuous employment. Must have good record with reputable contractors in order to be considered for this opening.  
Address No. 9741 e/o CONSTRUCTION  
Baltimore 3, Maryland

### GRAY CONCRETE PIPE CO.

Manufacturers Plain and Reinforced  
SEWER AND CULVERT PIPE  
All sizes for all purposes

PLANTS: Thomasville, N. C., 209 Randolph St., Phone 418; Hagerstown, Md., East Jefferson St., Phone 2866; Baltimore, Md., 6315 Eastern Ave., Phone 6804way 4614; Arlington, Va., 2777 Jefferson Davis Highway, Phone Jackson 2061.

## CONSULT ALBERT!

Tabular Piling, Points, Sleeves and  
Cobol Pile Tips

Power Piping Fabrication

Supplies of Fittings and Tube Turns

Pipe, Large and Small Diameters,  
Iron and Steel,

Welded, Seamless, Corrugated

**ALBERT PIPE SUPPLY CO., INC.**  
Berry & No. 13th St., Brooklyn, N. Y.  
Phone EV-7-8106

### FOR RENT OR SALE

1—34-E Dual Drum Foote Paver, practically new.

1—Excellent Ransome Dual Drum Paver.

8—Super C Tournapulls with TLP 15 Yd. Scrapers.

Location: East Orange, New Jersey

**DRAYO-DOYLE COMPANY**

2601 Preble Avenue Pittsburgh 12, Pa.

# INDEX OF ADVERTISERS

— A —			G. M. CORP. DETROIT DIESEL ENG. DIV. . .			— OSGOOD COMPANY . . . . .			59
ALBERT PIPE SUPPLY COMPANY, INC. . . . .	69		Agency—Kudner Agency, Inc.			Agency—Howard Swink Advtg. Agency			70
ALLIS-CHALMERS TRACTORS DIV. . . . .	8, 9		GORMAN-RUPP COMPANY . . . . .	49		OWEN BUCKET COMPANY . . . . .			
Agency—Bert S. Gittins			Agency—Coleman Todd & Associates			Agency—T. H. Ball & Sons			
AMERICAN CREOSOTING COMPANY . . . . .	—		GRAY CONCRETE PIPE COMPANY . . . . .	69		— P —			
Agency—Russell T. Gray, Inc.			GRUENDLER CRUSHER & PULVERIZER CO. . .			PAGE ENGINEERING COMPANY . . . . .			—
AMERICAN ROAD BUILDERS ASSOCIATION	43		Agency—Christy Humburg Advtg. Agency			Agency—Russell T. Gray, Inc.			53
AMERICAN STEEL DREDGE CO. . . . .	64		— H —			PATENT SCAFFOLDING CO. . . . .			—
Agency—Willis S. Martin			HARNISCHFEGGER CORPORATION . . . . .	36, 37		Agency—Evans Associates Co.			64
AUSTIN-WESTERN COMPANY . . . . .	72		Agency—The Buchen Company			PENNSYLVANIA DRILLING COMPANY . . . . .			64
Agency—The Advertising Corp.			HELTZEL STEEL FORM & IRON COMPANY . .	—		Agency—Edward M. Power Co., Inc.			64
AUTOLINE OIL COMPANY . . . . .	39		Agency—Meek & Thomas, Inc.			PINE HALL BRICK & PIPE . . . . .			—
Agency—James A. Stewart Company			HENDRIX MANUFACTURING CO., INC. . .	23		— Q —			
— B —			Agency—Scollos Advtg. Agency			"QUICK-WAY" TRUCK SHOVEL COMPANY			4
BAKER MANUFACTURING COMPANY . . . . .	61		HERCULES STEEL PRODUCTS CO. . . . .	—		Agency—Shaw Advertising Agency			—
Agency—Ervin R. Abramson			Agency—Howard Swink Advtg. Agency			— R —			
BAY CITY SHOVELS, INC. . . . .	—		HERMITAGE PORTLAND CEMENT CO. . . .	14		RENTAL EQUIPMENT COMPANY . . . . .			48
Agency—Price, Hedrick & Tanner, Inc.			HUBER MANUFACTURING COMPANY . . . .	41		ROGER BROS. CORPORATION . . . . .			63
BLAW-KNOX DIVISION . . . . .	—		Agency—Jay H. Maish Company			Agency—T. H. Ball & Sons			62
Agency—Al Paul Lefton			— I —			R. P. B. CORPORATION . . . . .			—
BUCHSUS-ERIE . . . . .	24		INDEPENDENT PNEUMATIC TOOL CO. . . .	65		Agency—Brinckman & Fellows			—
Agency—Bert S. Gittins			Agency—Edgar Walter Fischer			— S —			
BUTLER BIN COMPANY . . . . .	22		INLAND CONSTRUCTION CO. . . . .	69		SALEM FOUNDRY & MACHINE WORKS . . . .			64
Agency—Davis-Greene Corporation			INSLEY MANUFACTURING COMPANY . . . .	—		SALEM TOOL CO. . . . .			—
— C —			Agency—A. L. Perkins & Co.			Agency—Meek & Thomas, Inc.			—
CATERPILLAR TRACTOR COMPANY . . . . .	6, 7		INTERNATIONAL HARVESTER CO. . . . .	20, 21		SEAMAN MOTORS, INC. . . . .			—
Agency—N. W. Aver & Son, Inc.			Agency—Aubrey, Moore & Wallace, Inc.			Agency—Davis-Greene Corporation			2
CELOTEX CORPORATION . . . . .	18		Agency—Young & Rubicam			SMITH ENGINEERING WORKS . . . . .			—
Agency—Blaine-Thompson Co., Inc.			IOWA MANUFACTURING COMPANY . . . .	62		Agency—Cramer-Kravsett Co.			—
CLEVELAND TRENCHER COMPANY . . . .	—		Agency—Russell T. Gray, Inc.			SOLVAY SALES DIVISION . . . . .			—
Agency—Gates Bourgeois			IRVINGTON FORM & TALK CO. . . . .	—		ALLIED CHEMICAL & DYE CORP. . . . .			—
CONCRETE SURFACING MACHINERY CO. . .	45		Agency—Armstrong, Schleifer & Ripin			Agency—Atherton & Currier, Inc.			64
CUMBERLAND PORTLAND CEMENT CO. . .	—		— J —			SYDNOR PUMP & WELL CO., INC. . . . .			—
Agency—George H. Hartman Co.			JAEGER MACHINE COMPANY . . . . .	65, 67		— T —			
CUMMER & SON CO., F. D. . . . .	63		Agency—Mumm, Mullay & Nichols			TAMPO MANUFACTURING COMPANY . . . .			—
— D —			— L —			Agency—Collins-Cusick-Schwerke & Wild			67
DETROIT DIESEL ENGINE DIV.—G.M. CORP.	—		LACLEDE STEEL COMPANY . . . . .	—		TENNESSEE PRODUCTS & CHEMICAL CORP.			67
Agency—Kudner Agency, Inc.			Agency—Eggers-Rankin			Agency—Robert G. Fields & Company			64
DICKEY CLAY MANUFACTURING CO., W. S.	52		LEE CO., RALPH . . . . .	66		TINNEY DRILLING CO. . . . .			69
Agency—Homer J. Buckley & Associates			LIMA SHOVEL & CRANE DIVISION . . . .	47		TRACTOR & EQUIPMENT COMPANY . . . .			—
DRAVO-DOYLE COMPANY . . . . .	69		Agency—G. M. Basford Co.			— U —			
— E —			LINK-BELT SPEEDER CORPORATION . . . .	17		UNDERPINNING & FOUNDATION CO. . . .			60
ECONOMY FORMS COMPANY . . . . .	60		Agency—Don Proctor, Advertising			UNIT CRANE & SHOVEL CORPORATION . .			12
Agency—The Blakemore Company			LITTLEFORD BROS., INC. . . . .	5		UNITED STATES RUBBER COMPANY . . . .			—
ELLCOTT MACHINE CORP. . . . .	67		Agency—Jaap-Dorr Co.			Agency—Fletcher D. Richards, Inc.			—
Agency—Van Sant, Doudelle & Co.			LUFKIN RULE CO. . . . .	57		U. S. TRACTOR CORP. . . . .			—
ELPHINSTONE, INC., D. C. . . . .	69		LULL MANUFACTURING COMPANY . . . .	—		Agency—Carr-Liggett			—
EQUIPMENT CORP. OF AMERICA . . . . .	69		— M —			UNIVERSAL FORM CLAMP CO. . . . .			—
EULOID ROAD MACHINERY CO. . . . .	71		MARION POWER SHOVEL COMPANY . . . .	15		Agency—Ross, Llewellyn, Inc.			—
Agency—Bayless-Kerr Company			Agency—Jay H. Maish Co.			— V —			
— F —			MARVEL EQUIPMENT COMPANY . . . . .	64		VIRGINIA BRIDGE COMPANY . . . . .			16
FLEX-PLANE . . . . .	—		MOTT CORE DRILLING COMPANY . . . . .	—		VIRGINIA ENGINEERING CO., INC. . . . .			44
Agency—Meek & Thomas, Inc.			— N —			— W —			
FOOTE COMPANY, INC. . . . .	62		NEW HOLLAND MFG. CO. . . . .	—		WAPPAT, INC., FRED. W. . . . .			53
Agency—Russell T. Gray, Inc.			Agency—J. Walter Thompson			Agency—W. S. Hill Co.			—
FORD MOTOR COMPANY . . . . .	—		NORTHWEST ENGINEERING COMPANY . .	3		WARNER & SWASEY . . . . .			—
Agency—J. Walter Thompson Co.			Agency—Russell T. Gray, Inc.			Agency—Griswold-Eshleman Co.			58
— G —			NO. 9741 . . . . .	69		WELLMAN ENGINEERING CO. . . . .			—
GALION IRON WORKS & MFG. CO. . . . .	—		— O —			Agency—Griswold-Eshleman Co.			65
Agency—Morgan Advertising Co.			O'CONNELL & SWEENEY . . . . .	69		WHITE MANUFACTURING COMPANY . . . .			—
GARDNER-DENVER COMPANY . . . . .	—		O.K. CLUTCH & MACHINERY CO. . . . .	55		WINCH LIFT, INC. . . . .			—
Agency—The Buchen Company			Agency—Business Service Co.			Agency—Bozell & Jacobs, Inc.			—
GARWOOD INDUSTRIES—FINDLAY DIV. . .	—		OLIVER CORPORATION, CLETRAC DIV. . .	—		— Y —			
Agency—Tri-State Advertising Co.			Agency—The Buchen Company			YAUN DRAGLINE BUCKET & MFG. CO. . .			—
Agency—Witte & Burden						Agency—Herbert S. Benjamin Associates			—
GENERAL EXCAVATOR COMPANY . . . . .	59								
Agency—Howard Swink Advertising Agency									



**CLOSING Plus**  
POWER  
WHEN AN OWEN BUCKET  
Clamps Down

It's the "Plus" features in a product that contribute largely to outstanding performance and build user satisfaction and profits.

Relax and swing an Owen from your boom. Closing Power PLUS is there when required for licking the toughest excavating jobs which will confront you.

**THE OWEN BUCKET CO. 6090 Breakwater Ave., Cleveland, O.**

BRANCHES: PHILADELPHIA • CHICAGO • BERKELEY, CALIF.



# **EUCLID EFFICIENCY**

## **SPEEDS ANOTHER TVA PROJECT**



● Nearly four million cubic yards of earth and rock will go into Watauga Dam, a TVA flood control and power project, near Elizabethton, Tennessee. The dam will have a fill structure 900 feet long and 318 feet high, with a base width of 1,275 feet.

Because of their proved efficiency and rugged staying power, "Eucs" have been widely used for construction of earth-fill dams. At Watauga 26 Bottom-Dump and 15 Rear-Dump Euclids haul earth and rock on a twenty-four hour schedule. A Euclid Loader keeps pace with the speed and efficiency of Euclid hauling equipment by providing fast mobile loading of the Bottom-Dumps.



From borrow pit to fill, "Eucs" haul big payloads at Watauga under a wide range of operating conditions. Of sturdy but simple construction, Euclid equipment gives peak performance day after day at low maintenance cost.

Several new models have been added to the Euclid line of earth moving equipment—write or phone your Euclid distributor or representative for descriptive literature and information.

**The EUCLID ROAD MACHINERY Co.**  
Cleveland 17, Ohio








### THE POWER GRADERS THAT HAVE EVERYTHING

No motor grader without All-Wheel Drive and All-Wheel Steer can hope to equal the all-around operating efficiency of an Austin-Western "88-H," "99-H" or Master "99."


All-Wheel Drive and All-Wheel Steer make it easy for an Austin-Western Power Grader to do a superlative job of bank sloping.



**Badger Convertible Shovel.** 3/4-swing design eliminates tail swing; makes it possible to use the Badger in close quarters; reduces swinging weight and definitely increases work output.



**Model "40" Motor Sweeper.** Fast, maneuverable, and economical in operation. No troublesome expensive conveyor or elevator to keep in adjustment and repair—dirt is thrown directly into the 2-yard hopper.




**3-Wheeled Rollers.** Made in sizes ranging from 6 to 12 tons. All have full length side plates for maximum rigidity; low center of gravity for smooth operation, and hydraulic power steer.



**Portable Crushing Plants.** Built in sizes and types to fit every production requirement. Equipped with matching Crushers, Screens and Conveyors, correctly balanced to deliver the maximum amount of crushed and screened aggregate in controlled sizes.



**Stationary Crushing Plants.** This limestone plant with its two Jaw Crushers and Roll Reduction Crusher is typical of the efficiency of design that characterizes every Austin-Western plant. Two men control the entire operation.



**Tandem Rollers.** Variable weight type—in 5-8 ton and 8-10½ ton sizes. Important improvements provide exceptionally smooth and steady performance on precision jobs.

**AUSTIN-WESTERN COMPANY, AURORA, ILLINOIS, U. S. A.**

